

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	08201117	Call Order: 007	Proposal: E8S87	District:08
Counties:	BROWARD			
Road Name:	Sunrise Boulevard Interchange Barrier Wall Replacement			
Limits:	86470000			
Project(s):	40610315202(*)	Federal Aid No: N/A		
Total Roadway Length:	0.824 Miles	Contract Days:	45	
Total Bridge Length:	0.000 Miles	Letting Date:	11/17/20	
Total Proposal Length:	0.824 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$150,000.00			

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to replace F-shape barrier wall on the Sunrise Interchange, Milepost (MP) 59.0, replacing existing asphalt pavement, shoulder curb and gutter, concrete barrier wall, and furnish and install guardrail with all associated components.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Thursday.

**NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.**

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in asphalt paving, it is not necessary to submit the form.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 007 Proposal: E8S87**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 MAINTENANCE SUPPORT SERVICES (MH)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	270.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	138.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	390.000
	0104- 10- 3	SEDIMENT BARRIER	LF	98.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	20.000
	0120- 6-	EMBANKMENT	CY	12.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	32.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	440.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	3.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	3.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	40.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	30.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	5.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	80.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	153.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	3.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, NEW BRIDGE OR CONCRETE BARRIER, APPROACH , TL-2	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	151.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	150.000
	E102- 1- 2	MAINTENANCE OF TRAFFIC (SITE SPECIFIC CONTRACTS)	DA	30.000