

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08210810 Call Order: 001 Proposal: E8T32-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: POND AND CANAL MAINTENANCE - ZONE 1

Limits: Midpoint

Project(s): 44336517202(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 365

Total Bridge Length: 0.000 Miles Letting Date: 08/10/21

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$350,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to perform maintenance of wet stormwater ponds, canals, and roadside ditches, at various locations on the Homestead Extension Florida's Turnpike (MP) 0.0 to 46.5; Florida's Turnpike, Milepost (MP) 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Contractor shall utilize mechanical aquatic harvesting equipment (tow boats, conveyors, work boats, amphibious vehicles, etc.) to perform much of the work.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 001 Proposal: E8T32-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ROADSIDE DITCHES-CLEAN AND RESHAPE (LF)				
	0107- 1-	LITTER REMOVAL	AC	400.000
	0120- 10- 11	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH UP TO 15'	LF	500.000
	0120- 10- 12	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH 15-30'	LF	1,000.000
	0120- 10- 13	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH GREATER THAN 30'	LF	1,000.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	500.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	5,300.000
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	30,000.000
	E106- 22- 5	REMOVAL & DISPOSAL MATERIALS	CY	30.000
	E110- 2-	CLEARING & GRUBBING	AC	40.000