

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08210112      Call Order: 005      Proposal: E8S98      District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: SEAGRAPE CLEARING & GRUBBING, DITCH & SLOPE RESTORATION

Limits: Midpoint

Project(s): 19077445212(\*)      Federal Aid No: N/A

Total Roadway Length: 0.000 Miles      Contract Days: 365

Total Bridge Length: 0.000 Miles      Letting Date: 01/12/21

Total Proposal Length: 0.000 Miles      Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals to perform 15 acres of Seagrape clearing and grubbing (grade terrain for sodding) and 30 acres of selective clearing and grubbing (remove and dispose nuisance species, trim, protect, and leave standing desirable trees, and the disposal of all vegetation and debris resulting from this process) at various locations on the Homestead Extension of Florida's Turnpike (SR 821), Milepost (MP) 12.0 to 45.0, Sawgrass Expressway (SR 869), MP 0.0 to 19.0, and Florida's Turnpike (SR 91), MP 0.0X to 82.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

**Call Order: 005 Proposal: E8S98**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 MAINTENANCE SUPPORT SERVICES (MH)</b>				
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	30.000
	E101- 1- 1	MOBILIZATION	LO	8.000
	E110- 2-	CLEARING & GRUBBING	AC	15.000