

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08210608 Call Order: 003 Proposal: E8T25-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: PAVEMENT EDGE SILT REMOVAL - MP 0 TO 100 & SAWGRASS EXPWY

Limits: Midpoint

Project(s): 44888617201(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 365

Total Bridge Length: 0.000 Miles Letting Date: 06/08/21

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform routine silt built-up removal underneath guardrail sections including restoring miscellaneous asphalt underneath guardrail and unpaved shoulder restoration next to guardrail sections, at various locations on the Homestead Extension of Florida's Turnpike, Milepost (MP) 0.0 to 46.5, Florida's Turnpike, MP 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Payment for the Shoulder Rework item includes the removal of silt build-up on paved shoulder underneath guardrails and the rework of unpaved shoulder close to those guardrail sections when directed by the Department. Blading pavement shoulder is not feasible at sites with guardrail and would require power washing or other methods to remove the silt build-up.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 003 Proposal: E8T25-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	50.000
	E575- 1-	SODDING	SY	70,000.000
	E577- 70-	SHOULDER REWORK	SY	175,000.000