

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 08210608      Call Order: 007      Proposal: E8T29      District:08

Counties: BROWARD, TURNPIKE

Road Name: ASPHALT REPAIR - SAWGRASS EXPRESSWAY - MP 16.5 TO 16.7

Limits: Midpoint

Project(s): 19077445215(\*)      Federal Aid No: N/A

Total Roadway Length: 0.000 Miles      Contract Days: 60

Total Bridge Length: 0.000 Miles      Letting Date: 06/08/21

Total Proposal Length: 0.000 Miles      Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$265,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform maintenance and repair of asphalt pavement deficiencies and defects, including replacing existing asphalt pavement, providing painted pavement markings, and raised pavement markers, at various locations on the Sawgrass Expressway (SR 869), from MP 16.5 to 16.7.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Friday Morning.

**NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.**

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Asphalt Paving and Pavement Marking. The Experience in Asphalt Paving Form (850-070-01) and the Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in asphalt paving and pavement marking, it is not necessary to submit the form.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 007 Proposal: E8T29**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 MAINTENANCE SUPPORT SERVICES (MH)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	400.000
	0102- 60-	WORK ZONE SIGN	ED	400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,480.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	600.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	68.000
	0102-115-	TYPE III BARRICADE	ED	80.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	40.000
	0104- 10- 3	SEDIMENT BARRIER	LF	657.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	1.060
	0107- 2-	MOWING	AC	0.810
	0120- 6-	EMBANKMENT	CY	112.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	2,220.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	1,260.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	210.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	220.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	185.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	95.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.210
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,150.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	383.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.420
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.840
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.420
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.420
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.840
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.420
	E102- 1- 2	MAINTENANCE OF TRAFFIC (SITE SPECIFIC CONTRACTS)	DA	40.000
	E110- 2-	CLEARING & GRUBBING	AC	0.250