

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08210511      Call Order: 001      Proposal: E8T13-R0      District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: PAVEMENT MARKINGS - ZONE 1

Limits: Midpoint

Project(s): 40585037202(\*)

Federal Aid No: N/A

Total Roadway Length: 0.000 Miles      Contract Days: 365

Total Bridge Length: 0.000 Miles      Letting Date: 05/11/21

Total Proposal Length: 0.000 Miles      Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$480,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings at various locations on Homestead Extension of Florida's Turnpike (SR 821), Milepost (MP) 0.0 to 46.5; Florida's Turnpike (SR 91), MP 0.0X to 100.0, and Sawgrass Expressway (SR 869), MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through 5:00 AM Friday.

**NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.**

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E8T13-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)</b>				
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD,BLACK, SKIP, 6"	GM	10.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.500
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	500.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,000.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	200.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	30.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	40.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	30.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	80.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	30.000
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	2.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,000.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	320.000