

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08221213	Call Order: 007	Proposal: E8U22	District:08
Counties:	MIAMI-DADE			
Road Name:	PAVEMENT MARKING - HEFT			
Limits:	87471000			
Project(s):	41505155201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.063 Miles	Contract Days:	75	
Total Bridge Length:	0.000 Miles	Letting Date:	12/13/22	
Total Proposal Length:	3.063 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$300,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings at various locations on the Homestead Extension of Florida's Turnpike (SR 821), from North of SW 40th Street (Bird Road) to SR 836 (Dolphin Expressway) and SR 90 (Tamiami Trail) from SW 122nd Ave. to East of Snapper Creek Canal Road.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 007 Proposal: E8U22

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,500.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	7.600
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	2.125
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	600.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,500.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	900.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.575
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	59.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	135.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	300.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.060
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	21.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	21.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	9.200
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	4.400
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	21.400
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	2.750
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	9.100
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.200
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.800
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.425
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.170
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.600
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.250
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	100.000