

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08221213 Call Order: 008 Proposal: E8U23 District:08

Counties: SEMINOLE, TURNPIKE

Road Name: WATERING ON SEMINOLE EXPRESSWAY - MP 38 TO 55

Limits: Midpoint

Project(s): 19077445226(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 90

Total Bridge Length: 0.000 Miles Letting Date: 12/13/22

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$25,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide watering at the newly installed sodded areas, at various locations on the SR417 / Seminole Expressway MM 38 - MM 55.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

Watering Frequency- Watering shall be performed three times per week. This shall be done at ½ inch, or 13,577 gallons per acre. The total area of the newly installed sodded area(s) is approximately 9,000 SY (1.9 Acres).

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 008 Proposal: E8U23

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	930.000