

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08220614	Call Order: 004	Proposal: E8T91	District:08
Counties:	MIAMI-DADE			
Road Name:	PAVEMENT MARKINGS - HEFT - MP 18.0 TO MP 27.0			
Limits:	87471000			
Project(s):	44388225202(*)	Federal Aid No: N/A		
Total Roadway Length:	14.000 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	06/14/22	
Total Proposal Length:	14.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$325,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings, milling and resurfacing at various locations on the Homestead Extension of Florida's Turnpike Managed lanes (SR 821), from Milepost (MP) 18.0 to (MP) 27.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E8T91

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	182.000
	0102- 60-	WORK ZONE SIGN	ED	282.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,606.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	42.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	30.000
	0102-115-	TYPE III BARRICADE	ED	4.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	28.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	28.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	2,500.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	100.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	160.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	10,970.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.351
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	16.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.030
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.080
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.150
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	384.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	158.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	16.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	20.320
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0711- 15-171	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	1.890
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.150
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.830
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.090