

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08220614	Call Order: 009	Proposal: E8T92	District:08
Counties:	MIAMI-DADE			
Road Name:	SIGNING IMPROVEMENTS - HEFT - MP 20 TO 27			
Limits:	87471000			
Project(s):	44388225201(*)	Federal Aid No: N/A		
Total Roadway Length:	14.000 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	06/14/22	
Total Proposal Length:	14.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$335,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide highway signing improvements such as installation of signs panels, removal of fiber optic cable and electrical service wire at various locations on the Homestead Extension of Florida's Turnpike (SR 821), Milepost (MP) 20.0 to 27.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Overhead Signs. The Experience in Overhead Signs Form (850-070-03) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in overhead signs, it is not necessary to submit the form.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 009 Proposal: E8T92

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	578.000
	0102- 60-	WORK ZONE SIGN	ED	946.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,076.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	64.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	58.000
	0102-115-	TYPE III BARRICADE	ED	88.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	66.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	46.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	4,030.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	1,342.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	4.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	8.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	12.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	9.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	12.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	2.000