

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08220308	Call Order:	005	Proposal:	E8T72	District:	08
Counties:	HERNANDO, HILLSBOROUGH, PASCO, POLK, TURNPIKE						
Road Name:	THERMOPLASTIC PAVEMENT MARKINGS - ZONE 4						
Limits:	08470000						
Project(s):	43661915203(*)	Federal Aid No:	N/A				
Total Roadway Length:	17.731 Miles	Contract Days:	365				
Total Bridge Length:	0.000 Miles	Letting Date:	03/08/22				
Total Proposal Length:	17.731 Miles	Contract Execution Days:	10				
		Special Start Date:	N/A				
		Aquis/Flexible Start Time:	14				
Proposal Budget Estimate:	\$150,000.00						

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings at various locations on the Polk Parkway (SR 570), Veterans Spur (SR 589), Veterans Expressway/Suncoast Parkway (SR 589).

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 005 Proposal: E8T72

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	275.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	300.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	475.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.015
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	40.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	7,800.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	8.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.100
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.500
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.600
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	1.700
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	300.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	90.000
	E710- 17-	REMOVAL OF NON-CONFLICTING PAINT/LONGLINE STRIPE PRIOR TO REFURBISH	SF	50.000