

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08220308 Call Order: 008 Proposal: E8T75 District:08

Counties: HERNANDO

Road Name: RESURFACE SUNCOAST (SR 589) IN HERNANDO COUNTY, MP 44.5-55.2

Limits: 08470000

Project(s): 44591315201(*) Federal Aid No: N/A

Total Roadway Length:	21.418 Miles	Contract Days:	115
Total Bridge Length:	0.000 Miles	Letting Date:	03/08/22
Total Proposal Length:	21.418 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$4,142,378.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for milling and resurfacing of the friction course, replacement of pavement markings and other incidental construction along the Suncoast Parkway (SR 589) from MP 44.500 to MP 55.200 in Hernando County. No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans.

Call Order: 008 Proposal: E8T75

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44591315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44591315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	774.000
	0102- 60-	WORK ZONE SIGN	ED	7,686.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	26,612.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	234.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	340.000
	0102-115-	TYPE III BARRICADE	ED	316.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	230.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	230.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.216
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.215
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.216
	0104- 10- 3	SEDIMENT BARRIER	LF	1,190.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	150.000
	0107- 1-	LITTER REMOVAL	AC	2,769.740
	0107- 2-	MOWING	AC	2,614.640
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	299,175.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	16,005.900
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,101.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	18.762
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	18.177

Call Order: 008 Proposal: E8T75

ALT	Item	Description	Unit	Quantity
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	19.041
	0999- 16-	PARTNERING, DO NOT BID (44591315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44591315201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,101.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44591315201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.216
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,516.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	3,389.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	18.762
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.140
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	18.177
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	19.041
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.216
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.190
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.216
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.190