

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08220510 Call Order: 001 Proposal: E8T84 District:08

Counties: MIAMI-DADE

Road Name: RAMP IMPROVEMENTS - HEFT - MP 17.4 TO MP 17.9

Limits: 87471000

Project(s): 40609675201(*) Federal Aid No: N/A

Total Roadway Length:	0.100 Miles	Contract Days:	75
Total Bridge Length:	0.000 Miles	Letting Date:	05/10/22
Total Proposal Length:	0.100 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$336,000.00

Please read the full advertisement

Description: THIS IS A RE-ADVERTISEMENT.

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform ramp improvements for the SR 821/SR 873 Interchange consisting of lengthening the ramp gap acceptance between the South Bound (SB) SR 821 Express Ramp with the SB SR 874 Express Ramp including milling and resurfacing, miscellaneous asphalt pavement and barrier wall improvements on the Homestead Extension Florida's Turnpike (SR 821), Milepost (MP) 17.4 to 17.9.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Friday Morning.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving and Pavement Markings. The Experience in Asphalt Paving Form (850-070-01) and the Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Hot Plant Bituminous Course, and Pavement Marking it is not necessary to submit the forms.

Call Order: 001 Proposal: E8T84

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,930.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	40.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	425.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,960.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	320.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	187.000
	0102-115-	TYPE III BARRICADE	ED	550.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	200.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	2.230
	0107- 2-	MOWING	AC	0.790

Call Order: 001 Proposal: E8T84

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	140.000
	0120- 6-	EMBANKMENT	CY	150.000
	0160- 4-	TYPE B STABILIZATION	SY	119.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	416.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	70.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	208.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	98.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	6,381.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	29.400
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	70.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	265.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	7.900
	0521- 72- 60	SHOULDER CONCRETE BARRIER, 38" WALL SHIELDING BARRIER	LF	300.000
	0544- 2- 1	CRASH CUSHION, TL-2, NARROW	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.033
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	540.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	703.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.100
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.127
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.190
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.100
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.380
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.290
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.230
	E110- 2-	CLEARING & GRUBBING	AC	0.270