Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 08220913 Call Order: 002 Proposal: E8T96-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: RAMP ASPHALT MAINTENANCE - ZONE 1

Limits: Midpoint

Project(s): 44888717202(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 365

Total Bridge Length: 0.000 Miles Letting Date: 09/13/22

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A
Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform maintenance and repair of ramp asphalt pavement, including replacing existing asphalt pavement, providing thermoplastic pavement markings, and raised pavement markers, at various locations on the Homestead Extension of Florida's Turnpike, Milepost (MP) 0.0 to 46.5, Florida's Turnpike, MP 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Friday Morning.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving and Pavement Markings. The Experience in Asphalt Paving Form (850-070-01) and the Experience in Pavement Markings Form (850-070-06) must be filled out and submitted to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Hot Plant Mix Bituminous Course, and Pavement Marking it is not necessary to submit the forms.

Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

		Call Order: 002 Proposal: E8T96-R0		
ALT	Item	Description	Unit	Quantity
Section	on 0001 ASPHALT	REPAIR (MECHANICAL) (TN)		
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	18,000.000
	0337- 7-82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	1,030.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	800.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	400.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	750.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	120.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.000
	E101- 1- 1	MOBILIZATION	LO	4.000
	E102- 1- 3	MAINTENANCE OF TRAFFIC (SITE SPECIFIC)	LO	4.000