

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 08230822                      Call Order: 002      Proposal: E8U56                      District:08

Counties:      TURNPIKE

Road Name:      DMS UPGRADE AND RETROFIT ON SR589 - DYNAMIC MESSAGE SIGN

Limits:      10470000

Project(s): 44942325201(\*)

Federal Aid No: N/A

Total Roadway Length:	0.014 Miles	Contract Days:	240
Total Bridge Length:	0.000 Miles	Letting Date:	08/22/23
Total Proposal Length:	0.014 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate:                      \$1,805,759.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for the replacement of Front Access and Walk-In Dynamic Message Signs (DMS) and associated infrastructure along the Veterans Expressway (SR 589) from MP 2.3 to MP 8.4 in Hillsborough County, Florida. No Pre-Bid Conference. Contractor must be prequalified.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E8U56**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44942325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44942325201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	208.000
	0102- 60-	WORK ZONE SIGN	ED	1,549.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,649.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	46.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	190.000
	0102-115-	TYPE III BARRICADE	ED	40.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	63.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	42.000
	0104- 10- 3	SEDIMENT BARRIER	LF	179.000
	0999- 16-	PARTNERING, DO NOT BID (44942325201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44942325201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 8-136	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- W/UPS, FULL COLOR, 101-200 SF	EA	1.000
	0700- 8-600	FRONT ACCESS DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	6.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	6.000
<b>Section 0003 Intelligent Transportation System</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.346
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	18.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,828.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	240.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	8,550.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	4,089.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	120.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	10.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	10.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	240.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	8,286.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	4,089.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0639- 6-131	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 11-15 KVA, SINGLE PHASE, COPPER WINDINGS	EA	8.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	8.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	22.000