

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 08231212 Call Order: 003 Proposal: E8U89-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: DRAINAGE MAINTENANCE - HEFT & MP 0 TO 73 - ZONE I

Limits:

Project(s): 19276317213

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

365

Total Bridge Length:

0.000 Miles

Letting Date:

12/12/23

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

14

Proposal Budget Estimate:

\$525,000.00

Please read the full advertisement

Description:

The work specified in this Contract consists of providing all labor, materials, equipment, and all incidentals necessary to perform maintenance, repair, and restoration of the drainage systems, pipes, inlets, and storm water management facilities at various locations on the Florida's Turnpike in Miami-Dade, Broward, and Palm Beach Counties.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRAC.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E8U89-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 SODDING (SY)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	50.000
	0120- 1-	REGULAR EXCAVATION	CY	500.000
	0120- 6-	EMBANKMENT	CY	50.000
	0160- 4-	TYPE B STABILIZATION	SY	50.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	10.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	1.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	1.000
	0425- 78-	INLET CAP, PRECAST	EA	1.000
	0425- 82-	REPLACE GRATE	EA	5.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	25.000
	0430-173-124	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 24", GUTTER DRAIN	LF	25.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	50.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	1.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	25.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	20.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	500.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E103- 3- 1	TEMPORARY WORK STRUCTURE, HYDRAULIC PUMP SERVICES	ED	5.000
	E110- 2-	CLEARING & GRUBBING	AC	2.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	750.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	5.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	10.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	5.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	200.000
	E425- 73- 6	SECURE MANHOLE / INLET LIDS	EA	1.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	1.000
	E425- 73- 8	MANHOLE COVER	EA	1.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	10,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	50.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	50.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	50.000
	E431- 1- 11	PIPE LINER, SPRAY APPLICATION,0-24"	LF	25.000
	E431- 1- 12	PIPE LINER, SPRAY APPLICATION,25-36"	LF	25.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	100.000
	E575- 1-	SODDING	SY	110.000