

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08230608	Call Order: 001	Proposal: E8U06	District:08
Counties:	TURNPIKE			
Road Name:	REHAB OF AGING CONCRETE PILES (SR 91)			
Limits:	91470000			
Project(s):	44262295201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.900 Miles	Contract Days:	283	
Total Bridge Length:	0.217 Miles	Letting Date:	06/08/23	
Total Proposal Length:	1.117 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90	
Proposal Budget Estimate:	\$5,696,695.00			

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for rehabilitation of aging prestressed concrete piles along SR 91 by installing pile jackets including cathodic protection systems, installation of articulated concrete block, and working from barges in St. Lucie, Okeechobee and Osceola counties at various bridge locations from MP 142.200 to MP 192.420. No Pre-Bid Conference. Contractor must be prequalified.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E8U06

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	1.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	2.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	5.000
	0457- 1- 21	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, UP TO 16"	LF	753.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	1,061.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44262295201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44262295201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	336.000
	0102- 60-	WORK ZONE SIGN	ED	6,792.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,980.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	566.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	650.000
	0102-115-	TYPE III BARRICADE	ED	1,132.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,132.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,132.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,690.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,067.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	251.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	10.000
	0110- 1- 1	CLEARING & GRUBBING (44262295201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	324.000
	0120- 6-	EMBANKMENT	CY	916.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	36.000
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	2,188.000
	0530- 4- 9	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 9"	SY	2,078.000
	0999- 16-	PARTNERING, DO NOT BID (44262295201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44262295201)	LS	1.000