

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08230314      Call Order: 003      Proposal: E8U13-R0      District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: CABLE BARRIER MAINTENANCE - ZONE 1

Limits: Midpoint

Project(s): 19286717219(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	03/14/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform cable safety barrier maintenance in accordance with the manufacturer's recommendations including the removal, annual inspection and repair, and/or the replacement of damaged or destroyed sections with all associated components at various locations on the Homestead Extension of Florida's Turnpike (SR 821) MP 0.0 to 47 and Florida's Turnpike (SR 91) MP 0.0 to 100.0.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

**Call Order: 003 Proposal: E8U13-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 GUARDRAIL REPAIR (LF)</b>				
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	55.000
	E540- 0- 0	CABLE BARRIER INSPECTION	LS	1.000
	E540- 0- 22	PRE-STRETCHED GALVANIZED WIRE ROPE, INC INCIDENTALS TURNBUCKLES, TESTING AND RETENTIONING	LF	10,000.000
	E540- 0- 24	CABLE BARRIER TRANS TERMN POST REPAIR, INC INCIDENTALS FOUNDATION, POST, SOCKET, PINS, ETC	EA	5.000
	E540- 0- 25	END ANCHOR REPAIR/REPLACE INCLUDES ALL INCIDENTALS FOUNDATION, GATING END TERMINALS & ASSOC HARDWARE	EA	6.000
	E540- 0- 26	CABLE BARRIER HAIRPIN AND LOCKPLATE ASSEMBLY	EA	450.000
	E540- 3- 1	GIBALTAR TL 3 LINE POST REP INCL HAIRPIN & LOCKPLATE	EA	120.000
	E540- 3- 1	GIBALTAR TL 3 LINE POST REP >4 INCL HAIRPIN & LOCKPLATE	EA	300.000
	E540- 3- 2	GIBALTAR TERMINAL POST REP (INCL 1, 2, 3 & 4)	EA	25.000
	E540- 3- 3	GIBALTAR ANCHOR POST REPLACEMENT	EA	5.000