

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08230321 Call Order: 001 Proposal: E8U04 District:08

Counties: BROWARD

Road Name: RESURFACE TPK (SR91) IN BROWARD COUNTY

Limits: 86470000

Project(s): 44602415201(*) Federal Aid No: N/A

Project(s): 44602425201 Federal Aid No: N/A

Project(s): 44602425202 Federal Aid No: N/A

Total Roadway Length:	34.116 Miles	Contract Days:	386
Total Bridge Length:	0.158 Miles	Letting Date:	03/21/23
Total Proposal Length:	34.274 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$17,705,091.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for providing improvements to drainage, signing and pavement markings, structures, ITS, widen the auxiliary lane from Eastbound SR 869 (Sawgrass Expressway) to Southbound SR 91, and to mill and resurface SR 91 (Floridas Turnpike) and the interchange ramps from MP 65.2 (Pompano Beach Service Plaza) to MP 71.0 (North of Wiles Road) in Broward County (86470-000). No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44602425201 BRIDGE ID 860590)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	0.300
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	66.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	1,054.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	396.500
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44602415201)	LS	1.000
	0101- 1-	MOBILIZATION (44602425201)	LS	1.000
	0101- 1-	MOBILIZATION (44602425202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44602415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44602425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44602425202)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44602415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44602425202)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,864.000
	0102- 60-	WORK ZONE SIGN	ED	21,224.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	13,191.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,885.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	2,455.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	305.000

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	800.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	87,240.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,638.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	7.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,097.000
	0102- 99-106	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY- SMART WORK ZONE, PROJECT 446024-1-52-01	ED	16,885.000
	0102-115-	TYPE III BARRICADE	ED	150.000
	0102-125-106	PORTABLE TRAFFIC SENSOR- SMART WORK ZONE, PROJECT 446024-1-52-01	ED	2,046.000
	0102-126-106	NAVIGATION APPLICATION SENSOR- SMART WORK ZONE, PROJECT 446024-1-52-01	ED	1,364.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,364.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,364.000
	0104- 10- 3	SEDIMENT BARRIER	LF	23,949.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	89.000
	0107- 1-	LITTER REMOVAL	AC	3,316.740
	0107- 2-	MOWING	AC	2,900.110
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44602415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44602415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44602425201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44602425202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	347.000
	0120- 1-	REGULAR EXCAVATION	CY	3,336.800
	0120- 6-	EMBANKMENT	CY	4,534.300
	0160- 4-	TYPE B STABILIZATION	SY	11,483.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	6,402.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,976.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,260.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	1,394.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	4,569.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	34,395.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	99,210.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	13,693.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	250,272.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	14,641.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	5,365.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	2,641.000
	0327- 70- 26	MILLING EXISTING ASPHALT PAVEMENT, 4 3/4" AVG DEPTH	SY	1,267.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	13,627.900
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	141.300
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	256.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2,321.800
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	21,730.700

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	11,435.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,549.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1,420.300
	0425- 71-	INLETS RELOCATING	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	7.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-612-033	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 30"	EA	1.000
	0430-613-123	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,15"PIPE	EA	4.000
	0430-963- 2	PVC PIPE FOR BACK OF SIDEWALK, NON STANDARD DIAMETER	LF	72.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	842.000
	0521- 72- 44	SHOULDER CONCRETE BARRIER, 44" PIER PROTECTION BARRIER/CRASH WALL	LF	267.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	682.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	22,839.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	23.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, TRAILING	EA	5.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	6.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	18,600.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	21.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	15.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	18.658
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	95,158.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	605.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,370.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	14.388
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.022
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.057
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	452.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,112.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	255.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	25.253

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.311
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	21.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.608
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,725.000
	0999- 16-	PARTNERING, DO NOT BID (44602415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44602415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44602425201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44602425202)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	82.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	40.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	4.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	3.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	5.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	15.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	6.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	2.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	4.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	2.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	3.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	6.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	3.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	6.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	11.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	6.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	4.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	3.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	7.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	1.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	3.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	3.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	1.000

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
	0700- 11-232	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT-SOLAR POWER, SPEED FEEDBACK, 12-20 SF	AS	2.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	1.000
	0700- 12- 60	SIGN BEACON, REMOVE BEACON- SIGN TO REMAIN	AS	2.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	1.622
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	0.917
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	475.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,968.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44602415201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.057
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	304.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,965.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	255.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	21.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	13.728
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.852
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	23.923
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.311
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	13.948
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.405
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.199
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.203
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.076
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.182
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,693.000
Section 0004 Intelligent Transportation System				
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	9.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	2.400
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	282.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,943.000
	0630- 3- 1	REPLACE ROUTE MARKER FOR EXISTING CONDUIT	EA	145.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	2,035.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	14,740.000

Call Order: 001 Proposal: E8U04

ALT	Item	Description	Unit	Quantity
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	13,615.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	282.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	5.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	34.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	50.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	3.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	4.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	386.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	3.000
	0635- 2-118	PULL & SPLICE BOX, F&I, HS-20 FOR TPE, 54" X 54"	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	653.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000