

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08231114 Call Order: 002 Proposal: E8U85 District:08

Counties: MIAMI-DADE

Road Name: DOPHIN STADIUM LIGHTING INTERCHANGE

Limits: 87470001

Project(s): 44106745201(*) Federal Aid No: N/A

Total Roadway Length:	2.511 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	11/14/23
Total Proposal Length:	2.511 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to furnish and install light poles and lighting systems in accordance with the manufacturer's recommendations including the removal and disposal of existing luminaires and all associated components at the Dolphin Stadium Interchange of Florida's Turnpike (SR 91) milepost 2X in Miami-Dade County.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 002 Proposal: E8U85

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	72.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	462.000
	0102- 62- 12	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-012	ED	58.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,928.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	60.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	48.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	72.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,743.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	22.000
	0107- 1-	LITTER REMOVAL	AC	78.930
	0107- 2-	MOWING	AC	5.120
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	16.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	2.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	16.000
	0570- 1- 1	PERFORMANCE TURF	SY	72.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.000

Call Order: 002 Proposal: E8U85

ALT	Item	Description	Unit	Quantity
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	526.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,278.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	360.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	34.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID)	LS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	29,302.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	165.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	15,805.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	16.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	18.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	3.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	17.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	37.000