

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08240409      Call Order: 001      Proposal: E8U45      District:08

Counties: BROWARD

Road Name: WIDEN SAWGRASS (SR869) ATLANTIC BLVD TO SAMPLE RD

Limits: 86472000

Project(s): 43546115201(\*)      Federal Aid No: N/A

Total Roadway Length:	4.690 Miles	Contract Days:	1204
Total Bridge Length:	0.081 Miles	Letting Date:	04/09/24
Total Proposal Length:	4.771 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$112,395,057.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for the construction of roadway reconstruction, widening, milling and resurfacing, widening of Bridge Nos. 860490 and 860491 over Sample Rd, widening of Bridge No. 860492 over Canal 5, stormwater enhancements, stormwater ponds, Sample Road interchange reconstruction and lighting, signing, pavement marking, traffic signals and Intelligent Transportation System (ITS) improvements on of SR 869, Sawgrass Expressway in Broward County from MP 8.968 to MP 12.007. No Pre-Bid Conference. Contractor must be prequalified.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546115201 BRIDGE 860490)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546115201 BRIDGE 860491)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546115201 BRIDGE 860492)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	234.600
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	165.800
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	295.300
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	188.400
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	46.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	1,214.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	8.400
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	10.800
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	134,788.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	80,559.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	27,588.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	956.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	916.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0455- 34-400	PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, SIZE 18"	LF	1,924.000
	0455-113- 24	AUGER CAST PILE FOR BRIDGES, 24" DIAMETER	LF	984.000
	0455-119-103	LOAD TEST-STATIC, COMPRESSION,101-600 TONS	EA	1.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	358.000
	0455-148-	THERMAL INTEGRITY TESTING FOR AUGER CAST PILES	EA	16.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	731.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	225.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	132.800
	0460- 2- 1	STRUCT STEEL, CARBON (43546115201 BRIDGE ID 860492)	LS	1.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	538.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	850.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	19.200
	0530- 74-	BEDDING STONE	TN	60.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	2,100.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	16.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43546115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43546115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43546115201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43546115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,992.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	51,532.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,946.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	27,895.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	35,330.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	4,392.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	74,571.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	71,270.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	84,070.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	6,020.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	52.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7,650.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	578.000
	0102-115-	TYPE III BARRICADE	ED	10,396.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	9,632.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	7,224.000
	0104- 10- 3	SEDIMENT BARRIER	LF	26,873.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	223.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	272.000
	0107- 1-	LITTER REMOVAL	AC	3,130.550
	0107- 2-	MOWING	AC	2,085.100

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43546115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43546115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43546115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	506.000
	0110- 21-	TREE PROTECTION BARRIER	LF	1,162.000
	0120- 1-	REGULAR EXCAVATION	CY	123,943.300
	0120- 4-	SUBSOIL EXCAVATION	CY	39,675.000
	0120- 6-	EMBANKMENT	CY	99,132.100
	0160- 4-	TYPE B STABILIZATION	SY	230,708.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	10,841.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	93,484.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	10,588.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	120,894.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,503.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	10,715.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	4,105.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	689.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	8,343.000
	0327- 70- 9	MILLING EXISTING ASPHALT PAVEMENT, 5 1/4" AVG DEPTH	SY	1,609.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	114,088.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	8,586.600
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,243.400
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	17,368.500
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	98.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,485.600
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	19,136.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	9,656.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	822.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	484.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	821.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	660.000
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	1,901.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	108,555.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	5.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	3.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	2.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	62.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	2.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	33.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	2.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	28.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	14.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	5.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	527.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	35.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	28.000
	0430-174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	12.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	9,288.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	4,780.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	28.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	105.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	16.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	60.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	1,540.000
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	2,792.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	333.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	450.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-200	STRAIGHT CONCRETE ENDWALLS, 36", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-610-025	U-ENDWALL, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	1.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	3.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	205.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	32.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	25.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	6.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	2.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	527.000
	0451- 70-	PREST SOIL ANCHORS	EA	441.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	44.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	23.000
	0455- 35- 6	STEEL PILING, HP 14 X 89	LF	961.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0455- 35- 11	STEEL PILING, HP 12 X 74	LF	1,332.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	109,407.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43546115201)	LS	1.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	48.900
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,605.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,364.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	8,623.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	7,821.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	3,407.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	195.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	468.000
	0521- 72- 41	SHOULDER CONCRETE BARRIER, RETAINING SECTION	LF	4,146.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	430.000
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	41,170.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	28,602.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	38.000
	0536- 73-	GUARDRAIL REMOVAL	LF	53,009.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	20.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	12.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	11.400
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	3,867.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATMT	LF	24,730.000
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	255,014.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	7,667.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	28,917.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	41.146
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.911
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,695.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	121.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	29.817
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.234
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	35.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	58.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	27.368
	0922-102- 2	SMART WORK ZONE, PORTABLE CHANGEABLE MESSAGE SIGN	ED	10,134.000
	0922-102- 5	SMART WORK ZONE, VARIABLE SPEED LIMIT SIGN WITH ELECTRONIC SPEED FEEDBACK SIGN	ED	1,750.000
	0922-102- 6	SMART WORK ZONE, VEHICLE DETECTOR	ED	8,844.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0922-102- 8	SMART WORK ZONE, CENTRAL PROCESSOR	ED	4,204.000
	0922-102- 9	SMART WORK ZONE, LOCATION DEVICE	ED	7,322.000
	0999- 16-	PARTNERING, DO NOT BID (43546115201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	13.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43546115201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	18.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	15.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	46.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	4.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	15.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	5.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	5.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	5.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	3.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	2.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	4.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	1.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	6.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	1.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	1.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 10-115	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	18.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	10.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	101.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,405.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43546115201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,362.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	235.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.170
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	39.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	18,030.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	3.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.970
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.615
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	13.426
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.551
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.904
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.125
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.590
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.591
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.009
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.102
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.203
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.102
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.203
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,607.000
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	35,295.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,419.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	484.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	7,776.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	310.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	248.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	12.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	19.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,452.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	96,003.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	123,654.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	300.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	37,746.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	12.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	8.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	217.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	222.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	201.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	26.000
<b>Section 0005 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	186.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	816.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	23.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	2,940.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	3.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	3.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	3.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000



**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0684- 6- 11	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET ACCESS POINT	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
<b>Section 0006 Intelligent Transportation System</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.039
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	18.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	34,247.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,300.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	140.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	8,217.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	36,035.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	31,530.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	626.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	504.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	17.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	59.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	19.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	1,247.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	83.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	9.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	17.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	36,395.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	30,980.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	20.000
	0639- 6-112	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, ALUMINUM WINDINGS	EA	19.000
	0639- 6-122	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, ALUMINUM WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	5.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	14.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	10.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	4.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	2.000

**Call Order: 001 Proposal: E8U45**

ALT	Item	Description	Unit	Quantity
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	19.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	19.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	17.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	1.000
	0676- 2-600	ITS CABINET- REMOVE	EA	2.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	5.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	19.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	19.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	19.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	19.000