

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08240213 Call Order: 001 Proposal: E8U69 District:08

Counties: PALM BEACH

Road Name: WEST PALM BEACH SERVICE PLAZA PARKING IMP

Limits: 93470000

Project(s): 44262515201(*) Federal Aid No: N/A

Total Roadway Length:	1.183 Miles	Contract Days:	772
Total Bridge Length:	0.000 Miles	Letting Date:	02/13/24
Total Proposal Length:	1.183 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90

Proposal Budget Estimate: \$37,764,911.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for a new centralized concrete truck parking lot and an expanded passenger car parking at the West Palm Beach Service Plaza (MP94) in Palm Beach County. Pavement widening on SR 91 northbound adjacent to the service plaza and reconstruction of northbound ramps is included in the Contract. Additional work includes relocation and reconstruction of utility services, roadway and parking lot lighting, signing and pavement markings, drainage and stormwater management system, and ITS infrastructure. No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44262515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44262515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44262515201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44262515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	567.000
	0102- 60-	WORK ZONE SIGN	ED	11,004.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	1,060.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,139.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	4,716.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	3,019.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,493.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	5,305.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	4,070.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	83,429.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	89,001.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	110.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,750.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	772.000
	0102-115-	TYPE III BARRICADE	ED	990.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,502.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,077.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	88.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	72.000
	0107- 1-	LITTER REMOVAL	AC	1,070.810
	0107- 2-	MOWING	AC	721.630
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44262515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44262515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44262515201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.420
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,833.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44262515201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	50,638.200
	0120- 4-	SUBSOIL EXCAVATION	CY	3,943.500
	0120- 6-	EMBANKMENT	CY	43,562.600
	0120- 6-107	EMBANKMENT, SPECIFIED A-3 SOIL	CY	889.800
	0120- 72-	GRAVEL FILL	CY	1,150.800
	0160- 4-	TYPE B STABILIZATION	SY	77,887.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	37,104.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	891.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	7,550.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	8,415.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	21,641.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,024.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	1,252.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	34,266.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	177.600
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	3,519.200
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,540.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	750.100
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	5,306.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	2,295.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	773.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	52.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	232.500
	0350- 3- 6	PLAIN CEMENT CONCRETE PAVEMENT, 8.5"	SY	610.000
	0350- 3- 9	PLAIN CEMENT CONCRETE PAVEMENT, 10"	SY	34,263.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	45,711.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	7.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	4.000
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	7.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	6.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-571	INLETS, DITCH BOTTOM, TYPE G, <10'	EA	6.000
	0425- 1-572	INLETS, DITCH BOTTOM, TYPE G, >10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	5.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	2.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	8.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	4.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	24.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	3,866.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2,128.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	561.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	688.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	353.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	275.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	336.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	558.600
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0431- 1-112	PIPE LINER, CURED IN PLACE, 12"	LF	328.000
	0431- 1-115	PIPE LINER, CURED IN PLACE, 15"	LF	299.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	195.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	104.000
	0432- 3- 1	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 15"	EA	7.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	2,486.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	165.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	11,626.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	158.000
	0520- 4-	CURB-CONCRETE PAVEMENT JOINT	LF	5,508.000
	0520- 5- 51	TRAF SEP CONC, TYPE V, 4' WIDE	LF	30.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	588.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	171.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	1,646.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,239.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	68.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	815.000
	0527- 2-	DETECTABLE WARNINGS	SF	194.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	3,525.800
	0530- 74-	BEDDING STONE	TN	1,301.500
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	25.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	5,508.000
	0536- 73-	GUARDRAIL REMOVAL	LF	3,854.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	7.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	385.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	525.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	232.000
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	43,259.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	110.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	60.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.657
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.044
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.506
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.426
	0750- 1- 19	ARCHITECTURAL, BUILDING, NEW, OTHER BUILDING (44262515201)	LS	1.000
	0750- 1- 60	ARCHITECTURAL, BUILDING, REMOVE (44262515201)	LS	1.000
	0751- 2-	ARCHITECTURAL - ELECTRICAL/POWER (44262515201)	LS	1.000
	0751- 11-610	ARCHITECTURAL- SPECIAL, REMOVE & RELOCATE	EA	2.000
	0751- 46- 11	WINDSHIELD WASH STATION, FURNISH & INSTALL, STATION ASSEMBLY	EA	2.000
	0751- 46- 12	WINDSHIELD WASH STATION, FURNISH & INSTALL, WATER LINE	LF	845.000
	0999- 16-	PARTNERING, DO NOT BID (44262515201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	8.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44262515201)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.520
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	76.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	23.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	9.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	115.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	10.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	5.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	10.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	31.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	6.000
	0701- 17-101	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	0.009
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	709.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	31.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	30.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.015
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	5,006.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	83.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	38.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,071.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	33.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	398.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.931
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.745
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.973
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.820
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.110
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.163
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.090
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.635

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.783
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.564
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.084
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.139
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.188
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.143
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	11,255.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,623.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	120.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	88,058.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 19- 63	HIGH MAST LIGHT POLE, DEEP FOUNDATION REMOVAL	EA	8.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	38.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	19.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	32.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	82.000
	0715-510-130	LIGHT POLE- SPECIAL DESIGN, F&I NEW POLE ON EXISTING FOUNDATION, ALUMINUM, 30'	EA	3.000
	0715-516-330	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 30'	EA	12.000
	0715-516-350	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 50'	EA	9.000
Section 0004 Landscape / Peripheral				
	0581- 1- 1	RELOCATE TREES AND PALMS, PALM, <14' OF CLEAR TRUNK	EA	220.000
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	41.000
Section 0005 Utilities				
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44262515201)	LS	1.000
	0639- 5- 51	EMERGENCY GENERATOR-PERMANENT, RELOCATE	EA	1.000
	0751- 11-600	ARCHITECTURAL- SPECIAL, REMOVE	EA	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	741.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	1,115.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	1,805.000
	1050- 18-002	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 2- 4.9"	LF	228.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	294.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	574.000
	1050- 31-201	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 1.5"	LF	714.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	825.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	200.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	1050- 31-210	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	346.000
	1050- 51-206	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"	LF	475.000
	1050- 51-208	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 8"	LF	1,864.000
	1050- 61-116	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 16"	LF	48.000
	1055- 51-108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 8"	EA	23.000
	1055- 51-408	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 8"	EA	12.000
	1060- 11-222	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, 6.1 - 12'	EA	2.000
	1060- 16-	UTILITY STRUCTURE, BELOW GROUND, REMOVE&DISPOSE CONTRACTOR TAKES OWNERSHIP	EA	1.000
	1080- 21-101	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 1.5"	EA	2.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	10.000
	1080- 22-101	UTILITY FIXTURE- BACKFLOW ASSEMBLY, FURNISH & INSTALL,1"	EA	2.000
	1080- 23-102	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 2	EA	3.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8	EA	1.000
	1080- 24-101	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 1.5"	EA	4.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	4.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	4.000
	1080- 26-101	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 1"	EA	1.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	1.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	40.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	115.000
	1501- 1-	LIFT STATION, SANITARY SEWER	EA	1.000
	1644-133- 08	FIRE HYDRANT, F&I, TRAFFIC, 2 HOSE, 1PUMPER, 6"	EA	1.000
	1644-900-	FIRE HYDRANT, REMOVE	EA	1.000
Section 0006 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.620
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	13.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,297.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,817.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	255.000
	0630- 2-100	CONDUIT, RELOCATE CONDUIT WITH FIBER/WIRE REMAINING OPERATIONAL	LF	25.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	941.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	9,582.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	674.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	8,346.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	518.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	1.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	41.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	468.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	10.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	40.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	2.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	772.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	26.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	18.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4,135.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	5,136.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	17.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	2.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	3.000
	0639- 6-201	ELECTRICAL POWER SERVICE- TRANSFORMER, REPLACE, <25 KVA, COPPER WINDINGS	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	3.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	3.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	2.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	3.000
	0641- 3-700	CONCRETE CCTV POLE, SHALLOW POLE REMOVAL	EA	2.000
	0646- 2-600	ALUMINUM POLE- INDEX 695-001, REMOVE	EA	2.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	2.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	2.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	3.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	2.000
	0676- 2-600	ITS CABINET- REMOVE	EA	2.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	5.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	2.000

Call Order: 001 Proposal: E8U69

ALT	Item	Description	Unit	Quantity
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	5.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	5.000
	0700- 8-500	FRONT ACCESS DYNAMIC MESSAGE SIGN, RELOCATE	EA	1.000
	0700- 10-400	DMS SUPPORT STRUCTURE, RELOCATE	EA	1.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	1.000