

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08240213 Call Order: 006 Proposal: E8U71 District:08

Counties: BROWARD

Road Name: - BRIDGE REHABILITATION

Limits: 86470000

Project(s): 41592755201(*)

Federal Aid No: N/A

Total Roadway Length: 0.047 Miles Contract Days: 181

Total Bridge Length: 0.047 Miles Letting Date: 02/13/24

Total Proposal Length: 0.094 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 60

Proposal Budget Estimate: \$6,100,889.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for strengthening the existing beams of Bridge No. 860184 along SR 91 over the Hillsboro Canal in Broward County at MP 73.1. In addition to the beam strengthening, the outside traffic railing barriers will be upgraded with a rectangular tube retrofit.

No Pre-Bid Conference. Contractor must be prequalified.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: E8U71

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	0.100
	0450- 82-	BEAM REPAIR	LF	2,483.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	488.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (41592755201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41592755201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (41592755201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (41592755201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	990.000
	0102- 60-	WORK ZONE SIGN	ED	1,869.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	1,641.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,845.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	183.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	127.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	198.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	198.000
	0104- 10- 3	SEDIMENT BARRIER	LF	150.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	441.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	102.830
	0107- 2-	MOWING	AC	83.460
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	2,634.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	144.900
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.523
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,461.000
	0999- 16-	PARTNERING, DO NOT BID (41592755201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41592755201)	LS	1.000