

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08240621      Call Order: 001      Proposal: E8U76      District:08

Counties: PALM BEACH

Road Name: WIDEN TPK(SR91) WPB SERVICE PLAZA TO SOUTHERN BLVD

Limits: 93470000

Project(s): 40614355201(\*)      Federal Aid No: N/A

Project(s): 40614355601      Federal Aid No: N/A

Total Roadway Length:	15.580 Miles	Contract Days:	1759
Total Bridge Length:	0.282 Miles	Letting Date:	06/21/24
Total Proposal Length:	15.862 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$263,516,170.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for roadway widening, reconstruction, milling, resurfacing, bridge improvements/replacements, toll site construction, lighting, signing, pavement markings, drainage, signalization and Intelligent Transportation System (ITS) construction on the Turnpike Mainline (SR 91) from MP 93.901 to MP 98.734 in Palm Beach County. This project also includes 406143-5-56-01, Utility Work by Highway Contractor (UWHC) for Palm Beach County Water Utilities Department.

No Pre-Bid Conference. Contractor must be prequalified.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614355201 BRIDGE ID 930447)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614355201 BRIDGE ID 930565)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614355201 BRIDGE ID 931004)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614355201 BRIDGE ID 934971)	LS	1.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	64.900
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	124.400
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	4,658.400
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	479.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	1,016.700
	0400- 2- 25	CONCRETE CLASS II, MASS, BRIDGE SUBSTRUCTURE	CY	518.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	820.000
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	1,233.900
	0400- 7- 1	BRIDGE DECK GROOVING	SY	13,050.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0400- 9- 1	BRIDGE DECK PLANING	SY	10,133.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	40,815.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	121.200
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	78.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	1,141,325.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	720,260.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	189,838.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	2,148.000
	0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	3,665.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	6,788.000
	0450- 2- 78	PREST BEAMS: FLORIDA-I BEAM 78"	LF	2,812.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	16,325.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	2,080.000
	0455- 34-400	PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, SIZE 18"	LF	4,550.000
	0455- 35-117	STEEL PILING, 14" DIA. PIPE	LF	21,480.000
	0455- 35-118	STEEL PILING, 14" DIA. PIPE WITH 100% DYNAMIC LOAD TESTING	LF	735.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	2,020.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	190.000
	0455-144-102	TEST PILES - STEEL, 14" DIA PIPE	LF	1,447.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	1,743.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	312.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	1,090.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	649.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	2,750.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	721.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	3,851.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	3,130.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	1,172.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,605.800
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	6,270.000
	0530- 74-	BEDDING STONE	TN	831.500
	0550- 10-343	FENCING, TYPE R, 7.1-8.0, W/FULL ENCLOSURE	LF	962.000
	0550- 10-363	FENCING, TYPE R, GREATER THAN 10.0', WITH FULL ENCLOSURE	LF	2,168.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	15,885.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	53.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (40614355201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40614355201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (40614355201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,200.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (40614355201)	LS	1.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	82,594.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	23,054.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	28,615.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	44,869.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	39,304.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	47,266.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	722,110.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	8,292.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	1,392.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,616.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	49.000
	0102- 94- 1	TEMPORARY GLARE SCREEN, F&I, WALL MATERIAL-CONCRETE	LF	1,476.000
	0102- 94- 11	GLARE SCREEN, TEMPORARY, RELOCATE, WALL MATERIAL-CONCRETE	LF	864.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	11,378.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	250.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,049.000
	0102-115-	TYPE III BARRICADE	ED	7,964.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	3,554.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	3,554.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.815
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	2.130
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.902
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	640.000
	0104- 6-	TEMPORARY SLOPE DRAIN / RUNOFF CONTROL STRUCTURE	LF	59.000
	0104- 7-	SEDIMENT BASIN / CONTAINMENT SYSTEM	EA	3.000
	0104- 9-	SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	3.000
	0104- 10- 3	SEDIMENT BARRIER	LF	52,975.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	17,520.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	8.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	120.000
	0107- 1-	LITTER REMOVAL	AC	7,238.780
	0107- 2-	MOWING	AC	5,890.470
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (40614355201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (40614355201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (40614355201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.470
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	14,779.000
	0110- 21-	TREE PROTECTION BARRIER	LF	3,518.000
	0110- 23-	TREE REMOVAL	EA	14.000
	0120- 1-	REGULAR EXCAVATION	CY	311,293.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0120- 1-901	REGULAR EXCAVATION, CONTAMINATED GROUNDWATER ENCOUNTER (40614355201)	LS	1.000
	0120- 4-	SUBSOIL EXCAVATION	CY	2,982.000
	0120- 5-	CHANNEL EXCAVATION	CY	67,910.000
	0120- 6-	EMBANKMENT	CY	352,360.800
	0120- 72-	GRAVEL FILL	CY	51,653.000
	0121- 70-	FLOWABLE FILL	CY	16.000
	0160- 4-	TYPE B STABILIZATION	SY	393,387.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,156.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	117,252.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	10,016.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	258,977.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	102,912.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	86,257.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	15,985.300
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	671.500
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	42,885.400
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	40,312.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	15,955.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	4,517.400
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	4,177.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	903.900
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	112.500
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	1,579.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	284,403.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	21.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	3.000
	0425- 1-412	INLETS, CURB, TYPE J-1, >10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	8.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	8.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	3.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	2.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	5.000
	0425- 1-553	INLETS, DT BOT, TYPE E, J BOT, <10'	EA	6.000
	0425- 1-559	INLETS, DT BOT, TYPE E, MODIFY	EA	2.000
	0425- 1-571	INLETS, DITCH BOTTOM, TYPE G, <10'	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	4.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	11.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	1.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	6.000
	0425- 1-713	INLETS, GUTTER, TYPE V, J BOT, <10'	EA	1.000
	0425- 1-783	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10'	EA	12.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0425- 1-784	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, >10'	EA	2.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	2.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	44.000
	0425- 1-794	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, >10'	EA	12.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	48.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	2.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	16.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	10.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	8.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	3.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	4.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	19.000
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	246.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	147.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	11,617.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	6,749.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	5,997.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	5,509.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	5,438.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	3,379.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	2,126.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	334.000
	0430-185-142	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 42", STORM AND CROSS DRAIN	LF	195.000
	0430-185-148	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 48", STORM AND CROSS DRAIN	LF	635.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	3.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-548-100	STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-554-100	STRAIGHT CONCRETE ENDWALLS, 54", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-572-100	STRAIGHT CONCRETE ENDWALLS, 72", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-611-333	U-ENDWALL, BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 30"PIPE	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	91.500
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	12.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	3.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	6.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	3.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0451- 70-	PREST SOIL ANCHORS	EA	16.000
	0455- 87-	ANCHOR BAR, STEEL	EA	112.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	61,183.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	21,147.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	111.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	1,196.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	273.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	9,094.000
	0520- 2- 10	CONCRETE CURB, TOLL HEADER CURB	LF	800.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	475.000
	0520- 5- 46	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	LF	493.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	2,986.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	12,311.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	6,200.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	687.000
	0521- 1-121	MEDIAN CONC BARRIER, TOLL SITE, D521-005 SCHEME 7	LF	800.000
	0521- 6- 31	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	LF	1,833.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	1,532.000
	0521- 8- 11	CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL	LF	5,674.000
	0521- 72- 24	SHOULDER CONCRETE BARRIER WALL, 8' NOISE WALL	LF	998.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	7,851.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	11,362.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4,961.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	22.000
	0527- 2-	DETECTABLE WARNINGS	SF	9.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	54,777.900
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	10,636.100
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	181.000
	0530- 74-	BEDDING STONE	TN	17,611.200
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	3,796.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	13,097.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	2,696.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	42.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	73.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	5.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	10.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	13.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	16,912.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	17.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	17.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	14.970
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	201,426.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	10,788.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	6,380.000
	0550- 10-325	FENCING, TYPE R, 5.1-6.0', VERTICAL	LF	2,239.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	136,433.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	15,887.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	400.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	165.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	25,697.000
	0635- 2-121	PULL & SPLICE BOX, F&I,TOLL SITE, 30" x 48"	EA	16.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	122.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (40614355201)	LS	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	21.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	21.000
	0735- 88- 1	TOLL PLAZA MODIFY EXISTING, LOCATION 1 (40614355201)	LS	1.000
	0735- 88- 2	TOLL PLAZA MODIFY EXISTING, LOCATION 2 (40614355201)	LS	1.000
	0904-540- 11	HIGH TENSION CABLE BARRIER SYSTEM - REMOVE	LF	18,870.000
	0904-540- 13	HIGH TENSION CABLE BARRIER SYSTEM - LENGTH OF NEED SEGMENT	LF	3,706.000
	0904-540- 14	HIGH TENSION CABLE BARRIER SYSTEM - END TERMINAL	EA	4.000
	0904-540- 15	HIGH TENSION CABLE BARRIER SYSTEM, END TERMINAL FOUNDATION- MISCELLANEOUS DRILLED SHAFT	CY	170.000
	0919-528-100	DIRECTIONAL INDICATORS	SF	62.000
	0922-102- 1	SMART WORK ZONE, ARROW BOARD	ED	1,777.000
	0922-102- 2	SMART WORK ZONE, PORTABLE CHANGEABLE MESSAGE SIGN	ED	1,777.000
	0999- 16-	PARTNERING, DO NOT BID (40614355201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	18.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40614355201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (40614355601)	LS	1.000
	1050- 16-001	UTILITY PIPE,REMOVE & DISPOSE, 0 - 1.9"	LF	1,836.000
<b>Section 0003 Signing</b>				
	0523- 3-	PATTERNED PAVEMENT	SY	152.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	32.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	25.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	7.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	18.000
	0700- 1-213	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 20.1-30.0 SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	69.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	2.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	5.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	21.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	10.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	9.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	8.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	3.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	6.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	5.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	4.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	2.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	2.000
	0700- 7-500	EMBEDDED DYNAMIC MESSAGE SIGN, RELOCATE	EA	2.000
	0700- 10-115	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 10-117	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	9.000



**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-132	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, 12-20 SF OF STATIC SIGN PANELS	EA	1.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	76.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	35,752.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	66.238
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	3.857
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.138
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,512.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,464.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	895.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	68.341
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.686
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	4.881
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	52.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	192.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	50.741
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	320.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.937
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	18.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	18.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40614355201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	3.034
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.138
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,512.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,464.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	673.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.938
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	128.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	320.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.351
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,093.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	22.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	18.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	17.248
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	43.787
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	14.807
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.686
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	4,280.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.902
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.016
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.719
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.016
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	25,224.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,673.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	1,091.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	91.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	6.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	173.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	443.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	51,017.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	5,400.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	147,327.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,804.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	22.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	3.000
	0715- 11-225	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE, ROADWAY, WALL MOUNT	EA	16.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	16.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0715- 19- 62	HIGH MAST LIGHT POLE, SHALLOW FOUNDATION REMOVAL	EA	8.000
	0715- 52- 40	LIGHTING-SPECIAL, LIGHT POLE COMPLETE, F&I, MEDIAN BARRIER MOUNT, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	119.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	31.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	7.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	1.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	7.000
	0715- 62-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	1.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	8.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	26.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	40.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	126.000
<b>Section 0005 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	105.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	565.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	14.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	20.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	20.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	5.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	14.000
	0660- 4- 41	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE CABINET EQUIPMENT	EA	1.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
<b>Section 0006 Utilities</b>				
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	65.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	8,796.000
	1050- 51-206	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"	LF	15.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	1.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	2.000
	1644-113- 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 6"	EA	1.000
	1644-900-	FIRE HYDRANT, REMOVE	EA	1.000
<b>Section 0007 Intelligent Transportation System</b>				
	0102-112-	EXISTING ITS MAINTENANCE	DA	1,759.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.900
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	3.000
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	21.000
	0611- 2- 3	ITSFM LOCATION DOCUMENTATION- COMMUNICATIONS BUILDING	EA	4.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	36,884.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,157.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,374.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	944.000
	0633- 1-112	FIBER OPTIC CABLE, F&I, OVERHEAD,13-48 FIBERS	LF	107.000
	0633- 1-114	FIBER OPTIC CABLE, F&I, OVERHEAD,97-144 FIBERS	LF	1,044.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,434.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	26,188.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	5,323.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	109,298.000
	0633- 1-410	FIBER OPTIC CABLE, RELOCATE, OVERHEAD	LF	914.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	702.000
	0633- 1-610	FIBER OPTIC CABLE, REMOVE, OVERHEAD	LF	107.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	118,244.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	2,992.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	24.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	36.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	204.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	324.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	13.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	28.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	28.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	7.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	1,759.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	479.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	700.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	118.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	48.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	3.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	2.000
	0635- 2- 15	PULL & SPLICE BOX, F&I, 30" X 48" COVER SIZE	EA	4.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	2.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	13.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	25,758.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	26,758.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	23.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	10.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	5.000
	0639- 6-131	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 11-15 KVA, SINGLE PHASE, COPPER WINDINGS	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	10.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	5.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	11.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	5.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	2.000
	0641- 3-180	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 80'	EA	1.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	1.000
	0646- 2-600	ALUMINUM POLE- INDEX 695-001, REMOVE	EA	6.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	3.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0660- 6-421	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, CABINET EQUIPMENT	EA	2.000
	0660- 6-422	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, ABOVE GROUND EQUIPMENT	EA	2.000

**Call Order: 001 Proposal: E8U76**

ALT	Item	Description	Unit	Quantity
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	2.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	20.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	20.000
	0660- 8- 41	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, RELOCATE, CABINET EQUIPMENT	EA	4.000
	0660- 8- 42	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	4.000
	0660- 8- 51	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, ADJUST/MODIFY, CABINET EQUIPMENT	EA	6.000
	0660- 8- 52	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, ADJUST/MODIFY, ABOVE GROUND EQUIPMENT	EA	6.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	9.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	2.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	6.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	1.000
	0676- 2-600	ITS CABINET- REMOVE	EA	4.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	9.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	13.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	20.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	13.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	13.000
	0688- 2- 40	CITIZENS BAND RADIO ADVISORY SYSTEM- CBRAS. RELOCATE	EA	1.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	1.000
	0700- 9-500	WALK-IN DYNAMIC MESSAGE SIGN, RELOCATE	EA	1.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	1.000