

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08240510 Call Order: 001 Proposal: E8U74 District:08

Counties: BROWARD

Road Name: TSM&O ADD AUX LANES TO S TPK(SR91) IN BROWARD CNTY, MP 47-54

Limits: 86470000

Project(s): 44622315201(*) Federal Aid No: N/A

Project(s): 44622415201 Federal Aid No: N/A

Total Roadway Length:	14.000 Miles	Contract Days:	1693
Total Bridge Length:	0.000 Miles	Letting Date:	05/10/24
Total Proposal Length:	14.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$267,114,819.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for widening approximately seven miles of Florida's Turnpike mainline from six lanes to eight lanes by adding an auxiliary lane in each direction in Broward County from State Road 821 (milepost 47) to Griffin Road (milepost 54).

This project also includes improvements along Hollywood Blvd/Pines Blvd and Griffin Road. The proposed work includes drainage improvements, noise walls, signing and pavement markings, lighting, signalization, ITS, and landscaping. The summary of pay items for this project is listed in the plans.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44622315201)	LS	1.000
	0101- 1-	MOBILIZATION (44622415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44622315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44622415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44622315201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44622315201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44622415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,361.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (44622315201)	LS	1.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (44622415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	192,693.000
	0102- 62- 12	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-012	ED	5,256.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	33,979.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	315.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	72,957.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	19,106.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	49,663.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	6,313.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,038,075.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	8,409.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	3,857.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	44.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	16,396.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	6,772.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	6,772.000
	0102-115-	TYPE III BARRICADE	ED	10,040.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	604.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	604.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	1.125
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.028
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	1.125
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.734
	0104- 10- 3	SEDIMENT BARRIER	LF	47,756.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	9,806.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	848.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	6.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	330.000
	0107- 1-	LITTER REMOVAL	AC	10,855.040
	0107- 2-	MOWING	AC	7,509.520
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44622315201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44622415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44622315201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44622415201)	LS	1.000
	0108- 3-	MONITOR EXISTING STRUCTURES- GROUNDWATER MONITORING (44622415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44622315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44622415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	11,678.000
	0110- 21-	TREE PROTECTION BARRIER	LF	10,351.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	39.000
	0110- 73-	REMOVE EXISTING BULKHEAD	LF	20.000
	0120- 1-	REGULAR EXCAVATION	CY	100,065.200
	0120- 4-	SUBSOIL EXCAVATION	CY	41,394.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0120- 5-	CHANNEL EXCAVATION	CY	2,669.600
	0120- 6-	EMBANKMENT	CY	251,121.600
	0160- 4-	TYPE B STABILIZATION	SY	176,981.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	898.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	49,796.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	8,383.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,378.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	35,560.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	57,624.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	577.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	14,711.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	14,662.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,391.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	22,263.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	185,731.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	5,160.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	3,781.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	131,428.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	1,965.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	8,875.700
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,505.400
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	26,738.600
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,015.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	3,719.600
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	45,330.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	16,149.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	82.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,196.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	608.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2,397.700
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	228.800
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	10,818.500
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	1.500
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	20.300
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	20.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	34.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	99.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	1,813,198.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	889.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	4.000
	0425- 1-475	INLETS, CURB, TYPE 7, PARTIAL	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	1.000
	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	10.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	20.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-559	INLETS, DT BOT, TYPE E, MODIFY	EA	2.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	9.000
	0425- 1-585	INLETS, DT BOT, TYPE H, PARTIAL	EA	1.000
	0425- 1-611	INLETS, DITCH BOTTOM, TYPE K, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	84.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	2.000
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	5.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	5.000
	0425- 1-783	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10'	EA	97.000
	0425- 1-785	INLETS, MEDIAN BARRIER, TYPE 1, PARTIAL	EA	10.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	21.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	11.000
	0425- 1-925	INLETS, ADJACENT BARRIER, PARTIAL	EA	4.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	7.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	16.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	12.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	13.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	3.000
	0425- 2- 75	MANHOLES, J-7, >10' CONTROL STRUCTURE	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	8.000
	0425- 4-	INLETS, ADJUST	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	8.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	7.000
	0425- 6-	VALVE BOXES, ADJUST	EA	18.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	214.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	202.000
	0430-173-115	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 15", GUTTER DRAIN	LF	148.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	446.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	38.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	6,625.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	8,897.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2,986.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	20.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	4.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	1,508.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	2,846.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	1,253.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	123.000
	0430-175-166	PIPE CULVERT, OPT MATERIAL, ROUND, 66"S/CD	LF	4,840.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	342.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	180.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	194.000
	0430-185-154	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 54", STORM AND CROSS DRAIN	LF	670.000
	0430-185-166	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 66" , STORM AND CROSS DRAIN	LF	648.000
	0430-548-100	STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-554-100	STRAIGHT CONCRETE ENDWALLS, 54", SINGLE, 0 DEGREES, ROUND	EA	4.000
	0430-610-325	U-ENDWALL, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	5.000
	0430-613-123	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,15"PIPE	EA	1.000
	0430-613-125	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,18"PIPE	EA	5.000
	0430-613-323	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:2 SLOPE,15"PIPE	EA	1.000
	0430-613-325	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:2 SLOPE,18"PIPE	EA	10.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	208.700
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	566.600
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	5.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	47.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	2.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	2.000
	0430-982-144	MITERED END SECTION, OPTIONAL ROUND, 66" CD	EA	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0431- 1-115	PIPE LINER, CURED IN PLACE, 15"	LF	764.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	559.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	285.000
	0431- 1-130	PIPE LINER, CURED IN PLACE, 30"	LF	253.000
	0431- 1-154	PIPE LINER, CURED IN PLACE, 54"	LF	396.000
	0455- 35-116	STEEL PILING, HP 18 X 204	LF	221.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	127,816.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (44622415201)	LS	1.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	1,946.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	19.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	269.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,266.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	255.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	81.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	14,097.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	50.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	1,920.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	2,764.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	6,426.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	1,401.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	2,561.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	6,269.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	1,249.000
	0521- 72- 44	SHOULDER CONCRETE BARRIER, 44" PIER PROTECTION BARRIER/CRASH WALL	LF	314.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	1,340.000
	0521- 72- 60	SHOULDER CONCRETE BARRIER, 38" WALL SHIELDING BARRIER	LF	773.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	251.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	59.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	280.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	1,849.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	1,132.000
	0524- 3-	CONC CORE DITCH BLOCKS	CY	9.000
	0527- 2-	DETECTABLE WARNINGS	SF	145.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	124.100
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	709,072.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	66.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	44,936.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	8.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	15.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	20.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	2.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	5.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	59,532.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	32.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	9.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	25.184
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	55,494.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	20,868.000
	0550- 10-231	FENCING, TYPE B, 6.1-7.0, W/ BARB WIRE ATTMT	LF	15,707.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	437,299.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	6,399.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 2-120	ALUMINUM POLE- INDEX 695-001, FURNISH & INSTALL, 20'	EA	1.000
	0646- 2-400	ALUMINUM POLE- INDEX 695-001, RELOCATE	EA	1.000
	0695- 3- 11	TRAFFIC MONITORING SITE SPEED/CLASSIFICATION UNIT, FURNISH- & INSTALL, VOLUME SPEED AND CLASSIFICATION	AS	2.000
	0695- 5- 1	TRAFFIC MONITORING SITE SOLAR POWER UNIT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0695- 7-133	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, POLE MOUNT	EA	2.000
	0695- 8- 11	TRAFFIC MONITORING SITE COMMUNICATIONS MODEM FURNISH & INSTALL	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	10,606.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	64.788
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.782
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	1.992
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,829.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	8,298.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,532.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	97.284
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.628
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	71.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	157.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	55.481
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.139
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	1.261
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	2,394.000
	0922-102- 1	SMART WORK ZONE, ARROW BOARD	ED	3,098.000
	0922-102- 2	SMART WORK ZONE, PORTABLE CHANGEABLE MESSAGE SIGN	ED	13,500.000
	0922-102- 3	SMART WORK ZONE, VARIABLE SPEED LIMIT SIGN	ED	3,448.000
	0922-102- 6	SMART WORK ZONE, VEHICLE DETECTOR	ED	16,985.000
	0922-102- 9	SMART WORK ZONE, LOCATION DEVICE	ED	3,922.000
	0999- 16-	PARTNERING, DO NOT BID (44622315201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	17.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44622315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44622415201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	51.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	43.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	8.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	90.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	6.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	6.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	8.000
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	22.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	1.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	13.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	12.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	7.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	3.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	9.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	7.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	4.000
	0700- 3-611	SIGN PANEL, REMOVE, 601 SF AND GREATER	EA	3.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	5.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	1.000
	0700- 3-631	SIGN PANEL, REMOVE PANEL, 601 SF AND GREATER WITH LIGHTING	EA	1.000
	0700- 4-111	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, UP TO 20 FT	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	1.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	4.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	1.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	3.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	4.000
	0700- 4-621	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, SPAN	EA	1.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	16.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	6.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	4.000
	0701- 17-101	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	0.250
	0701- 17-201	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6"	GM	0.250
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	187.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	22,178.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	83.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44622315201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44622415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.625
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,548.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,721.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,099.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.350
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	36.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	106.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	500.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,549.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	21.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	19.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	14.576
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.370

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	39.401
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	14.696
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.793
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.180
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.406
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.580
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.346
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.712
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.336
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.643
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	6,433.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	66,509.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,847.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	100.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	4,067.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	26,052.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	446.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	30.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	48.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	4.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	30.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	15,403.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	278,576.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	52,112.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	196,987.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	352.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	364,568.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	11.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	6.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	50.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	25.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	41.000
	0715- 19- 51	HIGH MAST LIGHT POLE, REPLACE HPS LIGHT FIXTURE ON EXISTING POLE	EA	4.000
	0715- 19- 63	HIGH MAST LIGHT POLE, DEEP FOUNDATION REMOVAL	EA	2.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	31.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	6.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	272.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	315.000
	0715- 69-001	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	7.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	317.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	81.000
	0715-510-150	LIGHT POLE- SPECIAL DESIGN, F&I NEW POLE ON EXISTING FOUNDATION, ALUMINUM, 50'	EA	11.000
	0715-516-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, 50'	EA	42.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	223.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,406.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	250.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	5.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	35.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	3,230.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	3,730.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	208.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	24.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	3.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	3.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	41.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	2.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	465.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	6.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	5.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	3.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	25.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	4.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	9.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	7.000
Section 0005 Landscape / Peripheral				
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	29.000
Section 0006 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	7.200
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	24.000
	0611- 2- 3	ITSFM LOCATION DOCUMENTATION- COMMUNICATIONS BUILDING	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	31,838.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,985.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	855.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	5,745.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	41,313.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	35,388.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	628.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	336.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	23.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	73.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	288.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	11.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	12.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	12.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	3,518.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	79.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	56.000
	0635- 2-118	PULL & SPLICE BOX, F&I, HS-20 FOR TPE, 54" X 54"	EA	13.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	1.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	8.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	25,641.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	6,120.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	17.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	11.000
	0639- 6-112	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, ALUMINUM WINDINGS	EA	8.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	7.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	3.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	1.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	2.000
	0641- 3-180	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 80'	EA	6.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	5.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	9.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	9.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	3.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	15.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	15.000
	0676- 2-121	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336, 24" W X 36" H X 20" D	EA	2.000

Call Order: 001 Proposal: E8U74

ALT	Item	Description	Unit	Quantity
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	16.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-600	ITS CABINET- REMOVE	EA	1.000
	0676- 3- 30	SMALL EQUIPMENT ENCLOSURE, INSTALL, >10" W x 13" H x 11" D	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	8.000
	0682- 1-153	ITS CCTV CAMERA, F&I, STATIONARY, IP, HIGH DEFINITION	EA	1.000
	0682- 1-600	ITS CCTV CAMERA, REMOVE & DISPOSAL	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	23.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	16.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	20.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	20.000
	0700- 9-237	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITHOUT UPS, FULL COLOR, 201-300 SF	EA	1.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000