



**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	248.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	1,152.600
	0400- 2- 25	CONCRETE CLASS II, MASS, BRIDGE SUBSTRUCTURE	CY	87.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	694.100
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	985.800
	0400- 7- 1	BRIDGE DECK GROOVING	SY	10,932.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	9,929.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	14,081.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	6,155.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	97.800
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	57.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	4,419.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	51,551.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	770,628.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	405,815.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	237,180.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,114.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	2,320.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	2,008.000
	0450- 2- 78	PREST BEAMS: FLORIDA-I BEAM 78"	LF	3,334.000
	0451- 70-	PREST SOIL ANCHORS	EA	65.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	1,172.000
	0455- 17-124	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 24"	EA	29.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	268.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2,925.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	21,425.000
	0455-108-112	STEEL CASING FOR FUTURE PILE, 42"	LF	110.000
	0455-115-	PILE REDRIVE	EA	113.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	101,865.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	26,349.000
	0455-133- 10	SOLDIER PILE WALL, TEMPORARY-CRITICAL, STEEL H-PILES WITH TIMBER LAGGING	SF	1,656.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	268.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	29.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE, 18" SQ	LF	170.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE, 24" SQ	LF	2,945.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	926.000
	0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	LF	230.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	1,830.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (43619415201 BRIDGE ID 924230)	LS	1.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (43619415201 BRIDGE ID 924231)	LS	1.000
	0460- 2- 20	STRUCT STEEL - NEW/WIDENING, WEATHERING (43619415201 BRIDGE ID 924230)	LS	1.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0460- 2- 20	STRUCT STEEL - NEW/WIDENING, WEATHERING (43619415201 BRIDGE ID 924231)	LS	1.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	80.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	305.000
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	635.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	130.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	5,200.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,841.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	904.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	93.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,684.000
	0530- 74-	BEDDING STONE	TN	956.000
	0550- 10-333	FENCING, TYPE R, 6.1-7.0, W/FULL ENCLOSURE	LF	292.000
	0550- 10-353	FENCING, TYPE R, 8.1 - 10.0', WITH FULL ENCLOSURE	LF	2,184.000
	0560- 1-101	COATING NEW STRUCTURAL STEEL- HIGH PERFORMANCE COATING SYSTEM (43519415201 BRIDGE ID 924231)	LS	1.000
	0560- 1-101	COATING NEW STRUCTURAL STEEL- HIGH PERFORMANCE COATING SYSTEM (43619415201 BRIDGE ID 924230)	LS	1.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	16,516.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	212.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43619415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43619415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43619415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43619415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	9,024.000
	0102- 60-	WORK ZONE SIGN	ED	95,356.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	1,063.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	9,667.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	100,686.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	6,988.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	8,119.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	133,723.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	1,731.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	517,957.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	32,164.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	700.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	56.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	9,268.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	4,044.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	4,044.000
	0102-115-	TYPE III BARRICADE	ED	9,097.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	9,548.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	9,008.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	38,595.000
	0104- 10- 3	SEDIMENT BARRIER	LF	68,088.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,079.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	15.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	600.000
	0107- 1-	LITTER REMOVAL	AC	14,629.240
	0107- 2-	MOWING	AC	14,629.240
	0110- 1- 1	CLEARING & GRUBBING (43619415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.060
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	170.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	11,559.000
	0110- 23-	TREE REMOVAL	EA	10.000
	0120- 1-	REGULAR EXCAVATION	CY	980,903.900
	0120- 4-	SUBSOIL EXCAVATION	CY	37,465.900
	0120- 6-	EMBANKMENT	CY	1,261,801.700
	0160- 4-	TYPE B STABILIZATION	SY	558,403.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	12,134.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	5,918.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	126,307.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	2,294.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	32,324.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	10,822.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	321,592.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	13,205.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	13,573.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	11,721.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	23,940.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	3,187.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	11,488.500
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,673.600
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	37,813.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	375.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,631.200
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	52,464.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	14,222.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	342.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	3,986.200
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	2,500.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2,493.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	223.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	912.600
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	53.600

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	236.300
	0400- 45- 5	REINFORCED CONCRETE, TOLL SITE EQUIPMENT SLAB, 12" THICK	SY	116.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	29,425.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	4.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	304.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	170,458.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	20,714.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	22.000
	0425- 1-312	INLETS, CURB TYPE P-1, >10'	EA	4.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 1-522	INLETS, DT BOT, TYPE C,>10'	EA	3.000
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	1.000
	0425- 1-524	INLETS, DT BOT, TYPE C, JBOT, >10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	7.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	9.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	131.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	8.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	47.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	34.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	4.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, <=10'	EA	72.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	31.000
	0425- 1-794	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, >10'	EA	2.000
	0425- 1-881	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10'	EA	18.000
	0425- 1-882	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, >10'	EA	3.000
	0425- 1-883	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, J BOT<10'	EA	8.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	63.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	16.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	6.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	3.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	23.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	11.000
	0425- 2- 75	MANHOLES, J-7, >10' CONTROL STRUCTURE	EA	4.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	7.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	29.000
	0425- 10-	YARD DRAIN	EA	2.000
	0425-100- 25	SPECIAL DRAINAGE STRUCTURE, TOLL SITE DRY WELL AND ACCESSORIES	EA	4.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	54.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	37,792.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	11,502.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	6,171.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8,281.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	2,143.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	2,822.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	1,547.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	3,791.000
	0430-175-166	PIPE CULVERT, OPT MATERIAL, ROUND, 66"S/CD	LF	69.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	30.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	842.000
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	838.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	682.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	296.000
	0430-185-142	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 42", STORM AND CROSS DRAIN	LF	417.000
	0430-185-148	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 48", STORM AND CROSS DRAIN	LF	368.000
	0430-185-160	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 60" , STORM AND CROSS DRAIN	LF	476.000
	0430-536-300	STRAIGHT CONCRETE ENDWALLS, 36", TRIPLE, 0 DEGREES, ROUND	EA	1.000
	0430-542-100	STRAIGHT CONCRETE ENDWALLS, 42", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	1,546.900
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	39.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	13.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	8.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	13.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	4.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	5.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	3.000
	0430-982-144	MITERED END SECTION, OPTIONAL ROUND, 66" CD	EA	1.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	16.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	4.000
	0431- 1-900	PIPE LINER- SPIN CAST, 10' X 4'	LF	1,229.000
	0431- 1-901	PIPE LINER- SPIN CAST, 6' X 3'	LF	152.000
	0431- 1-902	PIPE LINER- SPIN CAST, 12.5' X 6'	LF	980.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	51.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	353.000
	0515- 2-312	PEDESTRIAN / BICYCLE RAILING, ALUMINUM, 42" TYPE 2	LF	130.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	112.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	9,433.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,766.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	2,669.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0520- 2- 10	CONCRETE CURB, TOLL HEADER CURB	LF	400.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	649.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	42,688.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	280.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	165.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	17,896.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	9,570.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	2,785.000
	0521- 1-122	MEDIAN CONC BARRIER, TOLL SITE, D521-005 CUSTOM SCHEME	LF	277.000
	0521- 6- 31	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	LF	4,393.000
	0521- 6- 32	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED	LF	888.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	9,000.000
	0521- 8- 11	CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL	LF	3,712.000
	0521- 8- 31	CONCRETE BARRIER, WITH SPECIAL JUNCTION SLAB, 32" VERTICAL FACE	LF	1,531.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	3,841.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	2,933.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	3,630.000
	0521- 72- 44	SHOULDER CONCRETE BARRIER, 44" PIER PROTECTION BARRIER/CRASH WALL	LF	160.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	170.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK (43619415201)	SY	4,528.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	403.000
	0527- 2-	DETECTABLE WARNINGS	SF	166.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2,319.300
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	2,542.000
	0530- 74-	BEDDING STONE	TN	965.600
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	573,559.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	35,485.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	612.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	612.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	1,640.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	23.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	13.000
	0536- 73-	GUARDRAIL REMOVAL	LF	56,980.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	17.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	23.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	8.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	9.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	21.214

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	300,651.000
	0548- 13-	RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER	SF	57,998.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	61,499.000
	0550- 10-325	FENCING, TYPE R, 5.1-6.0', VERTICAL	LF	6,004.000
	0550- 60-224	FENCE GATE, TYPE B, DOUBLE, 18.1-20.0' OPENING	EA	5.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	646,705.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	55,511.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	346.000
	0639- 8-144	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), OUC (DO NOT BID) (43619415201)	LS	1.000
	0639- 8-150	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), KISSIMMEE UTILITY AUTHORITY (DO NOT BID) (43619415201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,133.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	48.430
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.986
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	348.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	63.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	539.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	28.306
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.188
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	126.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	43.051
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	214.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.125
	0999- 16-	PARTNERING, DO NOT BID (43619415201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	21.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43619415201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (43619415602)	LS	1.000
	1050- 16-004	UTILITY PIPE, REMOVE & DISPOSE, 8-19.9"	LF	1,534.000
	1050- 18-004	UTILITY PIPE, PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	4.000
<b>Section 0003 Signing</b>				
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	77.000



**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	26.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	7.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	2.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	121.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	8.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	4.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	11.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	30.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	12.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	12.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	15.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-503	SIGN PANEL, RELOCATE, 21-30 SF	EA	4.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 3-608	SIGN PANEL, REMOVE, 301-400 SF	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	6.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	3.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	10.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	59.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,674.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43619415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,283.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,259.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,512.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.703
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	42.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	166.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	397.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.142
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	25.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	23.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	15.151
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.620
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	34.791
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	13.372
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.384
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.093
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.893
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.761
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	879.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.960
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.628
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.639
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.643
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	39,867.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	17,581.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	265.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	310.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	27.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	3.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	5.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	10.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	7,075.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	310,367.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	203,916.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	1,804.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	117,203.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	29.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	4.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	26.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	244.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	3.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	19.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	96.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	238.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	54.000
<b>Section 0005 Signalization</b>				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	234.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,439.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	212.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	3,042.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	168.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	12.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	2.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	2.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	503.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0649- 1- 14	STEEL STRAIN POLE, F&I, TYPE PS- VII	EA	3.000
	0649- 1- 15	STEEL STRAIN POLE, F&I, TYPE PS- VIII	EA	5.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	36.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	11.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	11.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
<b>Section 0006 Landscape / Peripheral</b>				
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	95.000
<b>Section 0007 Utilities</b>				
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9" (43619415602)	LF	4,096.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	1,140.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	306.000
	1050- 18-005	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 20-49.9"	LF	306.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	703.000
	1050- 42-130	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, CASING/CONDUIT, 30"	LF	761.000
	1050- 42-136	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, CASING/CONDUIT, 36"	LF	1,661.000
	1050- 42-214	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 14"	LF	761.000
	1050- 42-218	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 18"	LF	1,661.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	955.000
	1050- 51-216	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 16"	LF	376.000
	1055- 41-414	UTILITY FITTINGS FOR PE PIPE, FURNISH & INSTALL, UNION, 14"	EA	2.000
	1055- 41-418	UTILITY FITTINGS FOR PE PIPE, FURNISH & INSTALL, UNION, 18"	EA	4.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	12.000
	1055- 51-116	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"	EA	18.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	1055- 51-216	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 16"	EA	1.000
	1055- 51-314	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 14"	EA	2.000
	1055- 51-318	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 18"	EA	4.000
	1055- 51-512	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 12"	EA	3.000
	1055- 51-516	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 16"	EA	4.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	3.000
	1080- 23-116	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 16"	EA	4.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	5.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	8.000
	1080- 26-103	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 3"	EA	3.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12"	EA	3.000
	1080- 27-116	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 16"	EA	4.000
<b>Section 0008 Architectural</b>				
	0519- 78-	BOLLARDS	EA	23.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,959.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	732.000
	0635- 2-119	PULL & SPLICE BOX, F&I,TOLL SITE, 12" x 12"	EA	8.000
	0635- 2-120	PULL & SPLICE BOX, F&I,TOLL SITE, 24" x 36"	EA	10.000
	0635- 2-121	PULL & SPLICE BOX, F&I,TOLL SITE, 30" x 48"	EA	30.000
	0639- 5- 2	EMERGENCY GENERATOR-PERMANENT 26-50 KW	EA	4.000
	0639- 7-122	ELECTRICAL POWER SERVICE, TOLL SITE ELECTRIC METERING AND UTILITY SERVICE ENTRANCE	EA	4.000
	0735- 1-113	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, CANTILEVER, 31' TO 40'	EA	1.000
	0735- 1-114	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, CANTILEVER, 41' TO 50'	EA	2.000
	0735- 1-125	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, SPAN, 51' TO 100'	EA	1.000
	0735- 74- 1	TOLL PLAZA, LOCATION 1 (43619415201)	LS	1.000
	0735- 74- 2	TOLL PLAZA, LOCATION 2 (43619415201)	LS	1.000
	0735- 74- 3	TOLL PLAZA, LOCATION 3 (43619415201)	LS	1.000
	0735- 74- 4	TOLL PLAZA, LOCATION 4 (43619415201)	LS	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	1,639.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	53.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	1,125.000
	1080- 21-600	UTILITY FIXTURE, VALVE/METER BOX, REMOVE	EA	3.000
	1501- 1-	LIFT STATION, SANITARY SEWER	EA	2.000
	1720-900-	TRANSFORMER, REMOVE	EA	3.000
<b>Section 0009 Intelligent Transportation System</b>				
	0102-112-	EXISTING ITS MAINTENANCE	DA	2,022.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	5.154
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	17.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	20,693.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	22,260.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	300.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	10,882.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	7,128.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	36,200.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	25,950.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	648.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	432.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	17.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	51.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	34.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	22.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	2,022.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	1,156.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	129.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	69.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	17.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	7.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	15,859.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	29,950.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	35.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	15.000
	0639- 6-131	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 11-15 KVA, SINGLE PHASE, COPPER WINDINGS	EA	7.000
	0639- 6-141	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 16-25 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	22.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	10.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	2.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	14.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	14.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	12.000

**Call Order: 001 Proposal: E8U72**

ALT	Item	Description	Unit	Quantity
	0660- 3- 41	VEHICLE DETECTION SYSTEM- MICROWAVE, RELOCATE CABINET EQUIPMENT	EA	1.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 6-421	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, CABINET EQUIPMENT	EA	1.000
	0660- 6-422	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	1.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	2.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	17.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	3.000
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	1.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	1.000
	0676- 2-600	ITS CABINET- REMOVE	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	12.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	22.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	1.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	18.000
	0684- 2- 4	DEVICE SERVER, RELOCATE	EA	1.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	4.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	23.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	23.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	1.000
	0700- 10-116	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	12.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-141-241	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I BARRIER TOP MOUNT, HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	2.000
	0700-141-441	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I BARRIER SIDE MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	5.000