

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08250408      Call Order: 001      Proposal: E8V60      District:08

Counties: PASCO

Road Name: RESURF/SAF IMP SUNCOAST(SR 589)IN PASCO COUNTY, MP 17.5-28.5

Limits: 14470000

Project(s): 44770215201(\*)      Federal Aid No: N/A

Project(s): 44770225201      Federal Aid No: N/A

Total Roadway Length:	23.099 Miles	Contract Days:	416
Total Bridge Length:	1.227 Miles	Letting Date:	04/08/25
Total Proposal Length:	24.326 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$29,858,339.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for, but not limited to, maintenance of traffic, milling and resurfacing, signing, pavement markings, cross slope correction, bridge expansion joint repair and ITS along SR 589(Suncoast Parkway) from MM 17.500 to MM 28.575 within Pasco County.

No Pre-Bid Conference. Contractor must be prequalified.

**Call Order: 001 Proposal: E8V60**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	56.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	17.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	240.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,307.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	655.800
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44770215201)	LS	1.000
	0101- 1-	MOBILIZATION (44770225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44770215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44770225201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44770215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	7,600.000
	0102- 60-	WORK ZONE SIGN	ED	36,352.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	431,046.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	614.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,506.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,664.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,664.000
	0102-115-	TYPE III BARRICADE	ED	2,330.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,761.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	186.000

**Call Order: 001 Proposal: E8V60**

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	14.000
	0107- 1-	LITTER REMOVAL	AC	5,739.950
	0107- 2-	MOWING	AC	3,849.600
	0110- 1- 1	CLEARING & GRUBBING (44770225201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,198.000
	0120- 1-	REGULAR EXCAVATION	CY	378.700
	0120- 6-	EMBANKMENT	CY	1,378.200
	0160- 4-	TYPE B STABILIZATION	SY	48.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	48.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	26,004.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	10,181.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	197,840.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	95,399.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	25,462.000
	0327- 70- 10	MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH	SY	2,635.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	24,472.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	3,882.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	7,649.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	29,394.000
	0327- 70- 26	MILLING EXISTING ASPHALT PAVEMENT, 4 3/4" AVG DEPTH	SY	16,595.000
	0327- 70- 27	MILLING EXISTING ASPHALT PAVEMENT, 5 3/4" AVG DEPTH	SY	53,448.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	7,069.700
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,589.500
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	26,237.200
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,006.600
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	41,229.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	13,803.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	626.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	751.700
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	52.100
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	2.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-619	INLETS, DITCH BOTTOM, TYPE K, J BOTTOM, MODIFY	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	4.000
	0425- 4-	INLETS, ADJUST	EA	3.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0425- 82-	REPLACE GRATE	EA	3.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	124.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	196.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	119.000
	0430-613-325	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011, 1:2 SLOPE, 18" PIPE	EA	2.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	237.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	4.000

**Call Order: 001 Proposal: E8V60**

ALT	Item	Description	Unit	Quantity
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,564.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	139.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	868.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	30.100
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	10,359.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	9.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	10.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	3.000
	0536- 73-	GUARDRAIL REMOVAL	LF	10,012.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	9.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	17.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	95,248.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	2,311.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,904.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	22.857
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.236
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	181.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	4,391.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	346.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	22.014
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.140
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	40.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	22.555
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,079.000
	0999- 16-	PARTNERING, DO NOT BID (44770215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44770215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44770225201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	39.932
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	62.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	25.000

**Call Order: 001 Proposal: E8V60**

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	11.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	97.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	8.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	7.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	2.000
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	3.000
	0700- 2-118	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 300.1-400.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	21.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-402	SIGN PANEL, INSTALL, 12-20 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,568.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44770215201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	2.236
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	175.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	4,391.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	318.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,079.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	22.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	38.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	22.215
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	21.957
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	22.235
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.601
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.056
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.328
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	1.140
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.140

**Call Order: 001 Proposal: E8V60**

ALT	Item	Description	Unit	Quantity
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.140
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.140
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	9,027.000
<b>Section 0004 Intelligent Transportation System</b>				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	416.000