

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08250408 Call Order: 005 Proposal: E8W05-R0 District:08

Counties: BREVARD, LAKE, ORANGE, OSCEOLA, SEMINOLE, SUMTER, TURNPIKE

Road Name: ROADWAY REHABILITATION - ZONE 3

Limits: Midpoint

Project(s): 19077445235(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	04/08/25
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The work under this Contract consists of providing all labor, materials, equipment, and incidentals necessary to perform routine and priority repairs on roadway asphalt, pavement markings, and other miscellaneous repairs, at various locations along the Florida's Turnpike (SR-91) Milepost (MP) 237.0 to 308.0, Beachline East Expressway MP 0.0 to 35.7, Beachline West Expressway MP 0.9 to 36.9, Seminole Expressway MP 37.7 to 55.1, Southern Connector Extension MP 1.1 to 6.2, and Western Beltway MP 0.9 to 10.9.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

The budgetary ceiling for this contract shall be Five Hundred Thousand Dollars (\$500,000.00) over the 365-day term of the contract.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRACT

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted to be reviewed by the Department.

Call Order: 005 Proposal: E8W05-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	10.000
	0160- 4-	TYPE B STABILIZATION	SY	100.000
	0173- 71-	DRILLING HOLES FOR PRESSURE GROUTING	EA	2.000
	0173- 76-	GROUT PIPE INSTALLATION	LF	100.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	50.000
	0210- 2-	LIMEROCK-NEW MATERIAL FOR REWORKING BASE	CY	1,200.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	25.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	25.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	25.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	25.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	25.000

Call Order: 005 Proposal: E8W05-R0

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	25.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	25.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	25.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	25.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	25.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	100.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	25.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	100.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	25.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	25.000
	0327- 70- 9	MILLING EXISTING ASPHALT PAVEMENT, 5 1/4" AVG DEPTH	SY	25.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	200.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	25.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	25.000
	0327- 70- 14	MILLING EXISTING ASPHALT PAVEMENT, 6 1/2" AVG DEPTH	SY	25.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	25.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	25.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	25.000
	0327- 70- 18	MILLING EXISTING ASPHALT PAVEMENT, 5 1/2" AVG DEPTH	SY	25.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	25.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	25.000
	0327- 70- 21	MILLING EXISTING ASPHALT PAVEMENT, 7" AVG DEPTH	SY	25.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	25.000
	0327- 70- 23	MILLING EXISTING ASPHALT PAVEMENT, 6" AVG DEPTH	SY	25.000
	0327- 70- 26	MILLING EXISTING ASPHALT PAVEMENT, 4 3/4" AVG DEPTH	SY	25.000
	0327- 70- 27	MILLING EXISTING ASPHALT PAVEMENT, 5 3/4" AVG DEPTH	SY	25.000
	0327- 70- 28	MILLING EXISTING ASPHALT PAVEMENT, 6 3/4" AVG DEPTH	SY	25.000
	0327- 70- 29	MILLING EXISTING ASPHALT PAVEMENT, 6 1/4" AVG DEPTH	SY	25.000
	0327- 70- 31	MILLING EXISTING ASPHALT PAVEMENT, 7 1/2" AVG DEPTH	SY	3,400.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	5.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	950.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	125.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	10.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	125.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	25.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	25.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	25.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.500

Call Order: 005 Proposal: E8W05-R0

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	50.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.200
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.100
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.100
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E102- 97- 1	TRUCK MOUNTED ATTENUATOR (TEMPORARY)	ED	5.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	500.000
	E710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	500.000
	E710- 11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	LF	500.000
	E710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	LF	500.000
	E711- 3- 1	PAVEMENT MESSAGES (THERMOPLASTIC)	SF	25.000