

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08250812 Call Order: 003 Proposal: Z8153-R0 District:08  
 Counties: BREVARD, LAKE, ORANGE, OSCEOLA, SEMINOLE, SUMTER, TURNPIKE  
 Road Name: Pre-Event Lighting Repair & Replace -Central Florida  
 Limits: Midpoint  
 Project(s): 45712125201(\*) Federal Aid No: N/A  
 Total Roadway Length: 0.000 Miles Contract Days: 365  
 Total Bridge Length: 0.000 Miles Letting Date: 08/12/25  
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$0.00

Please read the full advertisement

**Description:**

Provide Lighting Repair and Replacement Operations pursuant to a Governor's and/or President's Declaration of a State Emergency. This contract includes Osceola, Orange, Brevard, Seminole, Lake and Sumter counties within District D-8/Florida's Turnpike. Perform Lighting Repair and Replacement Operations pursuant to the terms of this Contract and at the direction of the Department.

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Highway Lighting. The Experience in Highway Lighting Form (850-070-11) must be filled out and submitted with the bid. The form must be signed by the owner of the company or a company officer and dated in the space provided on the form.

1. NO PRE-BID WILL BE HELD FOR THIS CONTRACT.
2. Award is contingent upon legislative budget approval and availability of funds.
3. Awarded Contractor must execute documents within 10 days.
4. General Liability, Auto and Workman's Compensation Insurance required.
5. FHWA 1273/Davis-Bacon Wage Rates
6. The Contractor shall provide a letter to the Department at the time of bid, from a surety authorized to do business in the State of Florida verifying the Contractor is bondable in the State of Florida. For the purposes of this Contract the dollar amount is established at \$500,000.00. The performance bond will be required within five days after commencement of any services.

**Call Order: 003 Proposal: Z8153-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 HIGHWAY LIGHTING MAINTENANCE (MH)</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,000.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,000.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	500.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	5.000
	0635- 2- 50	PULL & SPLICE BOX, REPAIR	EA	5.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0639- 10-	ELECTRICAL POWER SERVICE DIAGNOSTIC AND MISCELLANEOUS REPAIR	EA	5.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,000.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,000.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,000.000
	0715- 1- 16	LIGHTING CONDUCTORS, F&I, NO.4/0 (0000) OR LARGER	LF	500.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	5.000

**Call Order: 003 Proposal: Z8153-R0**

ALT	Item	Description	Unit	Quantity
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 10- 3	LIGHT POLE FOUNDATION, REPAIR	EA	5.000
	0715- 10- 4	LIGHT POLE FOUNDATION, STRAIGHTEN EXISTING FOUNDATION	EA	10.000
	0715- 10- 5	LIGHT POLE FOUNDATION, REMOVE FOUNDATION- NO EXISTING POLE	EA	1.000
	0715- 11-118	LUMINAIRE, F&I, ROADWAY, FLOOD	EA	5.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	5.000
	0715- 11-128	LUMINAIRE, F&I, UNDER DECK, FLOOD	EA	5.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	20.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	20.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	1.000
	0715- 11-400	LUMINAIRE, RELOCATE	EA	1.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	1.000
	0715- 16- 5	LIGHTING - BALLAST, REPLACE	EA	1.000
	0715- 19- 3	LIGHTING - REPLACE EXISTING SURGE PROTECTOR	EA	50.000
	0715- 36- 12	LIGHT POLE, FRANGIBLE BASE, F&I, TRANSFORMER BASE	EA	5.000
	0715- 36- 14	LIGHT POLE, FRANGIBLE BASE, F&I, DOOR ASSEMBLY	EA	50.000
	0715-100- 1	LIGHT POLE COMPLETE- 30' TO 50 STANDARD FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	50.000
	0715-100- 2	LIGHT POLE COMPLETE- 30' TO 50 SPECIAL FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	50.000
	0715-100- 3	LIGHT POLE REPLACE ON EXISTING FOUNDATION- 30' TO 50', PRE-EVENT CONTRACT ONLY	EA	50.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	5.000
	E715- 16- 1	BALLAST (F&I)	EA	10.000
	E715- 16- 2	BALLAST ASSEMBLY (F&I)	AS	1.000
	E715- 17- 1	LAMP (HPS)	EA	40.000
	E715- 17- 2	LAMP (MERCURY VAPOR)	EA	1.000
	E715- 17- 3	LAMP (METAL HALIDE)	EA	1.000
	E715- 17- 5	LAMP (LPS)	EA	1.000
	E715- 17- 9	LAMP (LED)	EA	5.000
	E715- 18-101	LOAD CENTER PART (F&I) (SGL POLE BREAKER)	EA	1.000
	E715- 18-102	LOAD CENTER PART (F&I) (DBL POLE BREAKER)	EA	1.000
	E715- 18-104	LOAD CENTER PART (F&I)(BREAKER PANEL & ENCLOSURE)	EA	1.000
	E715- 18-105	LOAD CENTER PART (F&I) (CONTACTOR)	EA	1.000
	E715- 18-107	LOAD CENTER PART (F&I) (PHOTOCELL)	EA	1.000
	E715- 18-108	LOAD CENTER PART (F&I) (PHOTOCELL SOCKET)	EA	1.000
	E715- 18-110	LOAD CENTER PART (F&I)(SYSTEM SWITCH AUTO-OFF/ON)	EA	1.000
	E715- 18-111	LOAD CENTER PART (F&I) (LIGHTNING ARRESTOR)	EA	1.000
	E715- 18-112	LOAD CENTER PART (F&I) (CIRCUIT FUSE)	EA	1.000
	E715- 18-113	LOAD CENTER PART (F&I) (MAIN FUSE)	EA	1.000
	E715- 18-114	LOAD CENTER PART (F&I) (DUMMY SLUG)	EA	1.000

**Call Order: 003 Proposal: Z8153-R0**

ALT	Item	Description	Unit	Quantity
	E715- 18-115	LOAD CENTER PART(SFTY DIS SWTCH BOX,600V)(F&I)	EA	1.000
	E715- 18-116	LOAD CENTER PART (F&I) (COVER PLATE)	EA	1.000
	E715- 19- 99	LIGHTING - CABLE REMOVAL DETERRENT SYSTEM	EA	1.000
	E715- 22- 1	GROUND ROD	EA	1.000
	E715- 23- 1	REFRACTER (F&I) (STANDARD COBRA HEAD)	EA	1.000
	E715- 24- 1	FUSE (F&I) (POLE BASE)	EA	1.000
	E715- 24- 2	FUSE (F&I) (SIGN)	EA	1.000
	E715- 24- 4	DUMMY SLUG (F&I) (POLE BASE)	EA	1.000
	E715- 25- 1	FUSE HOLDER (F&I) (POLE BASE)	EA	1.000
	E715- 25- 2	FUSE HOLDER / DISCONNECT PLUG (F&I)	EA	1.000
	E715- 25- 41	FUSE HOLDER POLE BASE INSTALL ONLY	EA	1.000
	E715- 26- 4	QUICK DISCONNECT PLUG (MODULAR POLE BASE)	EA	1.000
	E715- 26- 13	SWITCH BOX (INSTALL) (FOR SIGN STRUCTURE)	EA	1.000
	E715- 32- 1	DIAGNOSTIC WORK (SHOULDER SINGLE ARM)	LO	1.000
	E715- 32- 2	DIAGNOSTIC WORK (SHOLDER DOUBLE ARM)	LO	1.000
	E715- 32- 3	DIAGNOSTIC WORK (MED SGL ARM WALL MTD)	LO	1.000
	E715- 32- 4	DIAGNOSTIC WORK (MED DBL ARM WALL MTD)	LO	1.000
	E715- 32- 5	DIAGNOSTIC WORK (BRIDGE MTD)	LO	1.000
	E715- 32- 6	DIAGNOSTIC WORK (UNDERDECK)	LO	1.000
	E715- 32- 7	DIAGNOSTIC WORK (LOAD CENTER)	LO	1.000
	E715- 32- 10	DIAGNOSTIC WORK (CIRCUIT)	LO	1.000
	E715- 32- 13	DIAGNOSTIC WORK (TOP MOUNT)	LO	1.000
	E715- 43- 1	ARRESTOR (HIGH VOLTAGE PRIMARY LIGHTING)	EA	1.000
	E715- 50-220	LIGHTING TRANSFORMER (F&I)(PAD MOUNT)	EA	1.000
	E715-561-101	LIGHT POLE-LEVELING (ALUM/STEEL, CONCRETE FOUNDATION)	EA	1.000