

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08251219	Call Order: 001	Proposal: E8W48	District:08
Counties:	BROWARD			
Road Name:	WIDEN SAWGRASS (SR869) SAMPLE TO UNIVERSITY DR (MP 12-14.8)			
Limits:	86472000			
Project(s):	43546145201(*)	Federal Aid No: N/A		
Total Roadway Length:	5.128 Miles	Contract Days:	1217	
Total Bridge Length:	0.148 Miles	Letting Date:	12/19/25	
Total Proposal Length:	5.276 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$112,998,139.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for the construction of roadway reconstruction, widening, milling and resurfacing, widening of Bridge Nos. 860494 and 860495 over Coral Ridge Drive, widening of Bridge No. 860496 and 860497 over Coral Springs Drive, stormwater enhancements, stormwater ponds, Coral Ridge Drive interchange reconstruction and lighting, signing, pavement marking, traffic signals and Intelligent Transportation System (ITS) improvements on SR 869, Sawgrass Expressway in Broward County from MP 12.007 to MP 14.867.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546145201 BRIDGE ID 860494)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546145201 BRIDGE ID 860495)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546145201 BRIDGE ID 860496)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43546145201 BRIDGE ID 860497)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	782.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	230.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	374.000
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	28.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	3,746.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	19.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	157,944.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	102,822.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	55,470.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,362.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	1,322.000
	0455- 17-118	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 18"	EA	8.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	78.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2,872.000
	0455-115-	PILE REDRIVE	EA	14.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	78.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	8.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	537.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	744.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	96.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	510.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,366.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	2,832.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	24.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43546145201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43546145201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43546145201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43546145201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	15,378.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	81,975.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	13,485.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	33,628.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	28,944.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	4,686.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	60,219.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	31,572.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	134,645.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,300.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	9,825.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	39.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	12,512.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,250.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,250.000
	0102-115-	TYPE III BARRICADE	ED	6,969.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	10,172.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	7,764.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	2.210
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.462
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.894
	0104- 10- 3	SEDIMENT BARRIER	LF	24,267.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	752.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	155.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	6.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	54.000
	0107- 1-	LITTER REMOVAL	AC	5,153.880
	0107- 2-	MOWING	AC	3,896.650
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43546145201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43546145201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43546145201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8,602.000
	0110- 21-	TREE PROTECTION BARRIER	LF	6,619.000
	0120- 1-	REGULAR EXCAVATION	CY	83,773.000
	0120- 4-	SUBSOIL EXCAVATION	CY	44,025.000
	0120- 6-	EMBANKMENT	CY	126,975.000
	0160- 4-	TYPE B STABILIZATION	SY	179,382.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	10,303.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	55,254.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	398.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	12,119.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	10,314.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	76,681.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,258.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	16,005.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	29,072.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	12,238.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	4,632.000
	0327- 70- 9	MILLING EXISTING ASPHALT PAVEMENT, 5 1/4" AVG DEPTH	SY	4,466.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	88,381.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	4,079.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	6,613.500
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,182.200
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	11,715.200
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	327.200
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,949.100
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	13,410.700
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	7,203.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	786.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	3,569.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	553.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1,804.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	1,100.900

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	236.200
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	22,812.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	2.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	3.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	1.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	3.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	5.000
	0425- 1-362	INLETS, CURB, TYPE P-6, >10'	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	1.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	3.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	1.000
	0425- 1-485	INLETS, CURB, TYPE 8, PARTIAL	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	8.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	35.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	4.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	4.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	4.000
	0425- 1-583	INLETS, DT BOT, TYPE H, J BOTTOM <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	9.000
	0425- 1-601	INLETS, DT BOT, TYPE J, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	62.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, <=10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	10.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	22.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	5.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	5.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	4.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	12.000
	0425- 6- 1	METER BOXES, ADJUST	EA	17.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	26.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	9,330.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2,054.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	361.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	554.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	121.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	16.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	8.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	53.000
	0430-175-172	PIPE CULVERT, OPT MATERIAL, ROUND, 72"S/CD	LF	24.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	432.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	1,700.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	1,921.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	966.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-524-400	STRAIGHT CONCRETE ENDWALLS, 24", QUAD, 0 DEGREES, ROUND	EA	2.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-530-200	STRAIGHT CONCRETE ENDWALLS, 30", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-560-100	STRAIGHT CONCRETE ENDWALLS, 60", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-610-025	U-ENDWALL, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	7.000
	0430-610-029	U-ENDWALL, INDEX 261/430-011, 1:6 SLOPE, 24"PIPE	EA	1.000
	0430-611-025	U-ENDWALL, INDEX 261/430-011, BAFFLES, 1:6 SLOPE, 18"PIPE	EA	3.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	2.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	33.000
	0430-611-329	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 24"PIPE	EA	1.000
	0430-612-029	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 24"PIPE	EA	3.000
	0430-612-033	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 30"	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	256.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	8.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	3.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	10.000
	0431- 1-115	PIPE LINER, CURED IN PLACE, 15"	LF	167.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	822.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	815.000
	0431- 1-154	PIPE LINER, CURED IN PLACE, 54"	LF	498.000
	0431- 1-172	PIPE LINER, CURED IN PLACE, 72"	LF	1,683.000
	0432- 3- 1	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 15"	EA	1.000
	0432- 3- 2	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 18"	EA	6.000
	0432- 3- 4	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 24"	EA	7.000
	0451- 70-	PREST SOIL ANCHORS	EA	76.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	8.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	4.000
	0455- 35- 11	STEEL PILING, HP 12 X 74	LF	2,179.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43546145201)	LS	1.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	35.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	15,303.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	860.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	10,239.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	618.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	27.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	1,835.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	1,112.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	109.000
	0521- 72- 41	SHOULDER CONCRETE BARRIER, RETAINING SECTION	LF	67.000
	0521- 72- 44	SHOULDER CONCRETE BARRIER, 44" PIER PROTECTION BARRIER/CRASH WALL	LF	678.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	474.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,526.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	596.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	123.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	408.000
	0527- 2-	DETECTABLE WARNINGS	SF	539.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	21,574.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	12,748.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	53.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	9.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	5.000
	0536- 73-	GUARDRAIL REMOVAL	LF	29,196.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	14.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	13.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	6,088.000
	0550- 60-236	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 24.1-30' OPENING	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	14,564.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	288,764.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	19,202.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	42.435
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	3.537
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,024.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,999.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	4,992.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	36.594
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.122
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	132.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	395.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	30.207
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	70.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.067
	0922-102- 2	SMART WORK ZONE, PORTABLE CHANGEABLE MESSAGE SIGN	ED	18,848.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0922-102- 5	SMART WORK ZONE, VARIABLE SPEED LIMIT SIGN WITH ELECTRONIC SPEED FEEDBACK SIGN	ED	17,156.000
	0922-102- 6	SMART WORK ZONE, VEHICLE DETECTOR	ED	17,558.000
	0922-102- 7	SMART WORK ZONE, CAMERA	ED	12,757.000
	0922-102- 8	SMART WORK ZONE, CENTRAL PROCESSOR	ED	3,386.000
	0922-102- 9	SMART WORK ZONE, LOCATION DEVICE	ED	6,772.000
	0999- 16-	PARTNERING, DO NOT BID (43546145201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	13.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43546145201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	9.442
	0654- 2- 11	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	4.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	102.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	78.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	25.000
	0700- 1-400	SINGLE COLUMN GROUND SIGN ASSEMBLY, INSTALL	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	10.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	118.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	5.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	16.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	7.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	9.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	6.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	1.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	1.000
	0700- 4-111	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, UP TO 20 FT	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	5.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	2.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	6.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	7.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0700- 8-136	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- W/UPS, FULL COLOR, 101-200 SF	EA	1.000
	0700- 8-600	FRONT ACCESS DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	2.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 10-115	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 10-122	DMS SUPPORT STRUCTURE, CANTILEVER, 21-30 FT	EA	1.000
	0700- 10-124	DMS SUPPORT STRUCTURE, CANTILEVER, 41-50 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	8.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	8.000
	0700-142-174	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS AND BEACON, 31-50 SF OF STATIC SIGN PANELS	EA	3.000
	0700-142-274	ENHANCED HWY SIGN ASSEMBLY, SOLAR POWERED, F&I BARRIER TOP MOUNT, W/EDS AND BEACON 31-50 SF OF STATIC PANELS	EA	1.000
	0700-142-314	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I OVERHEAD MOUNT, W/BEACON, 31-50 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	4.000
	0700-142-903	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - OVERHEAD MOUNT	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	16.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	54.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,880.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	541.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	42.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43546115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.882
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,715.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,706.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,636.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.588
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	43.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	159.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	882.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.387

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	275.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	35.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	37.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	4.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.001
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.778
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	17.140
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	6.607
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.477
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.188
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.431
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.153
	0713-103-171	PERMANENT TAPE, WHITE, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.034
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.425
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.153
	0713-103-371	PERMANENT TAPE, BLACK, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.034
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.425
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,492.000
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	10,785.000
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	42,433.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,053.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,929.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	7,149.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	270.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	319.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	24.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	12.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	300.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	129,772.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	190,284.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	300.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	35,528.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	58.000
	0715- 11-300	LUMINAIRE, INSTALL	EA	4.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	16.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	212.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	222.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	212.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	8.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,135.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,060.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	148.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	33.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	16.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	5.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	3.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	4.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	6.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	31.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	32.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	10.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	14.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	34.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	10.000
	0670- 5-300	TRAFFIC CONTROLLER ASSEMBLY, INSTALL	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	13.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	10.000
Section 0006 Intelligent Transportation System				
	0102-112-	EXISTING ITS MAINTENANCE	DA	1,217.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.000
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	17.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	28,530.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,255.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	560.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	12,480.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	32,695.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	33,205.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	848.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	457.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	15.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	63.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	16.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	17.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	1,209.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	69.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	25.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	13.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	24,385.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	28,045.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	17.000
	0639- 6-112	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, ALUMINUM WINDINGS	EA	15.000
	0639- 6-122	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, ALUMINUM WINDINGS	EA	3.000

Call Order: 001 Proposal: E8W48

ALT	Item	Description	Unit	Quantity
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	11.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	8.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	3.000
	0641- 3-180	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 80'	EA	1.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	3.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	2.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	12.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	13.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	12.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	2.000
	0676- 2-600	ITS CABINET- REMOVE	EA	3.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	2.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	6.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	17.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	12.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	17.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	17.000