

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08250213      Call Order: 002      Proposal: E8V61      District:08

Counties: TURNPIKE

Road Name: HPS TO LED LIGHTING CONVERSION TPKWIDE BROWARD/PALM BEACH

Limits: 86470000

Project(s): 45222875201(\*)      Federal Aid No: N/A

Total Roadway Length:	40.354 Miles	Contract Days:	400
Total Bridge Length:	0.000 Miles	Letting Date:	02/13/25
Total Proposal Length:	40.354 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$5,835,264.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for HPS to LED Lighting Conversion on SR 91 (Florida's Turnpike) from MP 54.110 to MP 86.776, Broward and Palm Beach Counties.

No Pre-Bid Conference. Contractor must be prequalified.

**Call Order: 002 Proposal: E8V61**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45222875201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45222875201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,320.000
	0102- 60-	WORK ZONE SIGN	ED	58,526.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	10,596.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	361,996.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,800.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,299.000
	0102-115-	TYPE III BARRICADE	ED	3,232.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,600.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	10,211.000
	0107- 1-	LITTER REMOVAL	AC	184.860
	0107- 2-	MOWING	AC	168.220
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45222875201)	LS	1.000
	0999- 16-	PARTNERING, DO NOT BID (45222875201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45222875201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	6,657.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,307.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	400.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	96.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	20.000

**Call Order: 002 Proposal: E8V61**

ALT	Item	Description	Unit	Quantity
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	10.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	12,131.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	19,021.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	26,603.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	2,139.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	39,417.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	10.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	10.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	132.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	1,114.000
	0715- 61-152	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 15' ARM LENGTH	EA	1.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	4.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	25.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	3.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	33.000
	0715- 69-001	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	6.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	1,147.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	121.000