

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08250117 Call Order: 001 Proposal: E8U72 District:08

Counties: OSCEOLA

Road Name: WIDEN TPK(SR91), PARTIN SETTLEMENT RD TO OSCEOLA PKWY

Limits: 92471000

Project(s): 43619415201(*) Federal Aid No: N/A

Project(s): 43619415602 Federal Aid No: N/A

Total Roadway Length:	20.294 Miles	Contract Days:	2022
Total Bridge Length:	0.430 Miles	Letting Date:	01/17/25
Total Proposal Length:	20.724 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90

Proposal Budget Estimate: \$325,842,207.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for new road construction, new bridge construction, MSE walls, box culverts, add lanes & reconstruct, milling & resurfacing, base work, shoulder treatment, landscaping, drainage improvements, curb & gutter, sidewalk, guardrail, traffic signals, signing/pavement markings, overhead signing, lighting, intelligent transportation systems, toll plaza, utility contracts on SR 91 from just south of Partin Settlement Road (MP 243.572) to just north of Osceola Parkway (MP 248.726) approximately 5.154 miles in Osceola County. No Pre-Bid Conference. Contractor must be prequalified.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE 924229)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 920611)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 920612)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 920613)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 924219)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 924230)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 924231)	LS	1.000
	0121- 70-	FLOWABLE FILL	CY	204.600
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43619415201 BRIDGE ID 924232)	LS	1.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	240.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	3,318.600
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	248.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	1,236.000
	0400- 2- 25	CONCRETE CLASS II, MASS, BRIDGE SUBSTRUCTURE	CY	87.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	503.100
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	1,157.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	9,278.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	8,275.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	14,081.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	6,155.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	97.800
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	57.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	4,419.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	51,551.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	770,628.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	405,815.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	237,180.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,114.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	2,320.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	2,008.000
	0450- 2- 78	PREST BEAMS: FLORIDA-I BEAM 78"	LF	3,334.000
	0451- 70-	PREST SOIL ANCHORS	EA	65.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	1,172.000
	0455- 17-124	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 24"	EA	29.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	268.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2,925.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	21,425.000
	0455-108-112	STEEL CASING FOR FUTURE PILE, 42"	LF	110.000
	0455-115-	PILE REDRIVE	EA	113.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	86,805.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	34,654.000
	0455-133- 10	SOLDIER PILE WALL, TEMPORARY-CRITICAL, STEEL H-PILES WITH TIMBER LAGGING	SF	1,437.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	268.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	29.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	170.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	2,945.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	926.000
	0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	LF	230.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	1,830.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (43619415201 BRIDGE ID 924230)	LS	1.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (43619415201 BRIDGE ID 924231)	LS	1.000
	0460- 2- 20	STRUCT STEEL - NEW/WIDENING, WEATHERING (43619415201 BRIDGE ID 924230)	LS	1.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0460- 2- 20	STRUCT STEEL - NEW/WIDENING, WEATHERING (43619415201 BRIDGE ID 924231)	LS	1.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	80.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	305.000
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	635.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	130.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	5,200.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,841.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	1,439.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	93.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,684.000
	0530- 74-	BEDDING STONE	TN	956.000
	0550- 10-333	FENCING, TYPE R, 6.1-7.0, W/FULL ENCLOSURE	LF	292.000
	0550- 10-353	FENCING, TYPE R, 8.1 - 10.0', WITH FULL ENCLOSURE	LF	2,184.000
	0560- 1-101	COATING NEW STRUCTURAL STEEL- HIGH PERFORMANCE COATING SYSTEM (43519415201 BRIDGE ID 924231)	LS	1.000
	0560- 1-101	COATING NEW STRUCTURAL STEEL- HIGH PERFORMANCE COATING SYSTEM (43619415201 BRIDGE ID 924230)	LS	1.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	16,516.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	212.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43619415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43619415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43619415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43619415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	9,024.000
	0102- 60-	WORK ZONE SIGN	ED	308,071.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	534.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	19,546.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	253,070.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	6,988.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	12,720.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	210,976.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	3,467.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	732,230.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	32,164.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,215.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	75.000
	0102- 94- 1	TEMPORARY GLARE SCREEN, F&I, WALL MATERIAL-CONCRETE	LF	3,980.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	11,649.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	4,044.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	4,044.000
	0102-115-	TYPE III BARRICADE	ED	11,755.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	19,506.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	19,506.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.410
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.354
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	38,595.000
	0104- 10- 3	SEDIMENT BARRIER	LF	68,088.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	3,929.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	15.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	600.000
	0107- 1-	LITTER REMOVAL	AC	14,629.240
	0107- 2-	MOWING	AC	14,629.240
	0110- 1- 1	CLEARING & GRUBBING (43619415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.060
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	170.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	12,334.000
	0110- 23-	TREE REMOVAL	EA	10.000
	0120- 1-	REGULAR EXCAVATION	CY	980,903.000
	0120- 4-	SUBSOIL EXCAVATION	CY	37,465.900
	0120- 6-	EMBANKMENT	CY	1,261,792.600
	0160- 4-	TYPE B STABILIZATION	SY	558,421.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	12,134.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	5,918.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	126,307.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	2,294.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	34,931.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	11,162.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	314,921.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	13,205.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	13,573.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	22,537.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	1,025.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	23,940.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	3,187.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	11,488.500
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,054.700
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	38,746.200
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	375.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,631.200
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	52,464.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	14,222.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	342.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	4,876.600
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	2,508.700

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2,505.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	544.100
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	766.900
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	196.000
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	239.700
	0400- 45- 5	REINFORCED CONCRETE, TOLL SITE EQUIPMENT SLAB, 12" THICK	SY	116.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	29,425.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	170,458.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	58,110.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	18.000
	0425- 1-312	INLETS, CURB TYPE P-1, >10'	EA	4.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	2.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-522	INLETS, DT BOT, TYPE C,>10'	EA	2.000
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	4.000
	0425- 1-524	INLETS, DT BOT, TYPE C, JBOT, >10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	9.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	132.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	7.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	46.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	35.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	4.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	71.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	31.000
	0425- 1-794	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, >10'	EA	3.000
	0425- 1-881	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10'	EA	18.000
	0425- 1-882	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, >10'	EA	3.000
	0425- 1-883	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, J BOT<10'	EA	8.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	63.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	13.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	7.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	4.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	19.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	9.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	8.000
	0425- 2- 75	MANHOLES, J-7, >10' CONTROL STRUCTURE	EA	4.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	8.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	31.000
	0425- 10-	YARD DRAIN	EA	2.000
	0425-100- 25	SPECIAL DRAINAGE STRUCTURE, TOLL SITE DRY WELL AND ACCESSORIES	EA	4.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0430-94- 1	DESILTING PIPE, 0 - 24"	LF	4,061.000
	0430-94- 3	DESILTING PIPE, 37 - 48"	LF	191.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	39.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	36,365.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	11,555.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	6,005.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	6,629.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	2,296.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	1,468.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	2,495.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	3,350.000
	0430-175-166	PIPE CULVERT, OPT MATERIAL, ROUND, 66"S/CD	LF	69.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	16.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	838.000
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	838.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	791.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	289.000
	0430-185-142	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 42", STORM AND CROSS DRAIN	LF	417.000
	0430-185-148	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 48", STORM AND CROSS DRAIN	LF	366.000
	0430-185-154	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 54", STORM AND CROSS DRAIN	LF	69.000
	0430-185-160	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 60" , STORM AND CROSS DRAIN	LF	460.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-300	STRAIGHT CONCRETE ENDWALLS, 36", TRIPLE, 0 DEGREES, ROUND	EA	1.000
	0430-542-100	STRAIGHT CONCRETE ENDWALLS, 42", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	1,246.400
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	577.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	37.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	15.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	9.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	13.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	4.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	4.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	2.000
	0430-982-144	MITERED END SECTION, OPTIONAL ROUND, 66" CD	EA	1.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	16.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	4.000
	0431- 1-900	PIPE LINER- SPIN CAST, 10' X 4'	LF	1,229.000
	0431- 1-901	PIPE LINER- SPIN CAST, 6' X 3'	LF	152.000
	0431- 1-902	PIPE LINER- SPIN CAST, 12.5' X 6'	LF	980.000
	0451- 70-	PREST SOIL ANCHORS	EA	116.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	12.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	6.000
	0455- 35- 11	STEEL PILING, HP 12 X 74	LF	2,044.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	260.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	25.900
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	413.000
	0515- 2-312	PEDESTRIAN / BICYCLE RAILING, ALUMINUM, 42" TYPE 2	LF	414.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	157.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	9,433.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,766.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	2,669.000
	0520- 2- 10	CONCRETE CURB, TOLL HEADER CURB	LF	400.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	649.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	42,688.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	262.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	165.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	17,475.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	9,570.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	2,322.000
	0521- 1-122	MEDIAN CONC BARRIER, TOLL SITE, D521-005 CUSTOM SCHEME	LF	264.000
	0521- 6- 31	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	LF	4,797.000
	0521- 6- 32	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED	LF	888.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	9,547.000
	0521- 8- 11	CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL	LF	3,805.000
	0521- 8- 31	CONCRETE BARRIER, WITH SPECIAL JUNCTION SLAB, 32" VERTICAL FACE	LF	1,531.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	3,881.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	3,571.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	4,538.000
	0521- 72- 44	SHOULDER CONCRETE BARRIER, 44" PIER PROTECTION BARRIER/CRASH WALL	LF	160.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	170.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK (43619415201)	SY	4,725.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	976.000
	0527- 2-	DETECTABLE WARNINGS	SF	166.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2,341.000
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	2,542.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	1,682.000
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	543,674.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	35,652.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	612.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	612.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	1,640.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	41.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	23.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	13.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	56,968.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	17.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	23.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	8.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	9.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	21.214
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	294,910.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	48,467.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	61,525.000
	0550- 10-325	FENCING, TYPE R, 5.1-6.0', VERTICAL	LF	6,540.000
	0550- 60-224	FENCE GATE, TYPE B, DOUBLE, 18.1-20.0' OPENING	EA	5.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	646,705.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	55,979.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	346.000
	0639- 8-144	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), OUC (DO NOT BID) (43619415201)	LS	1.000
	0639- 8-150	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), KISSIMMEE UTILITY AUTHORITY (DO NOT BID) (43619415201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	20,950.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	50.001
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	3.149
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	281.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	222.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	491.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	27.233
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.262
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	113.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	43.436
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	226.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.125
	0904-540- 11	HIGH TENSION CABLE BARRIER SYSTEM - REMOVE	LF	4,122.000
	0999- 16-	PARTNERING, DO NOT BID (43619415201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	21.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43619415201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (43619415602)	LS	1.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	1,534.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	8.000
Section 0003 Signing				
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	77.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	26.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	7.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	2.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	121.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	8.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	4.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	11.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	30.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	12.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	12.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	15.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-503	SIGN PANEL, RELOCATE, 21-30 SF	EA	4.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 3-608	SIGN PANEL, REMOVE, 301-400 SF	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	6.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	3.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	10.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	59.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,674.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43619415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,283.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,259.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,512.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.703
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	42.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	166.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	397.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.142
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	25.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	23.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	15.151
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.620
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	34.791
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	13.372
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.384
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.093
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.893
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.761

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	879.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.960
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.628
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.639
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.643
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	40,648.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	17,581.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	265.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	312.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	27.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	28.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	3.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	5.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	10.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	7,075.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	310,367.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	203,785.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	1,804.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	117,203.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	29.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	4.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	26.000
	0715- 61-211	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 8' ARM LENGTH	EA	17.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	244.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	3.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	19.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	97.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	241.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	51.000
Section 0005 Signalization				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	234.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,439.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	212.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	3,042.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	168.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	12.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	2.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	2.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	503.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0649- 1- 14	STEEL STRAIN POLE, F&I, TYPE PS- VII	EA	3.000
	0649- 1- 15	STEEL STRAIN POLE, F&I, TYPE PS- VIII	EA	5.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	36.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	11.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	11.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
Section 0006 Landscape / Peripheral				
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	95.000
Section 0007 Utilities				
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9" (43619415602)	LF	4,432.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	1,490.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	306.000
	1050- 18-005	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 20-49.9"	LF	306.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	703.000
	1050- 42-130	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, CASING/CONDUIT, 30"	LF	761.000
	1050- 42-136	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, CASING/CONDUIT, 36"	LF	1,661.000
	1050- 42-214	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 14"	LF	761.000
	1050- 42-218	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 18"	LF	1,661.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	955.000
	1050- 51-216	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 16"	LF	376.000
	1055- 41-414	UTILITY FITTINGS FOR PE PIPE, FURNISH & INSTALL, UNION, 14"	EA	2.000
	1055- 41-418	UTILITY FITTINGS FOR PE PIPE, FURNISH & INSTALL, UNION, 18"	EA	4.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	12.000
	1055- 51-116	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"	EA	18.000
	1055- 51-216	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 16"	EA	1.000
	1055- 51-314	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 14"	EA	2.000
	1055- 51-318	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 18"	EA	4.000
	1055- 51-512	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 12"	EA	3.000
	1055- 51-516	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 16"	EA	4.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	3.000
	1080- 23-116	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 16"	EA	4.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	5.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	8.000
	1080- 26-103	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 3"	EA	3.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12"	EA	3.000
	1080- 27-116	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 16"	EA	4.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
Section 0008 Architectural				
	0519- 78-	BOLLARDS	EA	23.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,959.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	732.000
	0635- 2-119	PULL & SPLICE BOX, F&I,TOLL SITE, 12" x 12"	EA	8.000
	0635- 2-120	PULL & SPLICE BOX, F&I,TOLL SITE, 24" x 36"	EA	10.000
	0635- 2-121	PULL & SPLICE BOX, F&I,TOLL SITE, 30" x 48"	EA	32.000
	0639- 5- 2	EMERGENCY GENERATOR-PERMANENT 26-50 KW	EA	4.000
	0639- 7-122	ELECTRICAL POWER SERVICE, TOLL SITE ELECTRIC METERING AND UTILITY SERVICE ENTRANCE	EA	4.000
	0735- 1-113	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, CANTILEVER, 31' TO 40'	EA	1.000
	0735- 1-114	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, CANTILEVER, 41' TO 50'	EA	2.000
	0735- 1-125	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, SPAN, 51' TO 100'	EA	1.000
	0735- 74- 1	TOLL PLAZA, LOCATION 1 (43619415201)	LS	1.000
	0735- 74- 2	TOLL PLAZA, LOCATION 2 (43619415201)	LS	1.000
	0735- 74- 3	TOLL PLAZA, LOCATION 3 (43619415201)	LS	1.000
	0735- 74- 4	TOLL PLAZA, LOCATION 4 (43619415201)	LS	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	1,639.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	53.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	1,125.000
	1080- 21-600	UTILITY FIXTURE, VALVE/METER BOX, REMOVE	EA	3.000
	1501- 1-	LIFT STATION, SANITARY SEWER	EA	2.000
	1720-900-	TRANSFORMER, REMOVE	EA	3.000
Section 0009 Intelligent Transportation System				
	0102-112-	EXISTING ITS MAINTENANCE	DA	2,022.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	5.154
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	17.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	20,693.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	22,260.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	300.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	10,882.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	7,128.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	36,200.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	25,950.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	648.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	432.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	17.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	51.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	34.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	22.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	2,022.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	1,156.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	129.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	69.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	17.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	7.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	15,859.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	29,950.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	35.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	15.000
	0639- 6-131	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 11-15 KVA, SINGLE PHASE, COPPER WINDINGS	EA	7.000
	0639- 6-141	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 16-25 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	22.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	10.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	2.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	14.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	14.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	12.000
	0660- 3- 41	VEHICLE DETECTION SYSTEM- MICROWAVE, RELOCATE CABINET EQUIPMENT	EA	1.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 6-421	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, CABINET EQUIPMENT	EA	1.000
	0660- 6-422	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	1.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	2.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	17.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	3.000

Call Order: 001 Proposal: E8U72

ALT	Item	Description	Unit	Quantity
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	1.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	1.000
	0676- 2-600	ITS CABINET- REMOVE	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	12.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	22.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	1.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	18.000
	0684- 2- 4	DEVICE SERVER, RELOCATE	EA	1.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	4.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	23.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	23.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	1.000
	0700- 10-116	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	12.000
	0700-141-141	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	5.000
	0700-141-241	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I BARRIER TOP MOUNT, HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	2.000
	0700-141-441	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I BARRIER SIDE MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	5.000