

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08251118 Call Order: 002 Proposal: E8W42 District:08

Counties: MIAMI-DADE

Road Name: SNAPPER CREEK SERVICE PLAZA GENERAL IMPROVEMENTS (MP 19)

Limits: 87471254

Project(s): 44262015201(*) Federal Aid No: N/A

Total Roadway Length:	1.403 Miles	Contract Days:	350
Total Bridge Length:	0.000 Miles	Letting Date:	11/18/25
Total Proposal Length:	1.403 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$9,997,040.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for general improvements at Snapper Creek Service Plaza [MP 19] in Miami-Dade County, Florida. The work includes, but is not limited to: asphalt pavement milling and resurfacing, widening, reconstruction, and placement of new asphalt pavement; construction of plain cement concrete pavement in truck parking areas; removal of concrete picnic tables; miscellaneous drainage improvements; guardrail replacement; sidewalk installation and reconstruction; tree protection and removal; and upgrades to lighting, signing and pavement markings.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 002 Proposal: E8W42

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44262015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44262015201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44262015201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44262015201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44262015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	640.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (44262015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,350.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	768.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	3,624.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,500.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	20,930.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,438.000
	0102-115-	TYPE III BARRICADE	ED	200.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.475
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.003
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	18.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.286
	0104- 10- 3	SEDIMENT BARRIER	LF	11,938.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	151.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	245.000

Call Order: 002 Proposal: E8W42

ALT	Item	Description	Unit	Quantity
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	6.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	57.000
	0107- 1-	LITTER REMOVAL	AC	585.590
	0107- 2-	MOWING	AC	585.590
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44262015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44262015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.180
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,700.000
	0110- 21-	TREE PROTECTION BARRIER	LF	1,800.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	31.000
	0110- 23-	TREE REMOVAL	EA	25.000
	0120- 1-	REGULAR EXCAVATION	CY	2,125.700
	0120- 4-	SUBSOIL EXCAVATION	CY	1,544.600
	0120- 6-	EMBANKMENT	CY	2,444.800
	0160- 4-	TYPE B STABILIZATION	SY	15,486.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	13,088.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,427.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	130.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	10,434.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	27,711.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	758.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	70.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	236.400
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	2,283.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	30.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	1,304.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.000
	0350- 3- 9	PLAIN CEMENT CONCRETE PAVEMENT, 10"	SY	12,941.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	3.000
	0425- 1-505	INLETS, DT BOT, TYPE A, PARTIAL	EA	1.000
	0425- 1-555	INLETS, DT BOT, TYPE E, PARTIAL	EA	5.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	8.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	16.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000

Call Order: 002 Proposal: E8W42

ALT	Item	Description	Unit	Quantity
	0431- 1-115	PIPE LINER, CURED IN PLACE, 15"	LF	330.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	130.000
	0431- 1-136	PIPE LINER, CURED IN PLACE, 36"	LF	260.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	2,936.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	131.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,115.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	509.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,813.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	270.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	39.000
	0527- 2-	DETECTABLE WARNINGS	SF	405.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	37.000
	0536- 73-	GUARDRAIL REMOVAL	LF	32.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	13.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,757.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44262015201)	LS	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.651
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.007
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	11.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	114.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.063
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.119
	0999- 16-	PARTNERING, DO NOT BID (44262015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44262015201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	118.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	26.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	146.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	4.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	12.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	30.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	469.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44262015201)	LS	1.000

Call Order: 002 Proposal: E8W42

ALT	Item	Description	Unit	Quantity
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.060
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	487.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	591.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	328.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	33.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	192.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	1,232.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	411.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.474
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.048
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.346
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	650.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9,751.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,953.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	99.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	240.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	55,493.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 19- 63	HIGH MAST LIGHT POLE, DEEP FOUNDATION REMOVAL	EA	5.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	14.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	23.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	46.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	56.000
	0715-516-340	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 40'	EA	11.000
	0715-516-345	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 45'	EA	1.000
	0715-518-340	LIGHT POLE COMPLETE-SPECIAL DESIGN, FURNISH & INSTALL DOUBLE ARM POLE TOP MOUNT, CONCRETE, 40'	EA	7.000

Call Order: 002 Proposal: E8W42

ALT	Item	Description	Unit	Quantity
Section 0004 Landscape / Peripheral				
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	1.000
	0581- 1- 8	RELOCATE TREES AND PALMS, >=14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	1.000