

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08250909 Call Order: 001 Proposal: E8W24 District:08

Counties: OKEECHOBEE

Road Name: Osowou Road Emergency Access Ramp SB TPK ML

Limits: 91470000

Project(s): 45433015201(*) Federal Aid No: N/A

Total Roadway Length:	0.407 Miles	Contract Days:	198
Total Bridge Length:	0.000 Miles	Letting Date:	09/09/25
Total Proposal Length:	0.407 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$1,684,282.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for new construction of an emergency access ramp, shoulder pavement widening, drainage improvements, signing/pavement markings, and ITS improvements along SR 91 (Florida s Turnpike) from MP 184.083 to MP 184.490 in Okeechobee County. No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8W24

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45433015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45433015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	960.000
	0102- 60-	WORK ZONE SIGN	ED	7,932.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	37,620.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	594.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	820.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	396.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	396.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,001.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	83.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	127.240
	0107- 2-	MOWING	AC	119.970
	0110- 1- 1	CLEARING & GRUBBING (45433015201)	LS	1.000
	0110- 23-	TREE REMOVAL	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	152.300
	0120- 6-	EMBANKMENT	CY	2,929.100
	0160- 4-	TYPE B STABILIZATION	SY	2,080.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,664.000
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	22.100
	0430-173-115	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 15", GUTTER DRAIN	LF	51.000
	0430-613-323	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:2 SLOPE,15"PIPE	EA	2.000

Call Order: 001 Proposal: E8W24

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	11.000
	0536- 73-	GUARDRAIL REMOVAL	LF	41.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	203.000
	0550- 60-812	FENCE GATE, EMERGENCY ACCESS GATE SYSTEM, SWING, 20.1'-24.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,746.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	892.000
	0999- 16-	PARTNERING, DO NOT BID (45433015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45433015201)	LS	1.000
Section 0002 Signing				
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	4.000
Section 0003 Intelligent Transportation System				
	0102-112-	EXISTING ITS MAINTENANCE	DA	198.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.407
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,167.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	244.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	75.000
	0630- 3- 1	REPLACE ROUTE MARKER FOR EXISTING CONDUIT	EA	1.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	1,218.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	4.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	24.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	198.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,371.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	1.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	1.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	1.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	1.000

Call Order: 001 Proposal: E8W24

ALT	Item	Description	Unit	Quantity
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000