

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08260410 Call Order: 001 Proposal: E8W43 District:08

Counties: OSCEOLA

Road Name: TRUCK PARKING AT CANOE CREEK SERVICE PLAZA (MP 229)

Limits: 92471000

Project(s): 44387915201(*) Federal Aid No: N/A

Total Roadway Length:	0.590 Miles	Contract Days:	539
Total Bridge Length:	0.000 Miles	Letting Date:	04/10/26
Total Proposal Length:	0.590 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$19,235,777.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for milling & resurfacing, construction of asphalt pavement, base work, drainage improvements, curb and gutters, lighting, ITS, sidewalks, and other incidental construction on Florida's Turnpike (SR 91) at the Canoe Creek Service Plaza (MP 21.422-21.983) in Osceola County.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44387915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44387915201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44387915201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44387915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (44387915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	14,830.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,004.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	261,209.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	8.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	7.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,118.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	539.000
	0102-115-	TYPE III BARRICADE	ED	2,801.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	24.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	24.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,731.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	206.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	186.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	13.000
	0107- 1-	LITTER REMOVAL	AC	876.310
	0107- 2-	MOWING	AC	836.860

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44387915201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44387915201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44387915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	850.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	8.000
	0110- 23-	TREE REMOVAL	EA	355.000
	0120- 1-	REGULAR EXCAVATION	CY	12,594.400
	0120- 4-	SUBSOIL EXCAVATION	CY	5,071.200
	0120- 6-	EMBANKMENT	CY	59,010.700
	0160- 4-	TYPE B STABILIZATION	SY	43,879.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	311.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	34,930.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	6,766.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	500.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	7,571.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	236.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	2,978.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	186.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	391.000
	0327- 70- 23	MILLING EXISTING ASPHALT PAVEMENT, 6" AVG DEPTH	SY	251.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,043.200
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,066.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	590.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	113.400
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	7.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	8.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	6.000
	0425- 1-419	INLETS, CURB, TYPE J-1, MODIFY	EA	1.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	4.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	4.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 2-147	DRAINAGE MANHOLES, CONTROL STRUCTURE, MODIFIED J-7, DIVERSION STRUCTURE	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,898.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	471.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	816.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	704.000
	0430-175-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	8.000

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0432- 3- 1	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 15"	EA	4.000
	0432- 3- 4	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 24"	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	7,050.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	513.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	166.000
	0527- 2-	DETECTABLE WARNINGS	SF	99.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	986.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,081.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	8.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	38,664.000
	0581- 1-282	RELOCATE TREES AND PALMS, OTHER PALMS, 10.0"-18.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	58.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	231.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.944
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	12.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.148
	0751- 2-	ARCHITECTURAL - ELECTRICAL/POWER (44387915201)	LS	1.000
	0751- 5-	ARCHITECTURAL-WATER, SANITARY SEWER/SEWAGE TREATMENT (44387915201)	LS	1.000
	0751- 46- 11	WINDSHIELD WASH STATION, FURNISH & INSTALL, STATION ASSEMBLY	EA	3.000
	0999- 16-	PARTNERING, DO NOT BID (44387915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44387915201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	46.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	12.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	51.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	11.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	7.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	45.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	183.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44387915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	350.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,840.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	440.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.925
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	42.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	1,457.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.945
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.543
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.191
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.964
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	12.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	8,160.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,805.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	91.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	55,881.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	9,597.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	8.000
	0715- 19- 63	HIGH MAST LIGHT POLE, DEEP FOUNDATION REMOVAL	EA	7.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	14.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	24.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	16.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	60.000
	0715-516-330	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 30'	EA	5.000
	0715-516-350	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MNT- CONCRETE, 50'	EA	8.000
Section 0004 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.590
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	10.000

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3,514.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,557.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	295.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	676.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	6,515.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	2,343.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	390.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	6.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	31.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	342.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	10.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	31.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	3.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	2.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	539.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	423.000
	0633- 8- 12	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, COMPOSITE	LF	468.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	41.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	16.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	9,783.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	4,423.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	9.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	8.000
	0639- 6-201	ELECTRICAL POWER SERVICE- TRANSFORMER, REPLACE, <25 KVA, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	2.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	3.000
	0641- 3-700	CONCRETE CCTV POLE, SHALLOW POLE REMOVAL	EA	1.000

Call Order: 001 Proposal: E8W43

ALT	Item	Description	Unit	Quantity
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	2.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 8- 52	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, ADJUST/MODIFY, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 8- 60	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, REMOVE	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	4.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	1.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	2.000
	0676- 2-600	ITS CABINET- REMOVE	EA	2.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	8.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	6.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	6.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	6.000
	0700- 8-500	FRONT ACCESS DYNAMIC MESSAGE SIGN, RELOCATE	EA	1.000
	0700- 10-400	DMS SUPPORT STRUCTURE, RELOCATE	EA	1.000
	0700-141-802	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RELOCATE - GROUND MOUNT	EA	1.000
	0700-141-902	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - GROUND MOUNT	EA	2.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	3.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	6.000