

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08260414 Call Order: 001 Proposal: E8W64 District:08

Counties: HERNANDO

Road Name: RESURF SAFETY SUNCOAST (SR 589) HERNANDO CTY, MP 37.3-44.5

Limits: 08470000

Project(s): 44770115201(*) Federal Aid No: N/A

Project(s): 44770125201 Federal Aid No: N/A

Total Roadway Length:	14.424 Miles	Contract Days:	343
Total Bridge Length:	0.261 Miles	Letting Date:	04/14/26
Total Proposal Length:	14.685 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$17,795,421.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for milling, resurfacing, safety, and design upgrade improvements for the Suncoast Parkway (SR 589) from County Line Road (MP 37.3) to SR 50/Cortez Boulevard (44.5) in Hernando County.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8W64

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	4.400
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	534.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44770115201)	LS	1.000
	0101- 1-	MOBILIZATION (44770125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44770115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44770125201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44770115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	9,622.000
	0102- 60-	WORK ZONE SIGN	ED	16,855.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	30,104.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,896.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	403.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,405.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	686.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	686.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	343.000
	0102-115-	TYPE III BARRICADE	ED	1,419.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	686.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	686.000

Call Order: 001 Proposal: E8W64

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	13,851.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	5,367.740
	0107- 2-	MOWING	AC	5,367.730
	0110- 1- 1	CLEARING & GRUBBING (44770125201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	282.500
	0120- 6-	EMBANKMENT	CY	3,605.700
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	997.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	12,957.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	25,253.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	76,234.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	6,945.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	148,484.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	1,047.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	86,182.000
	0327- 70-111	MILLING EXIST ASPHALT PAVEMENT AND LIMEROCK 11.75"	SY	808.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	8,192.200
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,245.600
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	14,428.300
	0334- 1- 59	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, HIGH POLYMER	TN	20,995.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,454.400
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	5,073.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,764.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	108.600
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	1.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	15.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	1.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	1.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	192.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	15.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	297.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	625.000
	0536- 73-	GUARDRAIL REMOVAL	LF	232.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	5,312.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	20,335.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	41,803.000
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	1,928.000

Call Order: 001 Proposal: E8W64

ALT	Item	Description	Unit	Quantity
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.331
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.486
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	654.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,696.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	718.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	14.865
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	16.196
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	37.000
	0922-334- 6	SUPERPAVE ASPHALTIC CONCRETE, THICK LIFT, TRAFFIC LEVEL E, HIGH POLYMER	TN	155.600
	0999- 16-	PARTNERING, DO NOT BID (44770115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44770115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44770125201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	26.660
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	48.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	24.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	8.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	85.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	6.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	6.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	15.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	5.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,332.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44770115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.066

Call Order: 001 Proposal: E8W64

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	654.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,696.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	101.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	30.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	37.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	617.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	14.985
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.420
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	14.555
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	14.907
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.346
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.310
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.289
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.192
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.172
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.192
	0713-103-341	PERMANENT TAPE, BLACK, 6-10 DOTTED EXTENSION, 6" FOR CONCRETE SURFACES	GM	0.182
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,273.000
Section 0004 Intelligent Transportation System				
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	20.000
	0630- 3- 1	REPLACE ROUTE MARKER FOR EXISTING CONDUIT	EA	49.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	343.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000