Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08261208	Call Order: 001	Proposal: E8X31-R0		District:08
Counties:	BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE				
Road Name:	DRAINAGE MAINTENANCE - ZONE 1 - NORTH - ROUTINE MAINTENANCE				
Limits:	Midpoint				
Project(s):	19276327203(*)		Federal Aid No: N/A		
Total Roadway Length:		0.000 Miles		Contract Days:	365
Total Bridge Length:		0.000 Miles		Letting Date:	12/08/26
Total Proposal Length:		0.000 Miles		Contract Execution Days:	10
				Special Start Date:	N/A
				Aquis/Flexible Start Time:	14
Proposal Budget Estimate:			$472,000.00		

Please read the full advertisement

Description:

The work specified in this Contract consists of providing all labor, materials, equipment, and all incidentals necessary to perform maintenance, repair, and restoration of the drainage systems, pipes, inlets, and storm water management facilities at various locations on Florida's Turnpike mainline (SR 91), from MP 0.0 to MP 297.9, in Miami-Dade, Broward, and Palm Beach Counties.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRACT

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Drainage Repair. Experience in Drainage Repair Form (850-070-05) must be filled out and submitted with the bid to be reviewed by the Department.

PREQUALIFICATION IS NOT REQUIRED.

Call Order: 001 Proposal: E8X31-R0

ALT	Item	Description	Unit	Quantity
Section 0001 BASE REPAIR (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	300.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	100.000
	0120- 1-	REGULAR EXCAVATION	CY	500.000
	0120- 6-	EMBANKMENT	CY	200.000
	0160- 4-	TYPE B STABILIZATION	SY	200.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	12.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	10.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	10.000
	0425- 78-	INLET CAP, PRECAST	EA	5.000
	0425- 82-	REPLACE GRATE	EA	3.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	50.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	50.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	100.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	2.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	50.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	25.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	750.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E103- 3- 1	TEMPORARY WORK STRUCTURE, HYDRAULIC PUMP SERVICES	ED	1.000
	E110- 2-	CLEARING & GRUBBING	AC	2.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	700.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	10.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	10.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	5.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	250.000
	E425- 73- 6	SECURE MANHOLE / INLET LIDS	EA	5.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	3.000
	E425- 73- 8	MANHOLE COVER	EA	2.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	2,181.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	500.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	500.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	500.000
	E431- 1- 11	PIPE LINER, SPRAY APPLICATION, 0-24”	LF	100.000
	E431- 1- 12	PIPE LINER, SPRAY APPLICATION, 25-36”	LF	50.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	400.000
	E575- 1-	SODDING	SY	750.000