

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08260310      Call Order: 001      Proposal: E8W60      District:08

Counties: TURNPIKE

Road Name: HPS TO LED LIGHTING CONVERSION TURNPIKEWIDE - PHASE III

Limits: 71470000

Project(s): 45222835201(\*)

Federal Aid No: N/A

Total Roadway Length:	27.630 Miles	Contract Days:	466
Total Bridge Length:	0.000 Miles	Letting Date:	03/10/26
Total Proposal Length:	27.630 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$6,613,876.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for HPS to LED Lighting Conversion on SR 23 in Duval and Clay Counties from MM 31.842 To MM 45.725. No Pre-Bid Conference.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtml>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/equalopportunity/bdi.shtml>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to: [SmallBusiness@dot.state.fl.us](mailto:SmallBusiness@dot.state.fl.us)

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application. BDI Reference Sheet may be downloaded from CPP Online Ordering from file E8W60OtherDocs.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

**Call Order: 001 Proposal: E8W60**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45222835201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45222835201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	5,060.000
	0102- 60-	WORK ZONE SIGN	ED	84,528.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	476,432.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	3,262.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	4,006.000
	0102-115-	TYPE III BARRICADE	ED	3,884.000

**Call Order: 001 Proposal: E8W60**

ALT	Item	Description	Unit	Quantity
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,864.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,864.000
	0104- 10- 3	SEDIMENT BARRIER	LF	24,767.000
	0107- 1-	LITTER REMOVAL	AC	2,523.600
	0107- 2-	MOWING	AC	2,372.160
	0639- 8-153	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), JACKSONVILLE ELECTRICAL AUTHORITY (DO NOT BID) (45222835201)	LS	1.000
	0999- 16-	PARTNERING, DO NOT BID (45222835201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45222835201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	14,443.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	18,729.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	466.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	160.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	5.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	687.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	490.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	5.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	26,079.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	148,830.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	15,975.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	158,259.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	5.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	157.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	625.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	6.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	30.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	4.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	10.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	10.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	825.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	7.000