

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08260310 Call Order: 002 Proposal: E8W63 District:08

Counties: HILLSBOROUGH

Road Name: RESURFACE AND SAFETY IMPRVMTS SUNCOAST PKWAY (SR589)

Limits: 10470000

Project(s): 45136615201(\*) Federal Aid No: N/A

Project(s): 45136625201 Federal Aid No: N/A

Total Roadway Length:	3.703 Miles	Contract Days:	312
Total Bridge Length:	0.049 Miles	Letting Date:	03/10/26
Total Proposal Length:	3.752 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$10,175,794.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for milling and resurfacing, widening, base work, guardrail, traffic signal loops, pavement markings, highway signing, bridge joint rehabilitation, and other incidental construction on Suncoast Pkwy (SR 589) from MP 14.3 to 17.5 in Hillsborough County.  
No Pre-Bid Conference. Contractor must be prequalified.

**Call Order: 002 Proposal: E8W63**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	168.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (45136615201)	LS	1.000
	0101- 1-	MOBILIZATION (45136625201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45136615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45136625201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45136615201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45136625201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45136625201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,840.000
	0102- 60-	WORK ZONE SIGN	ED	16,576.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,761.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,178.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	450.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	294.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,149.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,248.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,248.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	1,248.000
	0102-115-	TYPE III BARRICADE	ED	190.000

**Call Order: 002 Proposal: E8W63**

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	2,871.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	189.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	147.000
	0107- 1-	LITTER REMOVAL	AC	3,044.500
	0107- 2-	MOWING	AC	2,933.460
	0110- 1- 1	CLEARING & GRUBBING (45136625201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	947.300
	0120- 6-	EMBANKMENT	CY	631.100
	0160- 4-	TYPE B STABILIZATION	SY	3,637.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,778.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,629.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	1,914.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	58,038.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	96,040.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	14,828.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	3,670.000
	0327- 70- 26	MILLING EXISTING ASPHALT PAVEMENT, 4 3/4" AVG DEPTH	SY	3,737.000
	0327- 70-114	MILLING EXIST ASPHALT PAVEMENT AND LIMEROCK 10.75"	SY	3,737.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	450.400
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	7.600
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	371.200
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	4,360.400
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	17.400
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	9,758.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,471.300
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	1,911.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	99.500
	0430-174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	80.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,781.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	27,738.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	675.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,040.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.494
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.185
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	386.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	623.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	7.683

**Call Order: 002 Proposal: E8W63**

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.007
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	42.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.147
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,685.000
	0922-334- 3	SUPERPAVE ASPHALTIC CONCRETE, THICK LIFT, TRAFFIC LEVEL E	TN	1,233.200
	0999- 16-	PARTNERING, DO NOT BID (45136615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45136615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45136625201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	11.245
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	21.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	30.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	10.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	59.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	8.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	2.000
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	11.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	6.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	4.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	6.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	3.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	4.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	216.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,230.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45136625201)	LS	1.000

**Call Order: 002 Proposal: E8W63**

ALT	Item	Description	Unit	Quantity
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.794
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	386.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,025.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	79.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.007
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	42.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	544.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	6.573
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.112
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.827
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	6.826
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.250
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.234
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.559
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.517
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.189
	0713-103-122	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 8" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.073
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.188
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.185
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.184
<b>Section 0004 Lighting</b>				
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (45136625201)	LS	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	699.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	408.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,144.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	4,350.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,902.000
	0715- 62-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	7.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	7.000

Call Order: 002 Proposal: E8W63

ALT	Item	Description	Unit	Quantity
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	7.000
<b>Section 0005 Signalization</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.202
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	53.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	160.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	312.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	6.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	5.000