

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08260522      Call Order: 001      Proposal: E8W44      District:08

Counties: BROWARD

Road Name: WIDEN SAWGRASS(SR869) S OF NW8TH TO SUNRISE BLVD (MP0-0.5)

Limits: 86000371

Project(s): 4371555201(\*)

Federal Aid No: N/A

Total Roadway Length:	5.807 Miles	Contract Days:	1211
Total Bridge Length:	0.156 Miles	Letting Date:	05/22/26
Total Proposal Length:	5.963 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$102,965,440.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for widening a 0.50-mile segment of the Sawgrass Expressway from south of NW 8th Street to Sunrise Boulevard (MP 0.0 – MP 0.5) in Broward County from six to ten travel lanes. Construction includes pavement widening, milling and resurfacing, widening, maintenance of traffic plan, new stormwater treatment facilities, new bridge structures (northbound SR 869), bridge widening (southbound SR 869), signing, pavement marking improvements, lighting, and ITS communications.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

No Pre-Bid Conference. Contractor must be prequalified.

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (4371555201 BRIDGE ID 860514)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (4371555201 BRIDGE ID 860520)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (4371555201 BRIDGE ID 860692)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (4371555201 BRIDGE ID 860693)	LS	1.000
	0110- 12- 1	HYDRODEMOLITION, REMOVAL OF DECK SURFACE	SY	109.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	1,538.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	511.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	388.500
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	661.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	6,144.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	5,954.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	21,405.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	50.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	307,404.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	186,801.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	98,962.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,336.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	514.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	3,770.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	1,319.000
	0455- 15- 15	PREFORMED PILE HOLES, 30" TO 34" DRILL/PUNCH SIZE	LF	2,147.000
	0455- 17-118	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 18"	EA	4.000
	0455- 17-124	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 24"	EA	2.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	99.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2,088.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	4,138.000
	0455-111-	CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION	LF	990.000
	0455-113- 24	AUGER CAST PILE FOR BRIDGES, 24" DIAMETER	LF	990.000
	0455-115-	PILE REDRIVE	EA	7.000
	0455-119-103	LOAD TEST-STATIC, COMPRESSION,101-600 TONS	EA	2.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	10,187.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	99.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	9.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	542.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	490.000
	0455-148-	THERMAL INTEGRITY TESTING FOR AUGER CAST PILES	EA	20.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	624.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	250.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	369.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	145.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,636.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	482.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	3,625.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	26.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43715555201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43715555201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43715555201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43715555201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	12,110.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (43715555201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	91,637.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	24,505.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	36,167.000
	0102- 71-104	TEMPORARY BARRIER, F&I, ANCHORED, TO REMAIN	LF	1,061.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	242,203.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	3,022.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	29.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	5,620.000
	0102-115-	TYPE III BARRICADE	ED	1,600.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	690.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	460.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.561
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.701
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.561
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.350
	0104- 10- 3	SEDIMENT BARRIER	LF	13,293.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	236.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	17.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	109.000
	0107- 1-	LITTER REMOVAL	AC	1,961.420
	0107- 2-	MOWING	AC	1,961.420
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43715555201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43715555201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43715555201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,467.000
	0120- 1-	REGULAR EXCAVATION	CY	100,306.000
	0120- 6-	EMBANKMENT	CY	228,019.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	690.000
	0160- 4-	TYPE B STABILIZATION	SY	132,577.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	14,078.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	26,422.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	17,781.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	49,707.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	136.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	36,439.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	492.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	717.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	4,427.200
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,678.500
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2,158.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	15,566.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,624.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	230.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	420.000
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	2,968.300
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	445,244.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	4.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	2.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	39.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	5.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	2.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	19.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	1.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	6.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0430-173-115	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 15", GUTTER DRAIN	LF	40.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	753.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	56.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	3,488.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	1,279.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	376.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,159.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	107.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	89.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	139.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	14.000
	0430-200- 29	FLARED END SECTION, CONCRETE, 24"	EA	3.000
	0430-200- 41	FLARED END SECTION, CONCRETE, 48"	EA	1.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	2.000
	0430-611-129	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE	EA	1.000
	0430-611-225	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE	EA	5.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	10.000
	0430-613-233	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:3 SLOPE,30"PIPE	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	225.000
	0430-886- 36	MANATEE GRATE FOR 36", UNHINGED	EA	1.000
	0451- 70-	PREST SOIL ANCHORS	EA	599.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	64.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	33.000
	0455- 35- 11	STEEL PILING, HP 12 X 74	LF	448.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	16,556.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	139,251.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	2.400
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	6,182.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	1,335.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	2,237.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	1,090.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	7,978.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	7,282.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	2,247.000
	0524- 2- 29	CONCRETE SLOPE PAVEMENT, 4", REINFORCED	SY	875.000
	0524- 3-	CONC CORE DITCH BLOCKS	CY	34.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	19.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	45.000
	0530- 74-	BEDDING STONE	TN	11.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	6,891.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	46,472.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	6,967.000
	0550- 10-148	FENCING, TYPE A, 7.1-8.0', RESET EXISTING	LF	172.000
	0550- 60-125	FENCE GATE, TYPE A, DOUBLE, 20.1-24.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	98,748.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	20,973.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	84.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	19,410.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.770
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.430
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	20.414
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.766
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	31.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	23.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	10.222
	0999- 16-	PARTNERING, DO NOT BID (4371555201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	14.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (4371555201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	2.380
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	6.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	9.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	1.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	26.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	3.000
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	2.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 3-608	SIGN PANEL, REMOVE, 301-400 SF	EA	1.000
	0700- 3-611	SIGN PANEL, REMOVE, 601 SF AND GREATER	EA	1.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	1.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	2.000
	0700- 4-622	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, SPAN	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,112.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43715555201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.258
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.094
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,687.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,346.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	3.816
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	9.309
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.902
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	3.598
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.245

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.070
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.027
	0713-103-171	PERMANENT TAPE, WHITE, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.032
	0713-103-173	PERMANENT TAPE, WHITE, 3-9 DOTTED, 12" WIDE, FOR CONCRETE SURFACES	GM	0.016
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.393
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.171
	0713-103-371	PERMANENT TAPE, BLACK, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.032
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.388
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	3,982.000
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	22,810.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,253.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	133.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	9,614.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	2,618.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0639- 6-141	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 16-25 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0639- 6-151	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 26-50 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	42,920.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	38,207.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	10,487.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 52- 40	LIGHTING-SPECIAL, LIGHT POLE COMPLETE, F&I, MEDIAN BARRIER MOUNT, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	1.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	2.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	77.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	59.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	80.000
<b>Section 0005 Intelligent Transportation System</b>				
	0102-112-	EXISTING ITS MAINTENANCE	DA	1,211.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	15.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.000
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	5.000
	0611- 2- 3	ITSFM LOCATION DOCUMENTATION- COMMUNICATIONS BUILDING	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	939.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	18,095.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	60.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	987.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	26,615.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	13,109.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	528.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	48.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	6.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	49.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	168.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	13.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	1,211.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	833.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	16.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	11.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	6,872.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	3,665.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	5.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	5.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	2.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	6.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	6.000
	0660- 8- 52	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, ADJUST/MODIFY, ABOVE GROUND EQUIPMENT	EA	6.000

**Call Order: 001 Proposal: E8W44**

ALT	Item	Description	Unit	Quantity
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	3.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	6.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	2.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	3.000