

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08261110	Call Order: 003	Proposal: E8X11	District:08
Counties:	TURNPIKE			
Road Name:	IMPROVEMENTS TO BOX CULVERTS IN ORANGE AND OSCEOLA COUNTIES - DRAINAGE IMPROVEMENTS			
Limits:	75470000			
Project(s):	45208515201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.192 Miles	Contract Days:	305	
Total Bridge Length:	0.009 Miles	Letting Date:	11/10/26	
Total Proposal Length:	0.201 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	
Proposal Budget Estimate:	\$3,682,252.00			

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for culvert repair, including shotcrete, crack injection, and concrete spall repair for Culvert No. 920065 (SR 91 MP 223.7) and Culvert No. 92Q017 (SR 91 MP 222.7) in Osceola County, and Culvert No. Culvert No. 750600 (SR 528 MP 5.4), Culvert No. 75Q002 (SR 528 MP 6.5), and Culvert No. 75Q011 (SR 91 MO 272.2) in Orange County. Work will also consist of roadway improvements.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 003 Proposal: E8X11

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	21.600
	0401- 70- 7	RESTORE SPALLED AREAS, SHOTCRETE	CF	1,944.700
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	42.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	614.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	222.100
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45208515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45208515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	0.000
	0102- 60-	WORK ZONE SIGN	ED	0.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	388.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	0.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	0.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	0.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	0.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	0.000
	0104- 10- 3	SEDIMENT BARRIER	LF	467.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	512.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	498.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000

Call Order: 003 Proposal: E8X11

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	86.380
	0107- 2-	MOWING	AC	65.340
	0110- 1- 1	CLEARING & GRUBBING (45208515201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	13.800
	0120- 6-	EMBANKMENT	CY	15.200
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	398.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	43.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.800
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	11.400
	0401- 70- 7	RESTORE SPALLED AREAS, SHOTCRETE	CF	2,486.900
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	52.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	463.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	109.500
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	31.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	125.000
	0530- 74-	BEDDING STONE	TN	89.800
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	169.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	169.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.083
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	314.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,760.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	0.000
	0999- 16-	PARTNERING, DO NOT BID (45208515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45208515201)	LS	1.000