

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08261027	Call Order: 001	Proposal: E8V46	District:08
Counties:	BROWARD			
Road Name:	WIDEN SAWGRASS(SR869) SUNRISE BLVD TO OAKLAND PARK			
Limits:	86000070			
Project(s):	43715515201(*)	Federal Aid No:	N/A	
Project(s):	43715515602	Federal Aid No:	N/A	
Total Roadway Length:	25.248 Miles	Contract Days:	1730	
Total Bridge Length:	0.312 Miles	Letting Date:	10/27/26	
Total Proposal Length:	25.560 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$248,912,996.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for widening the SR 869 / Sawgrass Expressway from six (6) to future ten (10) lanes under FPID No. 437155-1-52-01 as part of the corridor wide safety and operation improvements. The limits of the project are from Sunrise Boulevard (Blvd.) (MP 0.5) to Oakland Park Blvd. (MP 4.1). The project includes Pavement Widening, Reconstruction, Milling and Resurfacing, and Interchange improvements at Sunrise Blvd/SR 838 (MP 1), Pat Salerno Drive (MP 2.5), and Oakland Park Blvd/SR 816 (MP 3).

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

No Pre-Bid Conference. Contractor must be prequalified.

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43715515201 BRIDGE ID 860482)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43715515201 BRIDGE ID 860483)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43715515201 BRIDGE ID 860484)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43715515201 BRIDGE ID 860485)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43715515201 BRIDGE ID 861019)	LS	1.000
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	121.900
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	1,989.800
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	592.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	442.700
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	848.300
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	1,555.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	7,086.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	7,086.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	11,448.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	80.700
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	132,337.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	426,721.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	457,936.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	112,811.000
	0450- 1-702	PRESTRESSED BEAMS, RECTANGULAR BEAM, 38"W X 30"H	LF	856.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	2,908.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	2,826.000
	0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	2,196.000
	0451- 70-	PREST SOIL ANCHORS	EA	347.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	38.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	21.000
	0455- 15- 11	PREFORMED PILE HOLES, 15" TO 17" DRILL/PUNCH SIZE	LF	5,499.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	216.000
	0455- 15- 15	PREFORMED PILE HOLES, 30" TO 34" DRILL/PUNCH SIZE	LF	3,444.000
	0455- 17-118	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 18"	EA	29.000
	0455- 17-124	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 24"	EA	3.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	235.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	7,192.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	9,166.000
	0455- 35- 11	STEEL PILING, HP 12 X 74	LF	5,499.000
	0455-115-	PILE REDRIVE	EA	34.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	9,121.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	255.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	37.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	747.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	778.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	1,053.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	508.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	422.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	91.100
	0520- 5- 46	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	LF	256.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	3,420.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	605.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	10,260.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	78.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43715515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43715515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43715515201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43715515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,480.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (43715515201)	LS	1.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	283,750.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	5,557.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	73,701.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	13,318.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	6,145.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	100,498.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	688.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	753,200.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	8,496.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	346.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	16,378.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	40,516.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	138.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	26,722.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	7,440.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	7,440.000
	0102-115-	TYPE III BARRICADE	ED	12,630.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	7,956.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	2,652.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.735
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.913
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.655
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.619
	0104- 10- 3	SEDIMENT BARRIER	LF	44,455.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	586.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	455.000
	0107- 1-	LITTER REMOVAL	AC	9,033.000
	0107- 2-	MOWING	AC	8,098.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43715515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43715515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	27,540.000
	0110- 21-	TREE PROTECTION BARRIER	LF	7,021.000
	0110- 23-	TREE REMOVAL	EA	495.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43715515201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	556,121.000
	0120- 4-	SUBSOIL EXCAVATION	CY	182,684.000
	0120- 6-	EMBANKMENT	CY	773,047.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	1,610.000
	0160- 4-	TYPE B STABILIZATION	SY	580,361.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	76,722.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	96,710.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	8,783.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,767.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	1,350.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	142,080.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	3,930.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	231,663.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	3,127.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	900.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	37,062.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	37,074.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	51,980.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	9,921.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	13,076.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	9,994.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,388.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	16,946.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	60,327.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	14,880.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	120.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	1,034.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,507.000
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	3,037.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	859.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	733.300
	0400- 45- 5	REINFORCED CONCRETE, TOLL SITE EQUIPMENT SLAB, 12" THICK	SY	189.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	3,700.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	11.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	2.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	7.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	3.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	1.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	66.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	28.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	5.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	7.000
	0425- 1-553	INLETS, DT BOT, TYPE E, J BOT, <10'	EA	2.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	3.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	16.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	2.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	1.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	1.000
	0425- 1-783	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10'	EA	2.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	31.000
	0425- 1-792	INLETS, MEDIAN BARRIER, TYPE 2, >10'	EA	5.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	11.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	5.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	89.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	10.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	17.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	7.000
	0425- 1-925	INLETS, ADJACENT BARRIER, PARTIAL	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 42	MANHOLES, P-7, >10'	EA	2.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	3.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	18.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	6.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	20.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	211.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	434.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	10,475.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	6,757.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	2,376.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	3,473.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	231.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	919.000
	0430-175-184	PIPE CULVERT, OPT MATERIAL, ROUND, 84"S/CD	LF	198.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	41.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	10.000
	0430-200- 29	FLARED END SECTION, CONCRETE, 24"	EA	2.000
	0430-200- 33	FLARED END SECTION, CONCRETE, 30"	EA	3.000
	0430-200- 38	FLARED END SECTION, CONCRETE, 36"	EA	5.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	8.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-542-100	STRAIGHT CONCRETE ENDWALLS, 42", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-548-100	STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 0 DEGREES, ROUND	EA	3.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0430-584-100	STRAIGHT CONCRETE ENDWALLS, 84", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-610-025	U-ENDWALL, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	5.000
	0430-610-029	U-ENDWALL, INDEX 261/430-011, 1:6 SLOPE, 24"PIPE	EA	7.000
	0430-610-125	U-ENDWALL, INDEX261/430-011, 1:4 SLOPE, 18"PIPE	EA	8.000
	0430-610-129	U-ENDWALL, INDEX 261 / 430-011, 1:4 SLOPE, 24"PIPE	EA	5.000
	0430-610-225	U-ENDWALL, INDEX 261/430-011 1:3 SLOPE, 18"PIPE	EA	3.000
	0430-610-325	U-ENDWALL, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	8.000
	0430-610-329	U-ENDWALL, INDEX 261/430-011,1:2 SLOPE, 24"PIPE	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	62.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	1,778.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	12.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	14.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	6.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	64,731.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	9,777.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	38.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	345.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	3,810.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	11,026.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	1,548.000
	0520- 2- 10	CONCRETE CURB, TOLL HEADER CURB	LF	801.000
	0520- 5- 21	TRAFFIC SEPARATOR - CONCRETE, TYPE II, 4' WIDE	LF	347.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	3,253.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	8,651.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	10,437.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	3,719.000
	0521- 1- 23	MEDIAN CONCRETE BARRIER, TOLL SITE, SCHEME 3	LF	426.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	12,636.000
	0521- 8- 9	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE WITH FRP REINFORCING	LF	114.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	36,086.000
	0521- 72- 41	SHOULDER CONCRETE BARRIER, RETAINING SECTION	LF	2,226.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	122.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	9,388.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	8,563.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	457.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	331.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	7,536.000
	0524- 3-	CONC CORE DITCH BLOCKS	CY	20.000
	0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	232.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	288.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	65.000
	0527- 2-	DETECTABLE WARNINGS	SF	217.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	107.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	479.000
	0530- 74-	BEDDING STONE	TN	249.000
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	132,940.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	615.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	13,719.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	196.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	4.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	14.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	11.000
	0536- 73-	GUARDRAIL REMOVAL	LF	55,506.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	10.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	17.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	1.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	8.000
	0544- 2- 1	CRASH CUSHION, TL-2, NARROW	EA	2.000
	0544- 2- 2	CRASH CUSHION, TL-2, WIDE	EA	1.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	5.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	7.747
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	228,393.000
	0548- 13-	RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER	SF	18,662.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	35,021.000
	0550- 60-225	FENCE GATE , TYPE B, DOUBLE, 20.1-24' OPENING	EA	1.000
	0550- 60-226	FENCE GATE , TYPE B, DOUBLE, 24.1-30.0' OPENING	EA	1.000
	0550- 60-227	FENCE GATE, TYPE B, DOUBLE, GREATER THAN 30' OPENING	EA	1.000
	0550- 60-525	FENCE GATE, TUBULAR METAL PIPE, DOUBLE, 20.1-24.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	509,176.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (43715515201)	LS	1.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	34,656.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	65.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (43715515201)	LS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	55.269
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	7.851
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.042
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,518.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,519.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,646.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	51.070
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	1.666
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.510
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	76.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	318.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	37.492
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	518.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.245
	0999- 16-	PARTNERING, DO NOT BID (43715515201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	32.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43715515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43715515603)	LS	1.000
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	87.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	65.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	3.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	25.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	17.000
	0700- 1-213	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 20.1-30.0 SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	1.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-313	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	7.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	121.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	13.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	10.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	13.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	28.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	17.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	4.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	23.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	16.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	2.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	2.000
	0700- 3-295	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF WITH LIGHTING	EA	2.000
	0700- 3-297	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF WITH LIGHTING	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	12.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	8.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	4.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	2.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	5.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	2.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	4.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	8.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	7.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	8.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	2.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	10.000
	0700- 4-622	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, SPAN	EA	5.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	2.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	2.000
	0700- 10-116	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	2.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	11.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	28.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	17.000
	0700-141-240	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I BARRIER TOP MOUNT, HIGHLIGHTED SIGN <12 SF	EA	9.000
	0700-141-440	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I BARRIER SIDE MOUNT, HIGHLIGHTED SIGN <12 SF	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	8.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,873.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43715515201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.386
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.008
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,086.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	8,231.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,109.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.282
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	55.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	243.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	8,033.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.186
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	24.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.025
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	9.000
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.032
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.032
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	6.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	6.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 14-760	THERMOPLASTIC, PREFORMED, MULTI COLOR, IN PAVEMENT WARNING	EA	3.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	21.479
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	5.747
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	42.040
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	1.060
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	16.778
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.021

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0711- 16-007	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 8"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.161
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.460
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.051
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.645
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.396
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.596
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,451.000
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	1,337.000
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	56,043.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,019.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,871.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	384.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	28.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	385.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	95.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	9.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	5,978.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	239,632.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	214,180.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	64,884.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	24.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	45.000
	0715- 19- 62	HIGH MAST LIGHT POLE, SHALLOW FOUNDATION REMOVAL	EA	2.000
	0715- 52- 40	LIGHTING-SPECIAL, LIGHT POLE COMPLETE, F&I, MEDIAN BARRIER MOUNT, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	5.000
	0715- 52- 41	LIGHTING-SPECIAL, LIGHT POLE COMPLETE, F&I, DOUBLE ARM POLE, MEDIAN BARRIER MOUNT, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	3.000
	0715- 52- 45	LIGHTING-SPECIAL, LIGHT POLE COMPLETE, F&I, DOUBLE ARM POLE, STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	19.000
	0715- 61-200	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 0' ARM LENGTH	EA	11.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	20.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	10.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	257.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	2.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	317.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	325.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	24.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	7,458.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	9,007.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	942.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	7.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	4,380.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	28,816.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	110.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	28.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	17.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	17.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	7.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	235.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	30.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	6.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	4.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	7.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	5,759.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	27.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	14.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	11.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	16.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 4- 6	STEEL MAST ARM ASSEMBLY, FURNISH & INSTALL WITH SPECIAL FOUNDATION	EA	1.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	2.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	3.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	7.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	5.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	5.000
	0649- 21- 26	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 78'-70'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	12.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	97.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	31.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	31.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	4.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	3.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	19.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 2070	AS	4.000
	0670- 5-142	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL, MODEL 2070, 2 PREEMPTION	AS	3.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	6.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	7.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	46.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	16.000
	0715- 5- 32	LUMINAIRE & BRACKET ARM- GALV STEEL, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	11.000
Section 0006 Utilities				
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	750.000
	1050- 51-206	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"	LF	65.000
	1050- 51-208	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 8"	LF	140.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	530.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	1055- 51-108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 8"	EA	4.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	18.000
	1055- 51-212	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 12"	EA	4.000
	1055- 51-308	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 8"	EA	1.000
	1055- 51-508	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 8"	EA	1.000
	1055- 51-512	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 12"	EA	4.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	1.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	20.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8"	EA	1.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	8.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	1.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	1.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	12.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	3.000
	1080- 32-102	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 2"	EA	5.000
	1644-113- 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 6"	EA	1.000
	1644-900-	FIRE HYDRANT, REMOVE	EA	1.000
Section 0007 Architectural				
	0519- 78-	BOLLARDS	EA	120.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	10,290.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,120.000
	0635- 5- 11	TOLL SITE PULL BOX, FURNISH & INSTALL, 12"W X 12"L X 12"D	EA	12.000
	0635- 5- 12	TOLL SITE PULL BOX, FURNISH & INSTALL, 24"W X 36"L X 24"D	EA	12.000
	0635- 5- 13	TOLL SITE PULL BOX, FURNISH & INSTALL, 30"W X 48"L X 24"D	EA	68.000
	0639- 5- 2	EMERGENCY GENERATOR-PERMANENT 26-50 KW	EA	6.000
	0639- 5- 50	EMERGENCY GENERATOR-PERMANENT, REMOVE	EA	3.000
	0639- 7-122	ELECTRICAL POWER SERVICE, TOLL SITE ELECTRIC METERING AND UTILITY SERVICE ENTRANCE	EA	6.000
	0676- 2-810	OUTDOOR COMMUNICATIONS CABINET, FURNISH & INSTALL, TOLL SITE	EA	4.000
	0735- 1-114	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, CANTILEVER, 41' TO 50'	EA	3.000
	0735- 1-125	TOLL GANTRY, NON-ACCESSIBLE, FURNISH AND INSTALL, SPAN, 51' TO 100'	EA	2.000
	0735- 1-126	TOLL GANTRY, FURNISH & INSTALL, NON-ACCESSIBLE, SPAN, 101-150 FT.	EA	1.000
	0735- 74- 1	TOLL PLAZA, LOCATION 1 (43715515201)	LS	1.000
	0735- 74- 2	TOLL PLAZA, LOCATION 2 (43715515201)	LS	1.000
	0735- 74- 3	TOLL PLAZA, LOCATION 3 (43715515201)	LS	1.000
	0735- 74- 4	TOLL PLAZA, LOCATION 4 (43715515201)	LS	1.000
	0735- 74- 5	TOLL PLAZA, LOCATION 5 (43715515201)	LS	1.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0735- 74- 6	TOLL PLAZA, LOCATION 6 (43715515201)	LS	1.000
Section 0008 Intelligent Transportation System				
	0102-112-	EXISTING ITS MAINTENANCE	DA	1,460.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	7.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	324.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.700
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	42.000
	0611- 2- 3	ITSFM LOCATION DOCUMENTATION- COMMUNICATIONS BUILDING	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	6,232.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	49,803.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,159.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	2,112.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	22,057.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	57,204.000
	0633- 1-320	FIBER OPTIC CABLE, INSTALL, UNDERGROUND	LF	48.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	156.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	46,682.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	1,222.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	2,328.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	39.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	254.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	49.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	5.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	1,460.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	274.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	50.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	142.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	43.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	5.000
	0635- 4- 11	FIBER OPTIC SPLICE VAULT, FURNISH & INSTALL, 54"W X 54"L X 48"D	EA	33.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	48,652.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	27,244.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	34.000
	0639- 5- 2	EMERGENCY GENERATOR-PERMANENT 26-50 KW	EA	1.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	25.000
	0639- 6-131	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 11-15 KVA, SINGLE PHASE, COPPER WINDINGS	EA	2.000
	0639- 6-151	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 26-50 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000

Call Order: 001 Proposal: E8V46

ALT	Item	Description	Unit	Quantity
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	19.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	2.000
	0641- 2- 15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	5.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	13.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	3.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	5.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	2.000
	0641- 3-180	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 80'	EA	1.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	2.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	5.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	5.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	7.000
	0660- 8- 11	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	19.000
	0660- 8- 12	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	19.000
	0660- 8- 52	TRAFFIC DATA DETECTION SYSTEM- MICROWAVE, ADJUST/MODIFY, ABOVE GROUND EQUIPMENT	EA	9.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	17.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	7.000
	0676- 2-147	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 332D 66" H x 48" W x 30" D	EA	3.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	4.000
	0677- 1- 11	EQUIPMENT SHELTER, FURNISH & INSTALL, UP TO 120 SF	EA	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	13.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	29.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	2.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	19.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	2.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	28.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	28.000
	0920-688-100	ROAD WEATHER INFORMATION SYSTEM (RWIS)	EA	1.000