

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08260915	Call Order: 007	Proposal: Z8189-R0	District:08
Counties:	BREVARD, LAKE, ORANGE, OSCEOLA, SEMINOLE, SUMTER, TURNPIKE			
Road Name:	TURNPIKE PRE-EVENT LIGHTING REPAIR FOR CENTRAL FLORIDA COUNTIES - EMERGENCY OPERATIONS			
Limits:	Midpoint			
Project(s):	45712125202(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/15/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$0.00			

Please read the full advertisement

Description:

Provide Lighting Repair and Replacement Operations pursuant to a Governor's and/or President's Declaration of a State Emergency. This contract includes Osceola, Orange, Brevard, Seminole, Lake and Sumter Counties within District D-8/Florida's Turnpike. Perform Lighting Repair and Replacement Operations pursuant to the terms of this Contract and at the direction of the Department.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRACT

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Highway Lighting. Experience in Highway Lighting Form (850-070-11) must be filled out and submitted with the bid to be reviewed by the Department.

PREQUALIFICATION IS NOT REQUIRED.

Call Order: 007 Proposal: Z8189-R0

ALT	Item	Description	Unit	Quantity
Section 0001 HIGHWAY LIGHTING MAINTENANCE (MH)				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,000.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	800.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	250.000
	0635- 2- 15	PULL & SPLICE BOX, F&I, 30" X 48" COVER SIZE	EA	5.000
	0635- 2- 50	PULL & SPLICE BOX, REPAIR	EA	5.000
	0639- 10-	ELECTRICAL POWER SERVICE DIAGNOSTIC AND MISCELLANEOUS REPAIR	EA	5.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	500.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	500.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	500.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	1,000.000
	0715- 1- 16	LIGHTING CONDUCTORS, F&I, NO.4/0 (0000) OR LARGER	LF	250.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	5.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 10- 3	LIGHT POLE FOUNDATION, REPAIR	EA	5.000

Call Order: 007 Proposal: Z8189-R0

ALT	Item	Description	Unit	Quantity
	0715- 10- 4	LIGHT POLE FOUNDATION, STRAIGHTEN EXISTING FOUNDATION	EA	10.000
	0715- 11-118	LUMINAIRE, F&I, ROADWAY, FLOOD	EA	5.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	5.000
	0715- 11-128	LUMINAIRE, F&I, UNDER DECK, FLOOD	EA	5.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	10.000
	0715- 11-212	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY HIGH MAST	EA	10.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	10.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	1.000
	0715- 11-237	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, SIGN, SIGN MOUNT	EA	5.000
	0715- 11-400	LUMINAIRE, RELOCATE	EA	1.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	1.000
	0715- 16- 5	LIGHTING - BALLAST, REPLACE	EA	1.000
	0715- 19- 3	LIGHTING - REPLACE EXISTING SURGE PROTECTOR	EA	50.000
	0715- 26- 1	QUICK DISCONNECT PLUG, SWITCH BOXING FOR SIGN	EA	2.000
	0715- 26- 2	QUICK DISCONNECT PLUG, PLUG POLE BASE, HIGH MAST	EA	2.000
	0715- 36- 12	LIGHT POLE, FRANGIBLE BASE, F&I, TRANSFORMER BASE	EA	5.000
	0715- 36- 14	LIGHT POLE, FRANGIBLE BASE, F&I, DOOR ASSEMBLY	EA	50.000
	0715-100- 1	LIGHT POLE COMPLETE- 30' TO 50 STANDARD FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	40.000
	0715-100- 2	LIGHT POLE COMPLETE- 30' TO 50 SPECIAL FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	40.000
	0715-100- 3	LIGHT POLE REPLACE ON EXISTING FOUNDATION- 30' TO 50', PRE-EVENT CONTRACT ONLY	EA	40.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	5.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	5.000
	E715- 15-100	HIGH MAST PARTS (F&I) (IMPOTTED BALLAST ASSEMBLY)	EA	5.000
	E715- 15-110	HIGH MAST PARTS (F&I)(LOWERING CABLE)	EA	5.000
	E715- 15-120	HIGH MAST PARTS (F&I)(POWER CABLE)	EA	5.000
	E715- 15-140	HIGH MAST PARTS (F&I)(LUMINAIRE SUPP. RING)	EA	2.000
	E715- 15-160	HIGH MAST PARTS (F&I)(COMPLETE LOWERING ASSEMBLY)	EA	2.000
	E715- 15-180	HIGH MAST PARTS (F&I) (BALLAST ASSEMBLY)	EA	5.000
	E715- 15-630	HIGH MAST PARTS (REPAIR) (WINCH)	EA	2.000
	E715- 15-640	HIGH MAST PARTS (REPAIR) (LUMINAIRE SUPPORT RING)	EA	2.000
	E715- 16- 1	BALLAST (F&I)	EA	10.000
	E715- 16- 2	BALLAST ASSEMBLY (F&I)	AS	1.000
	E715- 17- 1	LAMP (HPS)	EA	40.000
	E715- 17- 9	LAMP (LED)	EA	5.000
	E715- 18-101	LOAD CENTER PART (F&I) (SGL POLE BREAKER)	EA	1.000
	E715- 18-102	LOAD CENTER PART (F&I) (DBL POLE BREAKER)	EA	1.000
	E715- 18-104	LOAD CENTER PART (F&I)(BREAKER PANEL & ENCLOSURE)	EA	1.000
	E715- 18-105	LOAD CENTER PART (F&I) (CONTACTOR)	EA	1.000

Call Order: 007 Proposal: Z8189-R0

ALT	Item	Description	Unit	Quantity
	E715- 18-107	LOAD CENTER PART (F&I) (PHOTOCELL)	EA	1.000
	E715- 18-108	LOAD CENTER PART (F&I) (PHOTOCELL SOCKET)	EA	1.000
	E715- 18-109	LOAD CENTER PART (F&I) (POWER SAFETY SWITCH)	EA	2.000
	E715- 18-110	LOAD CENTER PART (F&I)(SYSTEM SWITCH AUTO-OFF/ON)	EA	1.000
	E715- 18-111	LOAD CENTER PART (F&I) (LIGHTNING ARRESTOR)	EA	1.000
	E715- 18-112	LOAD CENTER PART (F&I) (CIRCUIT FUSE)	EA	1.000
	E715- 18-113	LOAD CENTER PART (F&I) (MAIN FUSE)	EA	1.000
	E715- 18-115	LOAD CENTER PART(SFTY DIS SWTCH BOX,600V)(F&I)	EA	1.000
	E715- 18-116	LOAD CENTER PART (F&I) (COVER PLATE)	EA	1.000
	E715- 22- 1	GROUND ROD	EA	1.000
	E715- 24- 1	FUSE (F&I) (POLE BASE)	EA	1.000
	E715- 24- 2	FUSE (F&I) (SIGN)	EA	1.000
	E715- 24- 4	DUMMY SLUG (F&I) (POLE BASE)	EA	1.000
	E715- 25- 1	FUSE HOLDER (F&I) (POLE BASE)	EA	1.000
	E715- 25- 2	FUSE HOLDER / DISCONNECT PLUG (F&I)	EA	1.000
	E715- 26- 4	QUICK DISCONNECT PLUG (MODULAR POLE BASE)	EA	1.000
	E715- 26- 13	SWITCH BOX (INSTALL) (FOR SIGN STRUCTURE)	EA	1.000
	E715- 32- 1	DIAGNOSTIC WORK (SHOULDER SINGLE ARM)	LO	10.000
	E715- 32- 2	DIAGNOSTIC WORK (SHOLDER DOUBLE ARM)	LO	1.000
	E715- 32- 3	DIAGNOSTIC WORK (MED SGL ARM WALL MTD)	LO	1.000
	E715- 32- 4	DIAGNOSTIC WORK (MED DBL ARM WALL MTD)	LO	1.000
	E715- 32- 5	DIAGNOSTIC WORK (BRIDGE MTD)	LO	1.000
	E715- 32- 6	DIAGNOSTIC WORK (UNDERDECK)	LO	1.000
	E715- 32- 7	DIAGNOSTIC WORK (LOAD CENTER)	LO	10.000
	E715- 32- 10	DIAGNOSTIC WORK (CIRCUIT)	LO	10.000
	E715- 32- 11	DIAGNOSTIC WORK (HIGH MAST, GROUND)	LO	10.000
	E715- 32- 12	DIAGNOSTIC WORK (HIGH MAST, AERIAL)	LO	5.000
	E715- 32- 13	DIAGNOSTIC WORK (TOP MOUNT)	LO	1.000
	E715- 43- 1	ARRESTOR (HIGH VOLTAGE PRIMARY LIGHTING)	EA	1.000
	E715- 50-220	LIGHTING TRANSFORMER (F&I)(PAD MOUNT)	EA	1.000
	E715-561-101	LIGHT POLE-LEVELING (ALUM/STEEL, CONCRETE FOUNDATION)	EA	1.000