- A. Sidewalk, ramp, and landing slopes (i.e. 0.02, 0.05, and 1:12) shown in this Index are maximums. With approval of the Engineer, provide the minimum feasible slope where the requirements cannot be met.
- B. Landings must have cross-slopes less than or equal to 0.02 in any direction.
- C. Install ramp slopes along a single linear plane (i.e. no warps or varying slope). Ramp slopes are not required to exceed 15 feet in length.
- D. Joints permitted at the location of Slope Breaks. Otherwise locate joints in accordance with Index 522-001. No joints are permitted within the ramp portion of the Curb Ramp.

2. <u>Grade B</u>reaks:

Grade breaks at the top and bottom of ramps must be parallel to each other and perpendicular to the direction of the ramp slope.

3. Curb, Curb and Gutter and/or Sidewalk:

- A. Refer to Index 522-001 for concrete thickness and sidewalk details.
- B. Remove any existing curb or curb and gutter to the nearest joint beyond the curb transition or to the extent that no remaining section of curb or curb and gutter is less than 5 feet long. Remove any existing sidewalk to the nearest joint beyond the transition slope or to the extent that no remaining section of sidewalk is less than 5 feet long.

4. Curb Ramp Alpha-Identification:

- A. Sidewalk curb ramp alpha-identifications (e.g. CR-A) are provided for reference purposes in the Plans.
- B. Alpha-identifications CR-I and CR-J are intentionally omitted.


5. Detectable Warnings:

- A. Install detectable warnings in accordance with Specification 527.
- B. Place detectable warnings across the full width of the ramp or landing, to a minimum depth of 2 feet measured perpendicular to the curb line and no greater than 5 feet from the back of the curb or edge of pavement.
- C. If detectable warnings are shown in the Plans on slopes greater than 5%, align the truncated domes with the centerline of the ramp; otherwise, the truncated domes are not required to be aligned.

6. Detectable Warnings - Acceptance Criteria:

DESCRIPTION:


- A. Color and texture shall be complete and uniform.
- B. 90% of individual truncated domes shall be in accordance with the Americans with Disabilities Act Standards for Transportation Facilities, Section 705.
- C. There shall be no more than 4 non-compliant domes in any one square foot.
- D. Non-compliant domes shall not be adjacent to other non-compliant domes.
- E. Surfaces shall not deviate more than 0.10" from a true plane.



CURB RAMP NOMENCLATURE =

REVISION 11/01/17







11/01/17


FDOT

STANDARD PLANS












* Note: For Additional Information On Sidewalk Curb Construction, See SIDEWALK CURB OPTIONS details.






CONSTRUCTION OF SIDEWALK CURB IN CUT SECTIONS



SIDEWALK CURB OPTIONS



Note: Remove Elevated Pavement By Spading And Rolling, Smooth Milling or Grinding.

SECTION C-C

SIDEWALK CURB RAMPS CR-C AND SIDEWALK CURB


LAST REVISION 11/01/17

DESCRIPTION:

FDOT

SHEET

INDEX



11/01/17


FDOT


STANDARD PLANS


DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS


522-002

4 of 8











LANDINGS FOR CURB RAMPS WITHOUT SIDEWALKS

(See CR-F, CR-G & CR-K Respectively For Detectable Warning Details/Options)





OPTION B

DETECTABLE WARNING ON FLUSH SHOULDER SIDEWALKS =

CURB RAMPS WITHOUT SIDEWALKS AND FLUSH SHOULDER SIDEWALKS

LAST DESCRIPTION:
REVISION II/01/17


FDOT


FY 2018-19 STANDARD PLANS

DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS

522-002

_{SHEET} 6 of 8






= MEDIAN CROSSINGS =

NOTES:

- 1. Cross Slope of the median crossing not to exceed 0.02.
- 2. Running Slopes:
 - A. Slopes ≤ 0.05: For roadway cross sections were the Edge of Pavement elevation is the same for both directions of traffic, the median crossing running slopes (0.02 Typ.) should meet at the centerline of the median. For roadway cross sections with variable Edge of Pavement elevations, or to accommodate other construction in the median, the slopes may intersect off the centerline of the median.
 - B. Slopes > 0.05: Provide a median refuge area (landing, 0.02 slope) for crossings with running slopes > 0.05. The refuge area must extend the full width of the crossing and have a minimum length of 5 feet.
- 3. On existing facilities, remove and reconstruct curb transition for raised sidewalk with ramp.




MEDIAN CROSSING

REVISION 11/01/17

DESCRIPTION:

FDOT

FY 2018-19 STANDARD PLANS



11/01/17

FDOT

STANDARD PLANS

DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS

522-002

8 of 8