



BUTT CONSTRUCTION JOINT




EXPANSION JOINT
(See Note 6)




BUTT CONSTRUCTION JOINT
(Used At Discontinuance Of Work)

NOTES:


1. For joint seal dimensions see Sheet 2.
2. For slabs poured simultaneously, tie bars may be inserted in the plastic concrete by means approved by the Engineer.
3. For Longitudinal Joints:
 - A. Tie bars are deformed #4 or #5 reinforcing steel bars meeting the requirements of Specification 931.
 - B. Provide a standard load transfer tied joint with #4 bars 25" in length at 24" spacing or #5 bars 30" in length at 38" spacing.
4. Transverse joints are to be spaced at a maximum of 15'. Dowels are required at all transverse joints unless otherwise noted in the plans.
5. Expansion joints to be placed at street intersections and other locations as indicated in the Plans. For bridge expansion joints, see Index 370-001.
6. Punch clean holes in preformed joint filler greater than bar diameter.
7. Coat and lubricate plain steel dowel bars in accordance with Specification 350.
8. Sheet metal bottom strips in accordance with Specification 931. Not required with asphalt base.



LANE-TIE JOINT
(See Note 2)



CONTRACTION JOINT
(Vibro Case Method)




CONTRACTION JOINT
(Sawed Method)


===== **LONGITUDINAL JOINTS** =====

===== **TRANSVERSE JOINTS** =====

| DOWELS (LENGTH 18") | |
|----------------------------|----------|
| Pavement Thickness "D" | Diameter |
| 6"-6 1/2" | 3/4" |
| 7"-8" | 1" |
| 8 1/2"-10 1/2" | 1 1/4" |
| ≥11" | 1 1/2" |




METAL



PLASTIC

===== **DOWEL BARS CAPS** =====



===== **DOWEL BAR LAYOUT** =====

10/12/2020 6:39:04 AM

| | |
|---------------------------|--------------|
| LAST REVISION 11/01/19 | DESCRIPTION: |
|---------------------------|--------------|






FY 2021-22
STANDARD PLANS

CONCRETE PAVEMENT JOINTS

INDEX
350-001

SHEET
1 of 4



Note: Dimension w will be shown in the plans or established by the Engineer based on field conditions. Dimension d will be constructed so that the shape factor w/t has a maximum value of 2.0 and a minimum value of 1.0.


FOR NEW PROJECTS
PREFORMED ELASTOMERIC COMPRESSION SEAL

FOR NEW AND REHABILITATION PROJECTS
BACKER ROD BOND BREAKER

FOR REHABILITATION PROJECTS
TAPE BOND BREAKER


CONCRETE-CONCRETE JOINTS

$d = w = 3/4"$ Unless Specified Otherwise In The Plans



BACKER ROD BOND BREAKER

$d = w = 3/4"$ Unless Specified Otherwise In The Plans



TAPE BOND BREAKER

FOR NEW AND REHABILITATION PROJECTS;
 EITHER TAPE OR BACKER ROD BOND BREAKER REQUIRED;
 SHOULDER MUST BE REPAIRED IF PROPER JOINT SHAPE
 CAN NOT BE ATTAINED

CONCRETE-ASPHALT SHOULDER JOINTS

JOINT SEAL DIMENSIONS

**BACKER ROD BOND BREAKER
 (CONCRETE-CONCRETE JOINTS)**


JOINT DIMENSIONS (INCHES)

| JOINT WIDTH | SEALANT BEAD THICKNESS | BACKER ROD DIA. | MINIMUM JOINT DEPTH | BACKER ROD PLACEMENT DEPTH |
|-------------|------------------------|-----------------|---------------------|----------------------------|
| 1/4 | 1/4 | 3/8 | 1 | 1/2 |
| 3/8 | 1/4 | 1/2 | 1 1/4 | 1/2 |
| 1/2 | 1/4 | 5/8 | 1 1/4 | 1/2 |
| 5/8 | 5/16 | 3/4 | 1 1/2 | 9/16 |
| 3/4 | 3/8 | 1 | 1 3/4 | 5/8 |
| 7/8 | 7/16 | 1 1/8 | 1 3/4 | 1 1/16 |
| 1 | 1/2 | 1 1/4 | 2 | 3/4 |
| >1 | 1/2 | 1 1/4+ | 2+ | 3/4 |


Unless otherwise indicated on the plans the joint width for new construction will be 1/4" for construction joints, 3/8" for all other joints.

For rehabilitation projects the joint width will be shown on the plans or established by the Engineer based on field conditions.


10/12/2020 6:39:05 AM




Note: After the concrete has set to the extent that the keyway will retain its shape, the hex bolt and plastic insert shall be removed. The remaining portion of the hook bolt assembly shall be installed immediately prior to placing of concrete in the adjacent lane.




Anchor bolts shall be Grade C in accordance with ASTM A 307.
Threaded sleeves shall develop the full strength of the bolt and meet the material and thread requirements of ASTM A 563.



SECTION AA




TOP VIEW




SECTION BB


CONTRACTION ASSEMBLY



SECTION CC



TOP VIEW




SECTION DD

EXPANSION ASSEMBLY


Note: Proprietary contraction and expansion assemblies may be used. Products shall be introduced to the State Construction Office in accordance with section (C) of the Product Evaluation Procedure.

ALTERNATE KEYWAY AND HOOK BOLT

STEEL HOOK BOLT ASSEMBLY



JOINT LAYOUT AT THRU INTERSECTIONS



JOINT LAYOUT AT 'T' INTERSECTIONS


JOINT ARRANGEMENT

NOTES


1. Longitudinal joints will not be required for single lane pavement 14' or less in width. For entrance and exit ramp joint details, see Sheet 4.
2. Arrangement of longitudinal joints are to be as directed by the Engineer.
3. All manholes, meter boxes and other projections into the pavement shall be boxed-in with 1/2" preformed expansion joint material.

10/12/2020 6:39:07 AM


| | | | | | | | |
|---------------------------|----------|--------------|--|------------------------------|--------------------------|------------------|-----------------|
| LAST REVISION 11/01/18 | REVISION | DESCRIPTION: | | FY 2021-22 STANDARD PLANS | CONCRETE PAVEMENT JOINTS | INDEX 350-001 | SHEET 3 of 4 |
|---------------------------|----------|--------------|--|------------------------------|--------------------------|------------------|-----------------|




2-THRU LANES WITH SINGLE LANE ENTRANCE RAMP




ENTRANCE TAPER WITH AUXILIARY LANE



ENTRANCE RAMP WITH ADDED LANE




EXIT TAPER WITH AUXILIARY LANE



2-THRU LANES WITH SINGLE LANE EXIT RAMP

Note: On single lane ramps, longitudinal joint to be constructed along centerline of ramp.



3-THRU LANES WITH AUXILIARY LANE AND 2-LANE EXIT RAMP

JOINT LAYOUT AT ENTRANCE AND EXIT RAMP TERMINALS

Note: Transverse joint spacing should not exceed 15-ft or twenty-four times the slab thickness, whichever is less. If a lane exceeds 15-ft width, such as single lane ramps and weigh stations, longitudinal joint to be constructed in centerline of lane.

10/12/2020 6:39:09 AM

| | | | | | | |
|---------------------------|----------|--------------|--|--------------------------|------------------|-----------------|
| LAST REVISION 11/01/18 | REVISION | DESCRIPTION: |  FY 2021-22 STANDARD PLANS | CONCRETE PAVEMENT JOINTS | INDEX 350-001 | SHEET 4 of 4 |
|---------------------------|----------|--------------|--|--------------------------|------------------|-----------------|