# Index 700-110 Mounting Exit Number Panels to Signs

## Design Criteria

***AASHTO LRFD Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals (LRFDLTS)***; ***Structures Manual (SM)***, Volume 3, FDOT Modifications to LRFDLTS; ***FDOT Design Manual (FDM)***

## Design Assumptions and Limitations

See notes on ***Index 700-110***.

Coordinate the addition on a sign panel on an existing sign structure with the District Traffic Operations Engineer and District Structures Engineer.

## Plan Content Requirements

See ***FDM 940***.

## Payment

| Item number | Item Description | Unit Measure |
|---|---|---|
| 700-3-1BB | Sign Panel (F&I, Ground Mount) | EA |
| 700-3-2BB | Sign Panel (F&I, Overhead Mount) | EA |

See the ***BOE*** and ***Specification 700*** for additional information on payment, pay item use and compensation.