




PILE PICK-UP DETAILS



STORAGE AND TRANSPORTATION SUPPORT DETAILS

PRESTRESSED CONCRETE PILE NOTES:

1. *Work this Index with the Square Prestressed Concrete Pile Splices (Index 455-102), the Prestressed Concrete Pile Standards (Index 455-112, 455-114, 455-118, 455-124, 455-130, and the Pile Data Table in the Structures Plans.*
2. *Concrete:*
 - A. *Piles: Class V*
 - B. *See "GENERAL NOTES" in the Structures Plans for locations where the use of Highly Reactive Pozzolans is required for options using stainless steel strand and reinforcing.*
3. *Concrete strength at time of prestress transfer:*
 - A. *Piles: 4,000 psi minimum.*
4. *Reinforcing:*
 - A. *Bars:*
 - a. *Stainless Steel: Meet the requirements of Specification Section 931 for Type 304, Grade 75.*
 - b. *Carbon FRP: Meet the requirements of Specification Section 932.*
 - B. *Prestressing Strands:*
 - a. *Stainless Steel: Seven-wire HSSS, Grade 240 strand, meeting the requirements of Specification Section 933.*
 - b. *Carbon FRP: Meet the requirements of Specification Section 933.*
 - c. *All Strand diameters are nominal.*
5. *Spiral Ties:*
 - A. *Tie each wrap of the spiral strand to a minimum of two corner strands.*
 - B. *One full turn required for spiral splices.*
6. *Pile Splices: Fill dowel holes and form the joint between pile sections with a Type AB Epoxy Compound in accordance with Specification Section 926. Use an Epoxy Bonding Compound or an Epoxy Mortar as recommended by the Manufacturer.*

TABLE OF MAXIMUM PILE PICK-UP AND SUPPORT LENGTHS							
	D = Square Pile Size (inches)					Required Storage and Transportation Detail	Pick-Up Detail
	12	14	18	24	30		
Maximum Pile Length (Feet)	48	52	59	68	87	2, 3, or 4 point	1 Point
	69	75	85	98	124	2, 3, or 4 point	2 Point
	99	107	121	140	178	3 or 4 point	3 Point

