

GENERAL NOTES:

1. Meet the requirements of Specification 700.
2. Work with Index 700-010.
3. Shop Drawings: Not required.
4. Construction:

A. Locate Sign Support a minimum of 5 feet from an open joint or transition (sign stationing may be adjusted to accommodate this requirement.

B. Base plate must be flush with back of Traffic Railing

C. Anchors in Traffic Railings:

a. Install Adhesive Anchors in accordance with Specification 416 except perform field test on one anchor per sign support location.

b. Use templates and tie anchors as necessary to maintain correct placement of C-I-P Embedded Anchors

c. Do not drill into existing conduit

D. Temporary Signs on Permanent Traffic Railings: Same as Permanent except Field testing of anchors is not required

5. Removal of Temporary Signs on Permanent Traffic Railings:

A. Cut anchor rods flush with the top of the traffic railing

B. Coat anchors with Type F-1 epoxy to prevent corrosion

a. Extend coating 2 inches beyond edge of cut anchor rods

b. Epoxy coating 1/16" thick minimum

6. Bridge deck shown. Approach slabs, junction slabs, and miscellaneous structures are similar.

7. Traffic railings are shown. Concrete barriers and parapets are similar.

8. Materials:

A. Steel Plate: ASTM A36 or ASTM A709 Grade 36

B. Steel Pipe (Support Post): ASTM A501 Schedule 40

C. Aluminum Pipe: ASTM B429 Alloy 6061-T6

D. Galvanized U-Bolts, Nuts and Plate Washer

a. U-Bolts: ASTM A449

b. Hex Nuts: ASTM A 563 Lock Nuts

c. Plate Washer: ASTM A 36 or ASTM A709 Grade 36 or 50

E. Galvanized Anchor bolts, Nuts and Washers:

a. Anchor Rod: ASTM F1554 Grade 55 fully threaded (for Adhesive Anchors)

b. Anchor Bolts: ASTM F1554 Grade 55 Grade A Hex

c. Nuts: ASTM A563 Heavy Hex Locking

d. Washers: ASTM F436

| SIGN LIMITATIONS TABLE |                                             |
|------------------------|---------------------------------------------|
| MAX. SIGN AREA (SF)    | MAX. SIGN CENTROID HEIGHT (DIM. A + DIM. C) |
| 25                     | 9'-7"                                       |



Dimension A = Distance from centerline of the Support Post to the bottom of the sign or sign cluster.

Dimension C = Vertical distance from the bottom of the sign or sign cluster to the Centroid of the sign or sign cluster.

SIGN SUPPORT ASSEMBLY

9/28/2026 12:11:24 PM

|                              |          |              |                                                                                                                    |                                               |                  |                 |
|------------------------------|----------|--------------|--------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|------------------|-----------------|
| LAST<br>REVISION<br>11/01/22 | REVISION | DESCRIPTION: |  FY 2027-28<br>STANDARD PLANS | SINGLE POST SIGN SUPPORT BARRIER SIDE-MOUNTED | INDEX<br>700-012 | SHEET<br>1 of 3 |
|------------------------------|----------|--------------|--------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|------------------|-----------------|



3. Install 2 heavy hex nuts. Add a washer if required to account for concrete dimension tolerance.

