



District 4 – Major Projects Updates

- Bing Wang, PE, FDOT
- Michael Sileno, PE, H&H
- Brad Salisbury, PE, FDOT
- Robert Bostian, PE, FDOT
- Binod Basnet, PE, FDOT



1





Jupiter US-1 Bridge Replacement Project from CR A1A to CR 707



Bing Wang, PE - FDOT Michael Sileno, PE - H&H



Project Location







3



Δ

Timeline





TRANSPORTATION SYMPOSIUM

5

Jupiter Inlet and Surrounding Area





Outstanding Natural Area

The Inlet

Cultural Resources

TRANSPORTATION SYMPOSIUM

6

Jupiter Lighthouse & Museum










TRANSPORTATION SYMPOSIUM

7

Jupiter Lighthouse & Museum





Design and Construction Considerations

- Protection of Jupiter Inlet Lighthouse & Museum, and Existing Bridge
- New bridge will enhance community cohesion, emergency response, and mobility

TRANSPORTATION SYMPOSIUM





1958 Bridge Facts





US-1 Bridge over the ICWW/Loxahatchee River

- Built in 1958 and NRHP eligible
- Twin double leaf bascule span opens on demand
- Connected bascule piers for each set of leaves
- Two lanes in each direction
- Structurally deficient

TRANSPORTATION SYMPOSIUM

11

Purpose and Need






Lack of facilities for pedestrians and cyclists

Structural deficiencies of the previous bridge built in 1958




12





Final Bridge Rendering





15

Final Rendering





TRANSPORTATION SYMPOSIUM

Accelerate the Construction



Opportunities from the Past

Temporary Channel






TRANSPORTATION SYMPOSIUM

17

Accelerate the Construction








Construction Matters




No room for temporary bridge



Construction Matters



Risk of Using Half of Existing Bridge




21

Hybrid Phased Construction



- Pre-Detour intersection improvements, ITS installation, and construct parts of new bridge
- Detour to Alt A1A Construct half of new bridge superstructure and complete substructure
- Post-Detour Construct remaining half of new bridge superstructure with 2 lanes of traffic and bike/ped facilities

18-month shorter construction relative to fully phased





22

Pre-Detour Improvements




- Intersection improvements along detour route
- Real-time information from ITS
- Streamlined real-time monitoring by PBC traffic management operators and signal timing engineers







23





Current Construction





- 5 span bridge, including twin double leaf trunnion bascule
- 2 lanes, 8ft sidewalks, 8 ft shoulders/bike lanes with solid deck
- 38 ft vertical clearance
- 125 ft horizontal clearance
- Reduce openings by 44%
- 5% profile no permanent impacts to adjacent properties


TRANSPORTATION SYMPOSIUM

Control House



Multi-level control house with enhanced visibility of channel, sidewalks, and roadway






TRANSPORTATION SYMPOSIUM

27

27

Operating Machinery





TRANSPORTATION SYMPOSIUM

28



Operating Machinery







Above Deck Lock Bar








TRANSPORTATION SYMPOSIUM


31

31


Community Engagement - Construction jupiter ibridge The state of the




J.


























90%



October 30, 2025
Final Acceptance Completion Date

TRANSPORTATION SYMPOSIUM

44

Acknowledgements

















Our subconsultant partners

















TRANSPORTATION SYMPOSIUM

45





SR A1A Resiliency Project

Brad Salisbury, P.E. - FDOT



District Four Resiliency

Tidal Flooding on SR A1A in Hollywood



TRANSPORTATION SYMPOSIUM

47

Partners in Improving Resiliency













TRANSPORTATION SYMPOSIUM

Accelerated Timeline

- FY21 A1A Corridor Study
- FY21- Pilot Project Programming
- FY22 Design
- FY25 Construction
- Estimated 3 Years of Construction



49

Corridor Study

Existing Conditions Report

- Field Observations
- Seawalls
- Low Road Elevations
- Potential Overflow Locations
- Storm Sewer Systems

- Outfalls
- Contributing Areas
- · Land Use
- Create Model of System



TRANSPORTATION SYMPOSIUM

Field Observations





October 2020 King Tide Flooding

October 2019 King Tide Flooding

TRANSPORTATION SYMPOSIUM

51

Seawalls







TRANSPORTATION SYMPOSIUM

Hydrological Modeling

Using:

- LIDAR Data
- CADD Files
- ICPR4 Modeling




TRANSPORTATION SYMPOSIUM

53

Alternatives Report


- Review of existing backflow prevention devices
- Proposed remedies:
 - · Prevention
 - · Raise low seawalls
 - · Construct new seawalls where none exist
 - Attenuation
 - · Repair or replace backflow preventers
 - · Repair or replace leaking structures
 - · Pump stations to remove tidal flows
 - Restoration
 - · Raise/reconstruct low side streets
 - · Raise/reconstruct SR-A1A



TRANSPORTATION SYMPOSIUM

Accommodating Future Expansion with Today's Design






TRANSPORTATION SYMPOSIUM

55

Project Programming

- Mid Term Improvements
 - Seawall Installation to 5' NAVD within FDOT Right-of-Way (Broward County 2050 Ordinance)
 - Pipe Lining and Replacement of Drainage Structures
 - Pump Station Installation at 4 High Priority Drainage Basins
- Funding Partnerships for Design and Construction of the Pump Stations with Broward County and the City of Hollywood
- · Continued coordination between agencies



TRANSPORTATION SYMPOSIUM

Design Process

Date	Milestone
August 2022	Notice to Proceed
November 2022	Value Engineering Workshop
November 2022	Final Survey Received
December 2022	City of Hollywood Board Meeting
December 2022	Conceptual Drainage Report (Alternatives Analysis)
February 2023	Initial Engineering (30%)
June 2023	Permit Submittals – USACE, SFWMD
July 2023	Constructability (60%)
October 2023	Public Meeting
December 2023	Biddability (90%)
June 2024	Production (S&S)
September 2024	Letting

 Complex design performed on an accelerated schedule tied to local, state, federal funding and other resilience grants.

TRANSPORTATION SYMPOSIUM

57

Design Development


- Stormwater Model (ICPR4) development:
 - · Refine existing conditions using design survey
 - Add pump station model inputs
 - Model multiple tailwater alternatives -Design High Water, King Tides, Surge Tide
 - Propose storm drain hydraulic upgrades to maximize pump stations' effectiveness
 - · Model new seawalls as overland weirs
 - Consideration of construction funding, cost/benefit of larger pump stations
 - Present alternatives analysis to District 4
 Drainage Office for review and approval



From "Proposed Minimum Seawall Height Policy" – Broward County Environmental Planning and Community Resilience Division


> TRANSPORTATION SYMPOSIUM

Design Typicals



59

Design Typicals (cont.)



Typical Detail - Bulkhead Wall

TRANSPORTATION SYMPOSIUM

Design Challenges

- Develop Construction Plans with consideration of:
 - · 3 Projects, 2 Consultants, 6 Total FPIDs
 - · 6+ Disciplines
 - · 6+ Funding Sources
 - · Cost/Benefit Analysis
 - · Limited ROW
 - Maintenance Agreements
 - · Existing FDOT infrastructure
 - Major utility infrastructure on a barrier island
 - (3) Technical Special Provisions, (1) Modified Special Provision, (4) New Pay Items
 - · U.S. Army Corps of Engineers, South Florida Water Management District Permits
 - · Fulfill short-term purpose and need, with long-term vision in mind

TRANSPORTATION SYMPOSIUM

61




Project Location and Regional Connectivity



63

Project Location and Regional Connectivity



64

Future SW 10th St Connector Lanes / Local SW 10th St – Looking West



TRANSPORTATION SYMPOSIUM

G.E.

65

Existing SW 10th Street at Powerline Road



TRANSPORTATION SYMPOSIUM

66

Future SW 10th Street Connector Lanes elevated over Powerline Road



TRANSPORTATION SYMPOSIUM

67

67

Existing SW 10th Street over I-95



TRANSPORTATION SYMPOSIUM

68

Future SW 10th Street over I-95 with Direct Connector Ramps



TRANSPORTATION SYMPOSIUM

69

69

Existing SW 10th Street Looking East – East of Florida's Turnpike



TRANSPORTATION SYMPOSIUM

70

Future SW 10th Street Connector Lanes Decision Point – Looking East leaving Sawgrass Expressway



TRANSPORTATION SYMPOSIUM

71

71


Phased Design-Build Benefits

- Design, phasing and construction of combined projects managed by one designbuild team – reduces cost, claim and schedule risks
- Minimizes disruption to stakeholders and traveling public by reducing construction duration



TRANSPORTATION SYMPOSIUM

72



Planning Phase - Deliverables due 270 days after NTP

- Project Management Plan
- Quality Management Plan
- Construction Phasing Plan
- Master Schedule
- Initial Risk Register
- Opinion of Probable Cost (OPCC)
- Planning Phase Preliminary Plans of Project
 - Pre-30% Roadway, Drainage, Structures, etc.
 - 90% TSM&O Plans (Smart Work Zone) for Early Works Implementation
- · Technical memorandums
- PD&E Re-evaluation(s) and SIMR Re-evaluation, if required

TRANSPORTATION SYMPOSIUM

74

Preconstruction Phase - Summary of Scope

- Update and Maintain Planning Phase Documents
- Prepare the following:
 - · Community Awareness Plan
 - Safety Plan / Hurricane Preparedness Plan
 - Subcontractor Plan
 - Designs to 90% (some low-risk packages may be bid at 60%, pending FDOT agreement)
- · Prepare Governmental Approvals and permits
- · Continue conducting weekly design meetings


- Continue conducting Risk and opportunity / innovation workshops
- Maintain Project Risk Register and Risk Mitigation
- Develop OPCC at 60% and 90%
- Solicit Bids and Select Subcontractors
- Develop GMPs and Work Package Proposals

TRANSPORTATION SYMPOSIUM

75

75

Work Package Example



TRANSPORTATION SYMPOSIUM

76

Early Construction Builds – Smart Roads

Transportation Systems Management and Operations Smart Work Zone

Objective is to support safety and mobility within the vicinity of the SW 10th Street Connector and Local SW 10th Street roadway, and regional arterial traffic operations during and after construction.



CONGESTION AHEAD ON SW 10TH ST USE SAMPLE ROAD

Smart Work Zones Will be Built-Out With Technology to:

Help Motorists Make Informed Decisions on the Most Efficient Route Through and Around the Work Zone

Advise of Potential Congestion and Major Construction Activities in Advance

TRANSPORTATION SYMPOSIUM

77

77

Anticipated Project Timeline

- Advertised for Phased Design-Build Contract: February 2024
- Contract Execution (Planning Phase): March 2025
- Begin Construction (Early Works): 2026
- End Construction / Final Acceptance: Approximately 2032

SW 10TH STREET CONNECTOR PROJECT TIMELINE

Procurement Feb. 2024 - Fall 2024 Planning Phase Fall 2024 - Mid 2025 Preconstruction Phase 2024 - 2029

Construction Phase 2025 - 2031

TRANSPORTATION SYMPOSIUM

78

SW 10th Street Connector Project Website



www.sw10street.com

TRANSPORTATION SYMPOSIUM

70

79



Project Overview

Improve System Linkage on South Florida Rail Corridor (SFRC)

Complete double tracking of SFRC, only single-track section left on the 72-mile of Tri-Rail System

Meet Commuter + Freight Demand on SFRC in Miami-Dade County

• SFRTA Tri-Rail: 50 trains per day on weekdays 30 trains per day on weekends

• CSX: 6 to 8 freight trains daily

Improve Travel Time and Schedule Adherence



TRANSPORTATION SYMPOSIUM

81

81

Project Location

- Existing Tri-Rail Miami Airport Station @ MICC
- Existing bascule bridge/Proposed fixed bridge
- Hialeah Market Station
- Homestead Spur

- Downtown Spur
- Existing Metrorail crossing
- Existing SR 112 bridge crossing
- SFWMD Control Structure

From just north of Tri-Rail Hialeah Market Station (MP 1035.96) to just north of Tri-Rail Miami Airport Station (MP 1037.21)



82

Existing Condition



TRACK CORRIDOR

- Single mainline track from North of NW 46th Street/ SE 8th Street to north of the new NW 28th Street
- Right-of way width varies from 50-ft to 100-ft
- Land use is primarily industrial
- Seven at-grade railroad/roadway crossings
 - NW 25th Street
 - NW 28th Street
 - Old NW 28th Street
 - NW South River Drive
 - NW North River Drive
 - NW 36th Street
 - NW 46th Street/SE 8th Street
- Two spurs
 - Downtown Lead
 - Homestead Subdivision
- Sidings

TRANSPORTATION SYMPOSIUM

3

83

Proposed Improvements

PROPOSED RAILROAD TRACKS

Addition of a second mainline track for adding capacity to SFRC

Existing Single Track





TRANSPORTATION SYMPOSIUM

84


Proposed Improvements

PROPOSED TWIN BRIDGES OVER MIAMI RIVER









Both bridges have same dimensions

TRANSPORTATION SYMPOSIUM

85

Proposed Improvements

CONSTRUCT A 400-FT CENTER PLATFORM AT HIALEAH MARKET STATION

- Center Platform with single continuous canopy
- Reconfigured site for new bus parking, bicycle racks and storage units, trash receptacles, seating, and ticketing
- Near historic Hialeah Seaboard Air Line Railway Station building
- Tri-Rail Station blue canopy (i.e., Pompano Beach Station) distinct from the NRHP-listed Hialeah Seaboard Air Line Railway Station
- Requires temporary closure of station (approx. 6-8 weeks)













Proposed Improvements

UPGRADE RAILROAD SIGNALS, POSITIVE TRAIN CONTROL, AND CROSSINGS







TRANSPORTATION SYMPOSIUM

87

Act of Congress

DEAUTHORIZATION OF NAVIGATIONAL RIGHTS

- Deauthorization of navigation rights of Federal Project canal approved in December 2020 by U.S. Congress under Water Resources Development Act (WRDA).
- Defined the Miami River Canal as non-navigable from the existing bridge to the upstream SFWMD S-26 salinity barrier and flood control structure.

(A)

The Miami River Canal provision was approved via the Consolidated Appropriations Act, 2021 (12/21/2020) and is contained in Section 325 (page 3852) of the Water Resources Development Act of 2020 (page 3608): https://www.govinfo.gov/content/pkg/BILLS-116hr133eah/pdf/BILLS-116hr133eah.pdf

- 3 SEC. 325, MIAMI RIVER, FLORIDA
- The portion of the project for navigation, Miami River, Florida, authorized by the Act of July 3, 1930 (46 Stat. 925; 59 Stat. 16; 74 Stat. 481; 100 Stat. 4257), beginning at the existing railroad bascule bridge and extending ap
- proximately 1,000 linear feet upstream to an existing salin ity barrier and flood control structure, is no longer author 10 ized beginning on the date of enactment of this Act.



Existing Bascule Bridge



FIGURE 1 MR-MICCI PROJECT LOCATION MAP

Project timeline

SCHEDULE AND COST

Anticipated Construction Start:

Summer 2026

Anticipated Construction End:

Spring 2029

Estimated Construction Cost:

\$84 Million





TRANSPORTATION SYMPOSIUM

90

89

Partners

STAKEHOLDERS













US Army Corps of Engineers.







DESIGN CONSULTANT PARTNERS













PREMIERE



TRANSPORTATION SYMPOSIUM

٩n

Safety Message

secureyourload.com

"Secure Your Load as if everyone you love is driving in the car behind you"

Visit:

DID YOU KNOW:

- A 20 lb. object at 55 mph has a force of 1,000 lbs. at impact!
- Unsecured loads are responsible for up to 40% of the litter on our roads costing us billions of dollars each year.
- National GA report states unsecured loads cause 440 deaths, 10,000 injuries, and 51,000 incidents.

TO SECURE THE LOAD IN YOUR VEHICLE OR TRAILER:

- Tie it down with rope, netting, or straps.
- Tie large objects directly to your vehicle or trailer.
- Consider covering the entire load with a sturdy tarp
- Don't overload your vehicle or trailer.
- Always double-check your load to make sure it's secure.
- Don't forget that animals should also be properly secured.

BEFORE YOU DRIVE, ASK YOURSELF THESE QUESTIONS:

- Is there any chance of debris or cargo falling or blowing out of my vehicle?
- Is my load secured at the back, sides and top?
- What would happen to my load if I had to brake suddenly,
- Would I want my loaded vehicle driving through my neighborhood?
- Would I feel safe if I were driving behind my vehicle?
- Is "Secure Your Load" on my company's safety checklist?

TRANSPORTATION SYMPOSIUM

91

Contact Us





Bing Wang, P.E. FDOT D4-Consultant Management 3400 West Commercial Boulevard Fort Lauderdale, Florida 33309 Telephone: (954) 777-4406



Michael Sileno, P.E. 3250 West Commercial Boulevard, Ste 348 Fort Lauderdale, Florida 33309 Telephone: (954) 495-0566



Robert E. Bostian Jr., P.E. FDOT D4-Consultant Management 3400 West Commercial Boulevard Fort Lauderdale, Florida 33309 Telephone: (954) 777-4427



Binod Basnet, P.E. FDOT D4-Consultant Management 3400 West Commercial Boulevard Fort Lauderdale, Florida 33309 Telephone: (954) 777-4146



Brad Salisbury, P.E. Design Project Manager FDOT D4- In House Design 3400 West Commercial Blvd. Fort Lauderdale, Florida 33309 Telephone: (954) 777-4160

TRANSPORTATION SYMPOSIUM

