

SECTION 512 CONTROL HOUSE

512-1 Description.

Construct a complete bridge control house.

512-2 Materials and Construction Methods.

Meet the material and construction requirements specified in the Contract Documents for the various items which constitute the control house.

512-3 Method of Measurement.

The quantity to be paid for will be at the Contract lump sum price, completed and accepted.

512-4 Basis of Payment.

512-4.1 General. Price and payment will be full compensation for all work specified in this Section, including special windows and doors; plumbing fixtures; and all materials, equipment, tools, labor, and incidentals necessary for the control house. Anchor bolts and steel framing and plates will be paid for as specified in Section 460.

512-4.2 Sashes and Doors on Machinery Rooms: Where the plans include sashes and doors on machinery rooms that are constructed as integral parts of the piers for movable bridges, the sashes and doors will be included in the Contract lump sum price for Control House.

512-4.3 Water Supply: Where the plans require connection of plumbing fixtures to an existing water supply, or the provision of a water supply and connecting the plumbing fixtures thereto, the water supply and connections will be included in the Contract lump sum price for Control House.

512-4.4 Payment Items: Payment will be made under:

Item No. 512- 1-	Control House - lump sum.
Item No. 2512- 1-	Control House - lump sum.